

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐OTHER ☐SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Lomax Exploration Company

3. ADDRESS OF OPERATOR

P.O. Box 4503, Houston, TX 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface

1982' FNL & 1978' FWL SE/NW

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

13 miles South of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

1978

16. NO. OF ACRES IN LEASE

320

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1340

19. PROPOSED DEPTH

6000

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5678' GR

22. APPROX. DATE WORK WILL START*

April, 1983

23.

PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT |
|--------------|----------------|-----------------|---------------|--------------------|
| 12 1/4 | 8 5/8 | 24 | 300 | To Surface |
| 7 7/8 | 5 1/2 | 17 | TD | As Needed |

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 3-2-83
BY: *[Signature]*

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program if any.

24.

SIGNED

G. L. Pruitt

TITLE V.P. DRILLING & PRODUCTION

DATE 2/22/83

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

TITLE


DATE

CONDITIONS OF APPROVAL, IF ANY:

T 8 S , R 16 E , S.L.B. & M.

PROJECT
LOMAX EXPLORATION CO.

Well location, **WEST MONUMENT**
FED. # 6-33, located as shown in
the SE 1/4 NW 1/4 Section 33, T8S,
R 16 E, S.L.B. & M. Duchesne County,
Utah.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

Lawrence E. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO 3137
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P.O. BOX Q - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

| | |
|------------------------------|------------------------|
| SCALE 1" = 1000' | DATE 2/16/83 |
| PARTY R.K. D.B. J.K. S.B. | REFERENCES GLO Plat |
| WEATHER Cold | FILE LOMAX |

X = Section Corners Located

TEN POINT WELL PROGRAM

LOMAX EXPLORATION COMPANY
Federal #6-33
SE/NW Section 33, T8S, R16E
Duchesne County, Utah

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

| | |
|-------------|--------|
| Uinta | 0-3120 |
| Green River | 3120 |
| Wasatch | 6160 |

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

| | |
|-------------|---|
| Green River | 3120 |
| H zone | 3460 - Sand and Shale - possible oil and gas shows |
| J zone | 4360 - Sand and Shale - oil and gas shows anticipated |
| M zone | 5660 - Sand and Shale - primary objective oil |

4. PROPOSED CASING PROGRAM:

8 5/8", J-55, 24#; set at 300'
5 1/2", J-55, 17#, STC; set at TD
All casing will be new

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operators minimum specifications for pressure control equipment are as follows:

A 10" Series 900 Hydril Bag type BOP and a 10" Double Ram Hydraulic unit with a closing unit will be utilized. Pressure tests of BOP's to 1000# will be made prior to drilling surface plug and operation will be checked daily. (See exhibit A)

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

It is proposed that the hole be drilled with fresh water to the "J" zone and with mud thereafter. The mud system will be a water based gel-chemical, weighted to 10.0 ppg as necessary for gas control.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. TESTING, LOGGING AND CORING PROGRAMS:

No coring or drill stem testing has been scheduled for this well. The logging will consist of a Dual Induction Laterolog and a Compensated Neutron-Formation Density.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

It is not anticipated that abnormal pressures or temperatures will be encountered; nor that any other abnormal hazards such as H₂S gas will be encountered in this area.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

It is anticipated that operations will commence approximately April, 1983.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY(Other instructions on
reverse side)OIL & GAS OPERATIONS
RECEIVED

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

SALT LAKE CITY, UTAH

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐

OTHER

SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Lomax Exploration Company

3. ADDRESS OF OPERATOR

P.O. Box 4503, Houston, TX 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

1982' FNL & 1978' FWL

SE/NW

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

13 miles South of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line, if any)

1978

16. NO. OF ACRES IN LEASE

320

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1340

19. PROPOSED DEPTH

6000

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5678' GR

22. APPROX. DATE WORK WILL START*

April, 1983

23. PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT |
|--------------|----------------|-----------------|---------------|----------------------|
| 12 1/4 | 8 5/8 | 24 | 300 | To Surface |
| 7 7/8 | 5 1/2 | 17 | TD | As Needed TO PROTECT |

OIL SHALE & FRESH
WATER

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED G. L. Pruitt TITLE V.P. DRILLING & PRODUCTION DATE 2/22/83

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

E. W. Guynn
District Oil & Gas Supervisor

DATE

APR 14 1983

CONDITIONS OF APPROVAL, IF ANY:

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

NOTICE OF APPROVAL

FLARING OR VENTING OF
GAS IS SUBJECT TO NTL 4-A
DATED 1/1/80

Lomax Exploration Company
Well No. 6-33
Section 33, T. 8 S., R. 16 E.
Duchesne County, Utah
Lease U-34173

Supplemental Stipulations

- 1) The maximum width of access roads will be 30 feet total disturbed area. Turnouts will not be required and traveling off the right-of-way will not be allowed.
- 2) Topsoil will be stockpiled as addressed in the applicants 13 point plan. It is recommended the top 6-10 inches of topsoil material be stockpiled.
- 3) The BLM will be notified at least 24 hours prior to any rehabilitation.
- 4) A burn pit will not be constructed. There will be no burying of garbage or trash at the location. No trash will be thrown in the reserve pit. All trash must be contained and hauled to the nearest sanitary landfill.
- 5) All permanent (on site for six (6) months duration or longer) structures constructed or installed, including the pumpjack, shall be painted a flat, non-reflective, earth tone color to match Tnemec 23-08351 Mesa Brown Enduraton or an approved equal. All facilities shall be painted within 6 months of when the production facilities are put in place. Facilities that are required to comply with O.S.H.A. (Occupational Safety and Health Act) standards are excluded.
- 6) Reserve pits will be fenced with a wire mesh fence topped with at least one strand of barbed wire.
- 7) Adequate and sufficient electric/radioactive logs will be run to locate and identify the prime oil shale horizons in the Mahogany Zone of the Green River formation. Casing and cementing programs will be adjusted to eliminate any potential influence of the well bore or productive hydrocarbon zones on the oil shale resource. Surface casing program may require adjustment for protection of fresh water aquifers. (See attached tentative casing and cementing program for the Uinta Basin.)



United States Department of the Interior

GEOLOGICAL SURVEY
Conservation Division
2000 Administration Building
1745 West 1700 South
Salt Lake City, Utah 84104

February 2, 1981

General Outline for the Protection and Isolation of Ground Water and Oil Shale in the Uinta Basin.

The oil shale occurs with varying thicknesses in most parts of the Uinta Basin and at varying depths. Ground water also occurs at varied depths above and below the Oil Shale. These ground waters have varying degrees of salinity. Nonetheless, drilling for hydrocarbon in the Uinta Basin should provide for the protection of the oil shale and the ground water if either is present.

The protection of the oil shale and the ground water can effectively be carried on through the design of an adequate casing and cementing program for each well drilled in the area.

In the Uinta Basin, water occurs mainly in the Uinta and the Green River formations. As drilling for hydrocarbon gets deeper into the crust of the earth, more ground water might be encountered and will be protected as it is encountered.

This notice's purpose is to attempt to lay the groundwork for a casing program and cementing program that will protect the oil shale and the ground water if present.

These programs are to be considered as guidelines. The specificity of casing depth, amount of cement and the depth of staging collars will be considered on an individual basis after a careful study of the logs of each individual well. Cementing from the bottom up is an economical solution if carefully conducted.

The casing and cementing program presented here as an example, will assume that fresh water was encountered in the upper parts of the Green River, that the oil shale occurs in the middle of the Green River (1000 foot section) and that some ground water is encountered in the lower parts of the Green River.

In this case, three areas will have to be cemented to assure the integrity of the ground water and oil shale. These areas are above the upper fresh water, across the oil shale and below the lower water aquifer. Deep aquifers that do not contain useful water are cemented to prevent water zone influence on production.

The following casing and cementing program will be appropriate for this example:

- A. Surface casing is set at approximately 300 feet and cemented to the surface.

- B. The next casing string will be set at approximately 300 feet below the lowest aquifer. Cementing will be done in three stages, using two stage collars and cement baskets or equivalent as described below and on attached sketches:
1. Cement first stage through the casing shoe to fill annulus back to base of lower aquifer.
 2. Place 1st stage collar (with cement basket immediately below) at a selected point at the base of the oil shale. Cement will have to reach top of oil shale.
 3. Place 2nd stage collar (with cement basket immediately below) 50 feet above the top of the Bird's Nest aquifer and cement to at least 300 feet above the stage collar.
- C. The above is an example. Reasonable equivalents that accomplish these same protective measures, (such as cementing the water zones instead of isolating them), depending on the individual cases will be considered for approval.
- D. When the above mentioned well is to be abandoned, inner-casing plugs will have to be placed at the same depth as the above mentioned annulus cement jobs.

The use of cement bond logs will verify the authenticity of the cement job performed.

- E. The Operator of such well should notify U.S.G.S. 48 hours prior to commencement of casing and cementing activity, so a technician could be dispatched to witness the operations to verify compliance with casing and cementing program.

Attached Sketches:

1. Schematic of the required casing and cementing program.
2. Cross section of the Uinta Basin.
3. Schematic of the general ground water protection program.

E. W. Guynn
District Oil and Gas Supervisor

AMR/kr





Figure 5.- View east of cross section of Uinta Basin showing stratigraphy and intertonguing of Tertiary rocks. Ute Tribal-1 (in section) is located about 8 miles southeast of the application area .

PARTIAL CASING & CEMENTING PROGRAM FOR WELLS IN
NATURAL BUTTES FIELD. HINTAH COUNTY, UTAH



LOMAX EXPLORATION

13 Point Surface Use Plan

For

Well Location

West Monument Federal #6-33

Located In

Section. 33, T8S, R16E, S.L.B. & M.

Duchesne County, Utah

LOMAX EXPLORATION

West Monument Federal #6-33
Section 33, T8S, R16E, S.L.B. & M.

1. EXISTING ROADS

See attached Topographic Map "A".

To reach LOMAX EXPLORATION well location site West Monument Federal #6-33, located in the SE 1/4 NW 1/4 Section 33, T8S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed Westerly out of Myton, Utah along U.S. Highway 40 - 1.5 miles + to the junction of this Highway and Utah State Highway 53; proceed Southerly along Utah State Highway 53 - 9.5 miles to its junction with an existing dirt road to the Northeast; proceed Northeasterly along this road 1.4 miles to its junction with the proposed access road to be discussed in Item #2.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to a point 1.5 miles south on Highway 53; thereafter the road is constructed with existing materials and gravels. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing areas they are located in, and range from clays to a sandy-clay shale material.

The roads that are required for access during the drilling phase, completion phase, and production phase of this well will be maintained at the standards required by the B.L.M. or other controlling agencies. This maintenance will consist of some minor grader work for smoothing of road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

The planned road leaves the existing road described in Item #1 in the SE 1/4 NW 1/4 Section 33, T8S, R16E, S.L.B. & M., and proceeds in a Southeasterly direction approximately 300' to the proposed location site.

The proposed access road will be an 18" crown road (9' either side of the centerline) with drain ditches along either side of the proposed road where it is determined necessary in order to handle any run-off from normal meterological conditions that are prevalent to this area.

Back slopes along the cut areas of the road will be 1 1/2 to 1 slopes and terraced.

There will be no culverts required along this access road, as it crosses no drainage of any consequence.

There will be no turnouts required along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattlegaurds required.

The lands involved in this action are under B.L.M. jurisdiction.

The terrain that is traversed by this road is relatively flat. The grade of this road will not exceed 8%.

3. LOCATION OF EXISTING WELLS

There is one known existing well and within a one mile radius of this location site. (See Topographic Map "B").

There are no known water wells, injection wells, monitoring or observations wells for other resources within a one mile radius.

4. LOCATION OF EXISTING AND PROPOSED FACILITIES

There is one existing LOMAX EXPLORATION wells within a one mile radius of this location site. This location has the following production facilities - two 300 barrel tanks, line heaters, pumping units and heater traces.

A tank battery site will be set up at the proposed location site. This battery will be used to contain production from this well. If in the event this battery can not be improvised, a flowline will be built which will extend to an existing battery in the area.

The area will be built if possible, with native materials and if these materials are not available then the necessary arrangements will be made to get them from private sources. These facilities will be constructed using bulldozers, graders and workman crews to construct and place the proposed facilities. If there is any deviation from the above, all appropriate agencies will be notified. Rehabilitation of disturbed areas no longer needed for operation after construction is completed will meet the requirements of Item #10.

5. LOCATION AND TYPE OF WATER SUPPLY

See Topographic Map "B".

At the present time, it is anticipated that the water for this well will be hauled by truck from a private water source that is indicated on topo. map "A".

In the event that this source is not used, an alternate source will be used and all necessary arrangements will be made with the proper authorities.

There will be no water well drilled at this location site.

LOMAX EXPLORATION

West Monument Federal #6-33

Section 33, T8S, R16E, S.L.B. & M.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location site and access road shall be borrow material accumulated during construction of the location site and access road. No pit lining material from other sources are anticipated at this time, but if they are required, the appropriate actions will be taken to acquire them from private sources.

7. METHODS OF HANDLING WASTE DISPOSAL

See Location Layout Sheet.

A reserve pit will be constructed.

The reserve pit will vary in size and depth according to the water table at the time of drilling.

One half of the reserve pit will be used as a fresh water storage area during the drilling of this well and the other one half will be used to store non-flammable materials such as cuttings, salts, drilling fluids, chemicals and produced fluids, etc.

If deemed necessary by the agencies concerned to prevent contamination to surrounding areas, the reserve pits will be lined with a gel.

The pits will have wire and overhead flagging installed if deemed necessary to protect the water fowl, wildlife, and domestic animals.

At the onset of drilling, the reserve pit will be fenced on three sides and at the time drilling activities are completed, it will be fenced on the fourth side and allowed to dry completely prior to the time that backfilling and other reclamation activities are attempted.

When the reserve pit dries and reclamation activities commence, the pits will be covered with a minimum of four feet of soil and all requirements in Item #10 will be followed.

A portable chemical toilet will be provided for human waste.

8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT

See attached Location Layout Sheet.

The B.L.M. District Manager shall be notified before any construction begins on the proposed location site.

As mentioned in Item #7, the pits will be unlined unless it is determined by the representatives of the agencies involved that the materials are too porous and would cause contamination to the surrounding area; then the pits will be lined with a gel and any other type of material necessary to make it safe and tight.

LOMAX EXPLORATION

West Monument Federal #6-33

Section 33, T8S, R16E, S.L.B. & M.

When drilling activities commence, all work shall proceed in a neat and orderly sequence.

10. PLANS FOR RESTORATION OF SURFACE

As there is some topsoil on the location site, all topsoil shall be stripped and stockpiled. (See location layout sheet and Item #9). When all drilling and production activities have been completed, the location site and access road will be reshaped to the original contour and stockpiled topsoil spread over the disturbed area.

Any drainages re-routed during construction activities shall be restored to their original line of flow as near as possible. Fences around pits are to be removed upon completion of drilling activities and all waste being contained in the trash basket shall be hauled to the nearest Sanitary Landfill.

Restoration activities shall begin within 90 days after completion of the well. Once restoration activities have begun, they shall be completed within 30 days.

When restoration activities have been completed, the location site and access ramp shall be reseeded with a seed mixture recommended by the B.L.M. Representative when the moisture content of the soil is adequate for germination. The Lessee further covenants and agrees that all of said clean-up and restoration activities shall be done and performed in a diligent and most workmanlike manner and in strict conformity with the above mentioned Items #7 and #10.

11. OTHER INFORMATION

The Topography of the General Area - (See Topographic Map "A").

The area is a large basin formed by the Uinta Mountains to the North and the Book Cliff Mountains to the South. The Green River is located approximately 16 miles to the Southeast of the location site.

The basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone ledges, conglomerate deposits, and shale are common in this area.

The geologic structures of the area that are visible, are of the Uinta formation (Eocene Epoch) Tertiary Period in the upper elevations and the cobblestone and younger alluvial deposits from the Quaternary Period.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a light brownish-gray sandy clay (SM-ML) type soil with poorly graded gravels to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

LOMAX EXPLORATION

West Monument Federal #6-33

Section 33, T8S, R16E, S.L.B. & M.

Due to the low precipitation average, climatic conditions and the marginal types of soils, the vegetation that is found in the area are common of the semi-arid regions and consists of areas of sagebrush, rabbitbrush some grasses and cacti as the primary flora. This is also true of the lower elevations.

The fauna of the area is sparse and consists predominantly of the mule deer, pronghorn antelope, coyotes, rabbits, and varieties of small ground squirrels and other types of rodents. The area is used by man for the primary purpose of grazing domestic sheep and cattle.

The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

The Topography of the Immediate Area - (See Topographic Map "B").

West Monument Federal #6-33 is located approximately 0.25 miles West of Wells Draw, a non-perennial drainage which runs to the North and East.

The terrain in the vicinity of the location slopes from the Southwest through the location site to the Northeast at approximately 1% grade.

The vegetation in the immediate area surrounding the location site consists of sage brush and grasses with large areas devoid of any vegetation.

There are no occupied dwellings or other facilities of this nature in the general area.

There are no visible archaeological, historical or cultural sites within any reasonable proximity of the proposed location site. (See Topographic Map "B").

12. LESSEE'S OR OPERATOR'S REPRESENTATIVE

Jack Pruitt
LOMAX EXPLORATION
333 North Belt East, Ste. 880
Houston, TX 77060

1-713-931-9276

13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are to the best of my knowledge true and correct; and that the

LOMAX EXPLORATION

West Monument Federal #6-33


Section 33, T8S, R16E, S.L.B. & M.



work associated with the operation proposed herein will be performed by LOMAX EXPLORATION and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.

Date


2/22/83

Jack Pruitt






Shaffer Spherical
10" 900




Cameron Space Saver



10" 900





Casinghead



3000 psi
throughout

LOMAX EXPLORATION CO.
WEST MONUMENT FED. #6-33
LOCATION LAYOUT & CUT SHEET



1" = 10'

Scales
 1" = 50'

APPROXIMATE YARDAGES

Cubic Yards Cut - 932
 Cubic Yards Fill - 336


PROPOSED LOCATION


TOPO.

Map "A"



SCALE - 1" = 4 Mi.





PROPOSED ACCESS ROAD 300'±

PROPOSED LOCATION
WEST MONUMENT FED. #6-33

1.4 Mi.

WELL

WELL

WELL

WELL

WELL

R 15 E
R 16 E

T85
T95

Wells

JEEP

TRAIL

DILL HOLE


MONUMENT
SOIL FIC

Draw

peak

castle


PROPOSED LOCATION



SCALE - 1" = 2000'

ROAD CLASSIFICATION

Heavy-duty _____ Light-duty _____
Medium-duty _____ Unimproved dirt _____
U. S. Route _____ State Route _____



QUADRANGLE LOCATION

PROPOSED ACCESS ROAD 300'±

PROPOSED LOCATION
WEST MONUMENT FED. #6-33

T85
T95

R R
15 16

OPERATOR LOMAX EXPLORATION CO

DATE 3-2-83

WELL NAME FED 6-33

SEC SE NW 33 T 8S R 10E COUNTY DUCHESE

43-013-30747
API NUMBER

FED
TYPE OF LEASE

POSTING CHECK OFF:

☐

INDEX

☐

HL

☐☐

NID

☐

PI

☐☐

MAP

☐☐

PROCESSING COMMENTS:

no wells within 1000'

APPROVAL LETTER:

SPACING:

☐

A-3

UNIT

☐

c-3-a

CAUSE NO. & DATE

☒

c-3-b

☐

c-3-c

SPECIAL LANGUAGE:

☒

RECONCILE WELL NAME AND LOCATION ON APD AGAINST SAME DATA ON PLAT MAP.

☒

AUTHENTICATE LEASE AND OPERATOR INFORMATION

☒

VERIFY ADEQUATE AND PROPER BONDING *FCR*

☒

AUTHENTICATE IF SITE IS IN A NAMED FIELD, ETC.

☐

APPLY SPACING CONSIDERATION

☐

ORDER *NO*

☐

UNIT *NO*

☒

c-3-b

☐


c-3-c

☒

OUTSTANDING OR OVERDUE REPORTS FOR OTHER WELLS OF THE OPERATOR.

☒

POTASH



SCALE 1:1000

SECTION 33
TOWNSHIP 8S
RANGE 10E
COUNTY DUCHESNE

March 2, 1983

Lomax Exploration Company
P. O. Box 4503
Houston, Texas 77210

RE: Well No. Federal 6-33
SENW Sec. 33, T.8S, R.16E
Duchesne County, Utah

Gentlemen:

Insofar as this office is concerned, approval to drill the above referred to oil well is hereby granted in accordance with Rule C-3(b), General Rules and Regulations and Rules of Practice and Procedure.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:


RONALD J. FIRTH - Chief Petroleum Engineer
Office: 533-5771
Home: 571-6068

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-013-30747.

Sincerely,



Norman C. Stout
Administrative Assistant

NCS/as
cc: Oil & Gas Operations
Enclosure

Before 157
as.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: LOMAX EXPLORATION COMPANY

WELL NAME: West Monument 6-33

SECTION SENE 33 TOWNSHIP 8S RANGE 16E COUNTY Duchesne

DRILLING CONTRACTOR Orian

RIG # 1

SPUDDED: DATE 8-3-83

TIME 10:30 PM

HOW Rotary

DRILLING WILL COMMENCE _____

REPORTED BY Michelle

TELEPHONE # 713-931-9276

DATE 8-10-83 SIGNED AS

NOTICE OF SPUD

Company: Loma

Caller: Michelle

Phone: 713-931-9276

Well Number: 6-33

Location: SE NW 33 - 85-16E

County: Duchesne State: Utah

Lease Number: U-34173

Lease Expiration Date: _____

Unit Name (If Applicable): _____

Date & Time Spudded: 8-3-83 10:30 PM

Dry Hole Spudded Rotary: _____

Details of Spud (Hole, Casing, Cement, etc.) _____

Rotary Rig Name & Number: O'Regan #1

Approximate Date Rotary Moves In: _____

FOLLOW WITH SUNDRY NOTICE

Call Received By: DeLois

Date: 8-10-83

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for ~~well~~ proposals.)

1. oil well ☒ gas well ☐ other ☐

2. NAME OF OPERATOR
Lomax Exploration Company

3. ADDRESS OF OPERATOR
P.O. Box 4503, Houston, TX 77210

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1982' FNL & 1978' FWL SE/NW
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

| | | |
|---------------------------|--------------------------|--------------------------|
| TEST WATER SHUT-OFF | <input type="checkbox"/> | <input type="checkbox"/> |
| FRACTURE TREAT | <input type="checkbox"/> | <input type="checkbox"/> |
| SHOOT OR ACIDIZE | <input type="checkbox"/> | <input type="checkbox"/> |
| REPAIR WELL | <input type="checkbox"/> | <input type="checkbox"/> |
| PULL OR ALTER CASING | <input type="checkbox"/> | <input type="checkbox"/> |
| MULTIPLE COMPLETE | <input type="checkbox"/> | <input type="checkbox"/> |
| CHANGE ZONES | <input type="checkbox"/> | <input type="checkbox"/> |
| ABANDON* | <input type="checkbox"/> | <input type="checkbox"/> |
| (other) SPUD NOTIFICATION | | |

5. LEASE

U-34173

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

W. Monument Federal

9. WELL NO.

6-33

10. FIELD OR WILDCAT NAME

Undesignated

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Section 33, T8S, R16E

12. COUNTY OR PARISH 13. STATE

Duchesne

Utah

14. API NO.

43-013-30747

15. ELEVATIONS (SHOW DF, KDB, AND WD)

5678' GR

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

7/29/83 Drilled 12 1/4" hole to 290' w/dryhole digger. Set 8 5/8" 24# J-55 csg @ 281' GL. Cement w/210 sx class "G" + 2% CaCl + 1/4#/sx celloflake. Bumped plug. Float did not hold. Shut in.

8/03/83 Spud w/Orion Rig #1 @ 10:30 P.M. 8/3/83.

AUG 12 1983

Subsurface Safety Valve: Manu. and Type

Set @ DIVISION OF

18. I hereby certify that the foregoing is true and correct

SIGNED G.L. Pruitt TITLE V.P. Drlg. & Prod. DATE August 5, 1983

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

August 10, 1983

Minerals Management Service
2000 Administration Building
1745 West 1700 South
Salt Lake City, Utah 84104

W. Monument Federal #6-33
SE/NW Section 33, T8S, R16E
Duchesne County, Utah


Ute Tribal #11-19
NE/SW Section 19, T4S, R2W
Duchesne County, Utah

Gentlemen:

Enclosed are Sundry Notices for Spud Notification on the
subject wells.

Please advise if you need additional information.


Very truly yours,




Michele Tisdell
Sec. Drilling & Production

MT
Enclosures (6)

cc: State of Utah
Division of Oil and Gas
4241 State Office Building
Salt Lake City, Utah 84114



DIVISION OF
OIL, GAS & MINING



333 North Belt East • Suite 880
Houston, Texas 77090
(713) 931-9276
Mailing Address:
P.O. Box 4503
Houston, Texas 77210-4503

District Office:
248 North Union
Roosevelt, Utah 84066
Mailing Address:
P.O. Box 1446
Roosevelt, Utah 84066

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)Form approved.
Budget Bureau No. 42-R355.5.

5. LEASE DESIGNATION AND SERIAL NO.

U-34173

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

W. Monument Federal

9. WELL NO.

6-33

10. FIELD AND POOL, OR WILDCAT

Undesignated

11. SEC., T., R., M., OR BLOCK AND SURVEY
OR AREA

Section 33, T8S, R16E

12. COUNTY OR
PARISH
Duchesne13. STATE
Utah1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other

2. NAME OF OPERATOR

Lomax Exploration Company

3. ADDRESS OF OPERATOR

P.O. Box 4503, Houston, Texas 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 1982' FNL & 1978' FWL SE/NW

At top prod. interval reported below

At total depth

14. PERMIT NO.

43-013-30747

DATE ISSUED

3/2/83

15. DATE SPUDDED

8/3/83

16. DATE T.D. REACHED

8/14/83

17. DATE COMPL. (Ready to prod.)

9/7/83

18. ELEVATIONS (DF, REB, RT, GR, ETC.)*

5678' GR

19. ELEV. CASINGHEAD

5678

20. TOTAL DEPTH, MD & TVD

6200'

21. PLUG, BACK T.D., MD & TVD

6122'

22. IF MULTIPLE COMPL.,
HOW MANY*

-

23. INTERVALS
DRILLED BY

ROTARY TOOLS

XX

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*

Green River 5932-60'

25. WAS DIRECTIONAL
SURVEY MADE

NO

26. TYPE ELECTRIC AND OTHER LOGS RUN

DIL, CDI-CNL, CBL-GR

27. WAS WELL CORRED

YES

28. CASING RECORD (Report all strings set in well)

| CASING SIZE | WEIGHT, LB./FT. | DEPTH SET (MD) | HOLE SIZE | CEMENTING RECORD | AMOUNT PULLED |
|-------------|-----------------|----------------|-----------|--|---------------|
| 8 5/8" | 24 | 281 | 12 1/4 | 210 sx C1 "G" + 2% CaCl + 1/4#/sx flocele | |
| 5 1/2" | 17 | 6165' | 7 7/8 | 453 sx RFC & 155 sx Lodense | |

29. LINER RECORD

| SIZE | TOP (MD) | BOTTOM (MD) | SACKS CEMENT* | SCREEN (MD) |
|------|----------|-------------|---------------|-------------|
| | | | | |
| | | | | |

30. TUBING RECORD

| SIZE | DEPTH SET (MD) | PACKER SET (MD) |
|-------|----------------|-----------------|
| 2 7/8 | 6028 | |
| | | |

31. PERFORATION RECORD (Interval, size and number)

5932-60'

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

| DEPTH INTERVAL (MD) | AMOUNT AND KIND OF MATERIAL USED |
|---------------------|---|
| 5932-60' | 38,500 gals gelled KCl water & 116,000# 20/40 sand |
| | |

33.* PRODUCTION

DATE FIRST PRODUCTION

9/7/83

PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)

Pumping

WELL STATUS (Producing or
shut-in)

Producing

DATE OF TEST

9/17/83

HOURS TESTED

24

CHOKE SIZE

Open

PROD'N. FOR
TEST PERIOD

→

OIL—BBL.

22

GAS—MCF.

NM

WATER—BBL.

3

GAS-OIL RATIO

NM

FLOW. TUBING PRESS.

0

CASING PRESSURE

0

CALCULATED
24-HOUR RATE

→

OIL—BBL.

22

GAS—MCF.

NM

WATER—BBL.

3

OIL GRAVITY-API (CORR.)

35

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used for fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

G. L. Pruitt TITLE V.P. Drilling & Production

DATE

9/20/83

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

| FORMATION | TOP | BOTTOM | DESCRIPTION, CONTENTS, ETC. |
|--------------------|------------|--------|-----------------------------|
| Green River | -1800 | | |
| Garden Gulch | -3950 | | |
| Douglas Creek | -4964 | | |
| C | -5180 | | |
| B | -5340 | | |
| A | -5550 | | |
| Black Shale Facies | -5748 | | |
| Castle Peak | -6005 | | |
| Core Interval | 5596-5624' | | |

38.

GEOLOGIC MARKERS

| NAME | TOP | |
|------|-------------|------------------|
| | MEAS. DEPTH | TRUE VERT. DEPTH |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

December 6, 1983

RECEIVED
DEC 13 1983

DIVISION OF
OIL, GAS & MINING

Ms. Cari Furse
State of Utah
Division of Oil and Gas
4241 State Office Building
Salt Lake City, Utah 84114

Core Descriptions

Dear Cari:

As per our phone conversation Core Descriptions for the wells requested are as follows:

Federal #2-33, NW/NE Section 33, T8S, R16E

5647-5660' Sd, fs, slty, sl/calc, tr pyr

5660-5677' Sh, sdy lams

Federal #6-33, SE/NW Section 33, T8S, R16E

5596-5624' (Recovered 25' shale)

Please include these descriptions with our Well Completion Reports previously submitted.

If you need additional information, please advise.

Very truly yours,

Michele Tisdell

Michele Tisdell
Sec., V.P. Drilling & Production

MT

333 North Belt East • Suite 880 • Houston, Texas 77060 • 713/931-9276
Mailing Address: P.O. Box 4503 • Houston, Texas 77210-4503

District Office: 248 North Union • Roosevelt, Utah 84066
Mailing Address: P.O. Box 1446 • Roosevelt, Utah 84066

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE*

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

5. LEASE DESIGNATION AND SERIAL NO.

U-34173

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

W. Monument Federal

9. WELL NO.

#6-33

10. FIELD AND POOL, OR WILDCAT

Monument Butte

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec 33, T8S, R16E

12. COUNTY OR PARISH

Duchesne

13. STATE

Utah

1a. TYPE OF WELL:

OIL WELL ☐ GAS WELL ☐ DRY ☐ Other

b. TYPE OF COMPLETION:

NEW WELL ☐ WORK OVER ☒ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other

2. NAME OF OPERATOR

Lomax Exploration Co.

3. ADDRESS OF OPERATOR

P.O.Box 4503, Houston, Texas 77210

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 1982' FNL & 1978' FWL SE/NW

At top prod. interval reported below

At total depth

14. PERMIT NO.

43-013-30747

DATE ISSUED

3-02-83

15. DATE SPUDDED

8-3-83

16. DATE T.D. REACHED

8-14-83

17. DATE COMPL. (Ready to prod.)

3-5-84

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

5678' GR

19. ELEV. CASINGHEAD

5678'

20. TOTAL DEPTH, MD & TVD

6200'

21. PLUG, BACK T.D., MD & TVD

5310'

22. IF MULTIPLE COMPL., HOW MANY*

23. INTERVALS DRILLED BY

ROTARY TOOLS

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*

Green River 5057-66

25. WAS DIRECTIONAL SURVEY MADE

NO

26. TYPE ELECTRIC AND OTHER LOGS RUN

DIL, CDL-CNL, CBC-GR

27. WAS WELL CORED

YES

28. CASING RECORD (Report all strings set in well)

| CASING SIZE | WEIGHT, LB./FT. | DEPTH SET (MD) | HOLE SIZE | CEMENTING RECORD | AMOUNT PULLED |
|-------------|-----------------|----------------|-----------|--|---------------|
| 8 5/8" | 24 | 281 | 12 1/4 | 210 sx c1 "G" & 2% CACL & 1/4 #/sk Flocele | |
| 5 1/2" | 17 | 6165 | 7 7/8 | 453 sx RFC & 155 sx lodense | |
| | | | | | |
| | | | | | |

29. LINER RECORD

| SIZE | TOP (MD) | BOTTOM (MD) | SACKS CEMENT* | SCREEN (MD) |
|------|----------|-------------|---------------|-------------|
| | | | | |
| | | | | |

30. TUBING RECORD

| SIZE | DEPTH SET (MD) | PACKER SET (MD) |
|--------|----------------|-----------------|
| 2 7/8" | 5118 | |
| | | |

31. PERFORATION RECORD (Interval, size and number)

5057-66

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

| DEPTH INTERVAL (MD) | AMOUNT AND KIND OF MATERIAL USED |
|---------------------|---|
| 5057-66 | 19,330 gal KCL water & 62,640 # of 20/40 sand |
| | |
| | |

33.* PRODUCTION

| DATE FIRST PRODUCTION | | PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) | | | | | WELL STATUS (Producing or shut-in) | |
|-----------------------|-----------------|--|-------------------------|----------|------------|-------------------------|------------------------------------|--|
| 3-5-84 | | Pumping | | | | | Producing | |
| DATE OF TEST | HOURS TESTED | CHOKE SIZE | PROD'N. FOR TEST PERIOD | OIL—BBL. | GAS—MCF. | WATER—BBL. | GAS-OIL RATIO | |
| 4-2-84 | 24 | Open | → | 67 | 87 | 2 | 1304 | |
| FLOW, TUBING PRESS. | CASING PRESSURE | CALCULATED 24-HOUR RATE | OIL—BBL. | GAS—MCF. | WATER—BBL. | OIL GRAVITY-API (CORR.) | | |
| 0 | 0 | → | 67 | 87 | 2 | 38 | | |

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used for fuel and vented

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

G.L. Pruitt

TITLE

Vice-President of Drilling & Production

DATE

April 12, 1984

*(See Instructions and Spaces for Additional Data on Reverse Side)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIP
(Other instructions
verse side)

Form approved.
Budget Bureau No. 1004-0135
Expires August 31, 1985

5. LEASE DESIGNATION AND SERIAL NO.

U-34173

8. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

N/A

8. FARM OR LEASE NAME

N/A

9. WELL NO. W. Monument Federal

#2-33, #3-33, #6-33

10. FIELD AND POOL, OR WILDCAT

Monument Butte

11. SEC., T., R., M., OR BLM. AND
SURVEY OR AREA

33-8S-16E

12. COUNTY OR PARISH

Duchesne

13. STATE

Utah

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT--" for such proposals.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR
Lomax Exploration Company

3. ADDRESS OF OPERATOR
50 W. Broadway, Suite 1000, Salt Lake City, UT 84101

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

See attached sheet.

14. PERMIT NO.

See attached sheet.

15. ELEVATIONS (Show whether DP, RT, OR, etc.)

See attached sheet.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

PULL OR ALTER CASING

FRACTURE TREAT

MULTIPLE COMPLETION

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANS

(Other)

Construct gas gathering
system

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

REPAIRING WELL

FRACTURE TREATMENT

ALTERING CASING

SHOOTING OR ACIDIZING

ABANDONMENT*

(Other)

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Construct a gas gathering system for the subject wells. The system will consist of an 8" main line and 3" feeder lines from each of the subject wells to the main line. The 8" main line will enter the lease at a point approximately 2,050 feet East of the Northwest corner of Section 33, and will tie into a compressor site located in the SW/NE of Section 33. The 8" main line and the 3" feeder lines will be buried. A 4" surface line will be built from the compressor site to a point on the East line of Section 33 (lease boundary). A 3" gas fuel line will be buried along the entire system. The compressor site will contain a compressor (housed), condensate storage tank or tanks, gas separator, gas processing plant, and generator (housed). The compressor site will occupy approximately two (2) acres. Initial volumes of gas to be transported will be approximately 511 MCFD in addition to approximately 525 MCFD from other wells located off lease. Construction will begin upon receipt of approval. See attached plat.

RECEIVED

MAY 29 1984

DIVISION OF OIL
GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED David D. Perkins

(This space for Federal or State office use)

TITLE District Landman

DATE May 16, 1984

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

*See Instructions on Reverse Side

Attached to that certain Sundry Notice dated May 16, 1984 for the
W. Monument Butte Federal #2-33, #3-33 & #6-33 Wells on Lease U-34173.

Item 4. - Location of well:


#2-33 - 751' FNL, 2196' FEL, Section 33, T8S-R16E
#3-33 - 642' FNL, 1967' FWL, Section 33, T8S-R16E
#6-33 - 1982' FNL, 1978' FWL, Section 33, T8S-R16E

Item 14. - Permit No.:

#2-33 - 43013-30749
#3-33 - 43013-30693
#6-33 - 43013-30747

Item 15. - Elevations:

#2-33 - 5627 GR
#3-33 - 5634 GR
#6-33 - 5678 GR



RECEIVED

MAY 29 1904

DIVISION OF OIL,
GAS & MINING

4 4

Scale: 1" = 2000'

OPERATOR LOMAX EXPLORATION COMPANYOPERATOR ACCT. NO. N 0580ADDRESS P. O. BOX 1446ROOSEVELT, UT 84066

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|---|--------------------|----------------|-------------------------|------------------------|---------------|----|----|-----|----------|-----------|----------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 2635 | 10628 | 43-013-30693 | FEDERAL 3-33 | NENW | 33 | 8S | 16E | DUCHESNE | 11-9-82 | 12-1-91 |
| WELL 1 COMMENTS: *TRAVIS UNIT APPROVED EFFECTIVE 12-1-91 (6 WELLS IN UNIT), PER KEBBIE JONES W/LOMAX SET UP ALL WELLS UNDER THE SAME ENTITY FOR REPORTING PURPOSES. | | | | | | | | | | | |
| B | 2640 | 10628 | 43-013-30779 | FEDERAL 15-28 | SWSE | 28 | 8S | 16E | DUCHESNE | 08-19-83 | 12-1-91 |
| WELL 2 COMMENTS: | | | | | | | | | | | |
| B | 9487 | 10628 | 43-013-30856 | W. MONUMENT FED #10-28 | NWSE | 28 | 8S | 16E | DUCHESNE | 05-10-84 | 12-1-91 |
| WELL 3 COMMENTS: | | | | | | | | | | | |
| B | 10626 | 10628 | 43-013-30747 | FEDERAL 6-33 | SENW | 33 | 8S | 16E | DUCHESNE | 08-03-83 | 12-1-91 |
| WELL 4 COMMENTS: | | | | | | | | | | | |
| B | 10627 | 10628 | 43-013-30749 | FEDERAL 2-33 | NWNE | 33 | 8S | 16E | DUCHESNE | 05-31-83 | 12-1-91 |
| WELL 5 COMMENTS: | | | | | | | | | | | |

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

L. ROMERO (DOGM)

Signature

ADMIN. ANALYST

12-10-91

Title

Date

Phone No. ()

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|--|-----------------------|-------------------|--------------|---------------|---------------|----|----|-----|----------|--------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 10628 | 10628 | 43-013-30792 | FEDERAL 14-28 | SESW | 28 | 8S | 16E | DUCHESNE | 10-11-83 | 12-1-91 |
| WELL 1 COMMENTS: *TRAVIS UNIT APPROVED EFF. 12-1-91 (6 WELLS IN UNIT), PER KEBBIE JONES W/LOMAX SET UP ALL WELLS UNDER THE SAME ENTITY FOR REPORTING PURPOSES. | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 2 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 3 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 4 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 5 COMMENTS: | | | | | | | | | | | |

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

L. ROMERO (DOGM)

Signature

ADMIN. ANALYST12-10-91

Title

Date

Phone No. ()

Page No. 1
11/26/91

WELL STATUS REPORTS
UTAH STATE OFFICE

| API NUMBER | WELL NUMBER | QTQT SEC | TWN | RNG | WELL STATUS | LEASE NUMBER | DISTRICT | TYPE |
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|

** INSPECTION ITEM = UTSL071572A

* OPERATOR = LOMAX EXPL CO

| | | | | | | | | |
|------------------|-------|------|-------|-----|-----|-------------|------------|---|
| * 430133085600S1 | 10-28 | NWSE | 28 8S | 16E | POW | UTSL071572A | VERNAL, UT | L |
| * 430133079200S1 | 14-28 | SESW | 28 8S | 16E | OSI | UTSL071572A | VERNAL, UT | L |
| 430131620800S1 | J-1 | L2 | 21 8S | 16E | POW | UTSL071572A | VERNAL, UT | L |
| 430133039400S1 | PV-1 | SESE | 21 8S | 16E | TA | UTSL071572A | VERNAL, UT | L |

Page No. 1
11/26/91

WELL STATUS REPORTS
UTAH STATE OFFICE

| API NUMBER | WELL NUMBER | QTQT SEC | TWN | RNG | WELL STATUS | LEASE NUMBER | DISTRICT | TYPE |
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|

** INSPECTION ITEM = UTU26026A

* OPERATOR = LOMAX EXPL CO

| | | | | | | | | |
|------------------|-------|------|-------|-----|-----|-----------|------------|---|
| * 430133077900S1 | 15-28 | SWSE | 28 8S | 16E | POW | UTU26026A | VERNAL, UT | L |
| 430133070500X1 | 3-28 | NENW | 28 8S | 16E | ABD | UTU26026A | VERNAL, UT | L |

Page No. 1
11/26/91

WELL STATUS REPORTS
UTAH STATE OFFICE

| API NUMBER | WELL NUMBER | QTQT SEC | TWN | RNG | WELL STATUS | LEASE NUMBER | DISTRICT | TYPE |
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|
|------------|----------------|----------|-----|-----|----------------|--------------|----------|------|

** INSPECTION ITEM = UTU34173

* OPERATOR = LOMAX EXPL CO

| | | | | | | | | |
|------------------|------|------|-------|-----|-----|----------|------------|---|
| * 430133074900S1 | 2-33 | NWNE | 33 8S | 16E | POW | UTU34173 | VERNAL, UT | L |
| * 430133069300S1 | 3-33 | NENW | 33 8S | 16E | POW | UTU34173 | VERNAL, UT | L |
| * 430133075400X1 | 4-33 | NWNW | 33 8S | 16E | ABD | UTU34173 | VERNAL, UT | L |
| * 430133074700S1 | 6-33 | SENE | 33 8S | 16E | POW | UTU34173 | VERNAL, UT | L |

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

KEBBIE JONES
LOMAX EXPLORATION COMPANY
PO BOX 1446
ROOSEVELT UT 84066

UTAH ACCOUNT NUMBER: N0580

REPORT PERIOD (MONTH/YEAR): 6 / 95

AMENDED REPORT ☐ (Highlight Changes)

| Well Name | | | Producing Zone | Well Status | Days Oper | Production Volumes | | |
|-------------------------|--------|------------|----------------|-------------|-----------|--------------------|------------|------------------|
| API Number | Entity | Location | | | | OIL(BBL) | GAS(MCF) | WATER(BBL) |
| ✓ CASTLE PK FED 12-24 | | | | | | | | |
| 4301330588 | 02650 | 09S 16E 24 | GRRV | | | U15855 | | |
| ✓ FEDERAL 9-23 | | | | | | " | | |
| 4301330654 | 02655 | 09S 16E 23 | GRRV | | | | | |
| ✓ FEDERAL 13-21 | | | | | | U50376 | | |
| 4301330665 | 02660 | 08S 17E 21 | GRRV | | | | | |
| ✓ FEDERAL #1-1 | | | | | | U40652 | UTU 72104 | Lease Segregated |
| 4301330571 | 02685 | 09S 16E 1 | GRRV | | | | | |
| ✓ BOUNDARY FEDERAL 7-20 | | | | | | U50376 | | |
| 4301330750 | 08407 | 08S 17E 20 | GRRV | | | | | |
| ✓ BOUNDARY FEDERAL 9-20 | | | | | | " | | |
| 4301330690 | 08408 | 08S 17E 20 | GRRV | | | | | |
| ✓ UNDARY FEDERAL 15-20 | | | | | | " | | |
| 4301330667 | 08409 | 08S 17E 20 | GRRV | | | | | |
| ✓ CASTLE PEAK FED 6-23 | | | | | | U15855 | | |
| 4301330873 | 09700 | 09S 16E 23 | GRRV | | | | | |
| ✓ WELLS DRAW STATE 7-36 | | | | | | ML 21835 | | |
| 4301330934 | 09730 | 08S 15E 36 | GRRV | | | | | |
| ✓ PLEASANT VALLEY #1 | | | | | | U071572A | SL-071572A | |
| 4301330394 | 10520 | 08S 16E 21 | GRRV | | | | | |
| ✓ JENSEN #1 | | | | | | SL071572A | | |
| 4301316208 | 10521 | 08S 16E 21 | GRRV | | | | | |
| ✓ LAMBERT FEDERAL #1 | | | | | | U065914 | SL-065914 | |
| 4301316207 | 10522 | 08S 16E 22 | GRRV | | | | | |
| ✓ FEDERAL 6-33 | | | | | | U34173 | | |
| 4301330747 | 10628 | 08S 16E 33 | GRRV | | | | | |
| TOTALS | | | | | | | | |

COMMENTS:

I hereby certify that this report is true and complete to the best of my knowledge.

Date:

Name and Signature:

Telephone Number:

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
LOMAX EXPLORATION COMPANY

FILED
In the Office of the
Secretary of State of Texas

JUN 29 1995

Corporations Section

Pursuant to the provisions of Part Four of the Texas Business Corporation Act, the undersigned corporation adopts the following articles of amendment to its Articles of Incorporation:

1. Name. The name of the corporation is LOMAX EXPLORATION COMPANY.
2. Statement of Amendment. The amendment alters or changes Article One of the original Articles of Incorporation to read in full as follows:

"Article One. The name of the corporation is INLAND PRODUCTION COMPANY."

3. Shareholders. The number of shares of the corporation outstanding at the time of such adoption was 205,315, there being 107,546 Common Shares and 97,769 Non-voting Preferred Shares; and the number of shares entitled to vote thereon was 107,546.

4. Adoption by Shareholders. Only the holders of Common Shares of the corporation are entitled to vote on the amendment. The shareholders adopted the foregoing amendment by unanimous written consent dated June 23, 1995, pursuant to the provisions of Article 9.10 of the Texas Business Corporation Act and, therefore, no notice was required to be delivered under said Article 9.10.

5. Adoption by Board of Directors. The Board of Directors adopted said amendment by a consent in writing signed by all Directors.

6. Future Effective Date. This amendment will become effective on July 1, 1995, at 12:01 a.m.

EXECUTED June 26, 1995.



Kyle R. Miller, President

Lomax Exploration Company

A subsidiary of Inland Resources Inc.



July 13, 1995

State of Utah Department of Natural Resources
Attention: Ms Becky Pritchett
355 W. North Temple
3 Triad Center, Suite 400
Salt Lake City, Utah 84180-1204

RE: Corporate Name Change

Dear Sir or Madame:

Effective July 1, 1995, Lomax Exploration Company will have taken the steps necessary to change its name to **Inland Production Company**. A Certificate issued by the Texas Secretary of State evidencing the name change is attached for your files. We have also attached to this letter those Utah State leases (Exhibit "B") and wells (Exhibit "A") affected by this name change. We have attempted to provide a complete list from the records we have. The intent is to include all leases and wells that Lomax Exploration Company operates or has an interest in.


Riders changing the Principal from Lomax Exploration Company to Inland Production Company under Nationwide Oil and Gas Bond # 4488944 for Lomax Exploration Company will be furnished to the State of Utah in the very near future.

Please amend your records by substituting Inland Production Company in place of Lomax Exploration Company on the leases and wells listed on the attached exhibits. In the future we will begin submitting notices and permits for new operations after July 1, 1995 in the name of Inland Production Company.

Should a fee be required or should you need further information or documents relating to our name change please contact the undersigned at your convenience at the following number: (303) 292-0900 or Cheryl Cameron at our Roosevelt, Utah office (801) 722-5103.

Sincerely yours,

Chris A Potter, CPL
Manager of Land



The State of Texas

Secretary of State
JUNE 30, 1995

MIKE PARSONS...GLAST, PHILLIPS & MURRAY
2200 ONE GALLERIA TWR, 13355 NOEL RD, LB48
DALLAS ,TX 75240-6657

RE:
INLAND PRODUCTION COMPANY
CHARTER NUMBER 00415304-00


IT HAS BEEN OUR PLEASURE TO APPROVE AND PLACE ON RECORD YOUR ARTICLES OF AMENDMENT. A COPY OF THE INSTRUMENT FILED IN THIS OFFICE IS ATTACHED FOR YOUR RECORDS.

THIS LETTER WILL ACKNOWLEDGE PAYMENT OF THE FILING FEE.

IF WE CAN BE OF FURTHER SERVICE AT ANY TIME, PLEASE LET US KNOW.

VERY TRULY YOURS,




Antonio O. Garza, Jr., Secretary of State



The State of Texas

Secretary of State

CERTIFICATE OF AMENDMENT

FOR

INLAND PRODUCTION COMPANY

FORMERLY

LOMAX EXPLORATION COMPANY
CHARTER NUMBER 00415304

THE UNDERSIGNED, AS SECRETARY OF STATE OF THE STATE OF TEXAS,
HEREBY CERTIFIES THAT THE ATTACHED ARTICLES OF AMENDMENT FOR THE ABOVE
NAMED ENTITY HAVE BEEN RECEIVED IN THIS OFFICE AND ARE FOUND TO
CONFORM TO LAW.

ACCORDINGLY THE UNDERSIGNED, AS SECRETARY OF STATE, AND BY VIRTUE
OF THE AUTHORITY VESTED IN THE SECRETARY BY LAW, HEREBY ISSUES THIS
CERTIFICATE OF AMENDMENT.

DATED JUNE 29, 1995


EFFECTIVE JUNE 29, 1995




Antonio O. Garza, Jr., Secretary of State

Lomax Exploration Company

A subsidiary of Inland Resources Inc.



Announcing
Our Name Change

From

Lomax Exploration Company

To

**Inland Production
Company**

** N 5160 assigned 7/26/95. Lee*

Field And Corporate Office Locations Remain The Same:

Corporate Office:

Inland Resources Inc.

475 Seventeenth Street, Suite 1500

Denver, CO 80202

Field Office:


W. Pole Line Road

P.O. Box 1446

Roosevelt, Utah 84066

United States Department of the Interior
BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155



JUL 25 1995

IN REPLY REFER TO:
3100
SL-065914 et al
(UT-923)

NOTICE

| | | |
|--------------------------------|---|--------------------|
| Inland Production Company | : | Oil and Gas Leases |
| 475 Seventeenth St., Ste. 1500 | : | SL-065914 et al |
| Denver, Colorado 80202 | : | |

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of Lomax Exploration Company to Inland Production Company on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

For our purposes, the name change is recognized effective June 29, 1995 (Secretary of State's approval date).

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Lomax Exploration Company to Inland Production Company on Bond No. 4488944 (BLM Bond No. UT0056). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to this office. BLM Bond Nos. MT0771 and WY0821 should also be changed for the bonds held by Montana and Wyoming respectively.

/s/ ROBERT LOPEZ

Chief, Branch of Mineral
Leasing Adjudication

Enclosure
1-Exhibit (1 p)

cc: Hartford Accident & Indemnity Co.
Hartford Plaza
Hartford, CT 06115

bc: Moab District Office
Vernal District Office
Montana State Office
Wyoming State Office
Eastern States Office
MMS--Data Management Division, MS 3113, P.O. Box 5860, Denver, CO 80217
State of Utah, Attn: Lisha Cordova, Division of Oil, Gas & Mining,
355 West North Temple, 3 Triad Center, Suite 350, SLIC, UT 84180
Teresa Thompson (UT-922)
Dianne Wright (UT-923)

EXHIBIT

| | | |
|------------|-----------|-----------|
| SL-065914 | U-36846 | UTU-66185 |
| SL-071572A | U-38428 | UTU-67170 |
| U-02458 | U-45431 | UTU-68548 |
| U-15855 | U-47171 | UTU-69060 |
| U-16535 | U-50376 | UTU-69061 |
| U-26026 | U-62848 | UTU-72103 |
| U-34173 | UTU-65965 | UTU-72104 |
| U-36442 | UTU-66184 | UTU-73088 |

FAX COVER SHEET



475 17th Street, Suite 1500
Denver, CO 80202
303-292-0900, Fax #303-296-4070

DATE: August 8, 1995

TO: Lisha Cordova

COMPANY: State of Utah - Division of Oil, Gas and Mining

FAX NUMBER: 801 359 3940

FROM: Chris A Potter

NUMBER OF PAGES: 1 (INCLUDING COVER SHEET):

RE: Transfer of Authority to Inject
Lomax Exploration Company to Inland Production Company

I hope the info I sent to you August 1st was acceptable regarding our name change and your phone call to me last week.....

If there is anything missing or you need additional info, please let me know. I am located in our Denver office.....

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change.
Initial each listed item when completed. Write N/A if item is not applicable.

| | |
|----------------|--------|
| Routing: (GIL) | |
| 1-MC | 7-PL |
| 2-LWP | 8-SJ |
| 3-DTS | 9-FILE |
| 4-VLD | |
| 5-RJF | |
| 6-LWP | |

- ☒ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☐ Operator Name Change Only

(MERGER)

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 6-29-95)

TO (new operator) INLAND PRODUCTION COMPANY
(address) PO BOX 1446
ROOSEVELT UT 84066
KEBBIE JONES
phone (801) 722-5103
account no. N 5160

FROM (former operator) LOMAX EXPLORATION COMPANY
(address) PO BOX 1446
ROOSEVELT UT 84066
KEBBIE JONES
phone (801) 722-5103
account no. N 0580

Well(s) (attach additional page if needed):

| | | | | | | |
|-------------------------------|-----------------------|---------------|-----------|-----------|-----------|-------------------|
| Name: **SEE ATTACHED** | API: <u>013-30747</u> | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |
| Name: _____ | API: _____ | Entity: _____ | Sec _____ | Twp _____ | Rng _____ | Lease Type: _____ |

OPERATOR CHANGE DOCUMENTATION

- Sec 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). (Rec'd 7/14/95)
- N/A 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- Sec 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) no If yes, show company file number: _____ (7-28-95)
- Sec 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- Sec 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (7-31-95)
- Sup 6. Cardex file has been updated for each well listed above. 8-16-95
- Sup 7. Well file labels have been updated for each well listed above. 8-22-95
- Sec 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (7-31-95)
- Sec 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Yes 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (~~Fee wells only~~) *Trust Lands Admin. / Rider or Repl. in Progress.*

- N/A Yes 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no) . Today's date 19 . If yes, division response was made by letter dated 19 .

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- N/A 1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated 19 , of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- OL 2. Copies of documents have been sent to State Lands for changes involving State leases.
8/23/95 sent to Ed Bonner

FILMING

- ✓ 1. All attachments to this form have been microfilmed. Date: August 30 1995.

FILING

1. Copies of all attachments to this form have been filed in each well file.
2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

950726 BLM/SL Appr. eff. 6-29-95.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

5. Lease Designation and Serial No.

U-34173

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

TRAVIS

8. Well Name and No.

FEDERAL 6-33

9. API Well No.

43-013-30747

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UTAH

SUBMIT IN TRIPLICATE

1. Type of Well

☒

Oil
Well

☐

Gas
Well

☐

Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

475 17TH STREET, SUITE 1500, DENVER, COLORADO 80202 (303) 292-0900

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

1982 FNL 1978 FWL

SE/NW Section 33, T08S R16E

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐

Notice of Intent

☒

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☐

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☒

Other

Site Security Diagram

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection


☐

Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is direction-ally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Attached please find a site security diagram for the above referenced well. This diagram supercedes any previously submitted site security diagrams.



14. I hereby certify that the foregoing is true and correct

Signed

Debbie E. Knight

Title

Manager, Regulatory Compliance

Date

8/25/98

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

UTAH DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Inland Production Company


Site Facility Diagram

Travis 6-33

SE/NW Sec. 33, T8S, 16E

Duchesne County

May 12, 1998



Site Security Plan is held at the Roosevelt Office,
Roosevelt Utah

Production Phase:

- 1) Valves 1, 3, 4 sealed closed
- 2) Valves 2 and 5 sealed open

Sales Phase:

- 1) Valves 1, 2, 4, 5 sealed closed
- 2) Valves 3 open

Draining Phase:

- 1) Valve 1 open

Legend

| | |
|---------------|-------------|
| Emulsion Line | |
| Load Line | ----- |
| Water Line | - . - . - . |
| Oil Line | ————— |
| Gas Sales | ----- |

(June 1990)

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

FORM APPROVED

Budget Bureau No. 1004-0135

Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

5. Lease Designation and Serial No.

U-34173

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

TRAVIS

8. Well Name and No.

FEDERAL 6-33

9. API Well No.

43-013-30747

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UTAH**SUBMIT IN TRIPLICATE**

1. Type of Well

Oil
WellGas
Well

Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

475 17TH STREET, SUITE 1500, DENVER, COLORADO 80202 (303) 292-0900

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

1982 FNL 1978 FWL**SE/NW Section 33, T08S R16E**

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

Notice of Intent



Subsequent Report



Final Abandonment Notice

TYPE OF ACTION

Abandonment



Recompletion



Plugging Back



Casing Repair



Altering Casing

Other Site Security

Change of Plans



New Construction



Non-Routine Fracturing



Water Shut-Off



Conversion to Injection




Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Attached please find the site security diagram for the above referenced well.



14. I hereby certify that the foregoing is true and correct

Signed

Leah E. Knight

Title

Manager, Regulatory Compliance

Date

10/7/98

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: UTAH DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Inland Production Company

Site Facility Diagram

Travis 6-33

SE/NW Sec. 33, T8S, 16E

Duchesne County

May 12, 1998

Well Head

Pumping Unit

Site Security Plan is held at the Roosevelt Office,
Roosevelt Utah

Production Phase:

- 1) Valves 1, 3, 4 sealed closed
- 2) Valves 2 and 5 sealed open

Sales Phase:

- 1) Valves 1, 2, 4, 5 sealed closed
- 2) Valves 3 open

Draining Phase:

- 1) Valve 1 open

Diked Section

Treater

Gas Sales Meter

Water Tank

Contained Section

Production Tank

Production Tank

Diked Section

Legend

| | |
|---------------|-------|
| Emulsion Line | |
| Load Line | ----- |
| Water Line | ----- |
| Oil Line | ----- |
| Gas Sales | ----- |

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

1982' FNL & 1978' FWL SE/NW Section 33, T8S, R16E

5. Lease Designation and Serial No.

U-34173

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

Travis

8. Well Name and No.

Federal 6-33-8-16

9. API Well No.

43-013-30747

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UTA

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Status Report**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Status report for time period 6/18/01 through 6/24/01.

Subject well had re-completion procedures initiated in the Green River formation on 6/16/01. The first new interval was perforated W/ 4 JSPF as follows: CP3 sds @ 6010-6018' & 6040-6046'. Interval was broken down W/ KCL water only (no proppant). Four additional intervals were perforated W/ 4 JSPF and hydraulically fracture treated W/ 20/40 mesh sand as follows: LODC sds @ 5652-5666'; fraced W/ 19,595# 20/40 sand in 233 bbls Viking I-25 fluid (screened out early). A1 sds @ 5450-5458'; fraced W/ 40,600# 20/40 sand in 284 bbls Viking I-25 fluid (screened out on flush). C sds @ 5184-5194'; fraced W/ 37,413# 20/40 sand in 266 bbls Viking I-25 fluid. GB4 sds @ 4505-4519' & GB6 sds @ 4544-4555'; fraced W/ 112,834# 20/40 sand in 670 bbls Viking I-25 fluid. Well awaits bridge plug removal at present time.

RECEIVED

JUN 26 2001

**DIVISION OF
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Signed

Gary Dietz
Gary Dietz

Title

Completion Foreman

Date

25-Jun-01

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

5. Lease Designation and Serial No.

U-34173

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

Travis

8. Well Name and No.

Federal 6-33-8-16

9. API Well No.

43-013-30747

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UTA

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

1982' FNL & 1978' FWL SE/NW Section 33, T8S, R16E

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Status Report**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Status report for time period 6/18/01 through 6/24/01.

Subject well had re-completion procedures initiated in the Green River formation on 6/16/01. The first new interval was perforated W/ 4 JSPF as follows: CP3 sds @ 6010-6018' & 6040-6046'. Interval was broken down W/ KCL water only (no proppant). Four additional intervals were perforated W/ 4 JSPF and hydraulically fracture treated W/ 20/40 mesh sand as follows: LODC sds @ 5652-5666'; fraced W/ 19,595# 20/40 sand in 233 bbls Viking I-25 fluid (screened out early). A1 sds @ 5450-5458'; fraced W/ 40,600# 20/40 sand in 284 bbls Viking I-25 fluid (screened out on flush). C sds @ 5184-5194'; fraced W/ 37,413# 20/40 sand in 266 bbls Viking I-25 fluid. GB4 sds @ 4505-4519' & GB6 sds @ 4544-4555'; fraced W/ 112,834# 20/40 sand in 670 bbls Viking I-25 fluid. Bridge plugs and sand plugs were removed from wellbore. Zones were swab tested to clean up sand. Production equipment was replaced in well. Well resumed producing on pump on 6/30/01.

RECEIVED

JUL 03 2001

**DIVISION OF
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Signed

Gary Dietz
Gary Dietz

Title

Completion Foreman

Date

01-Jul-01

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer

| | | | | | |
|---------|--------|--------|--------|-------|--------|
| UTSL- | 15855 | 61052 | 73088 | 76561 | |
| 071572A | 16535 | 62848 | 73089 | 76787 | |
| 065914 | 16539 | 63073B | 73520A | 76808 | |
| | 16544 | 63073D | 74108 | 76813 | |
| | 17036 | 63073E | 74805 | 76954 | 63073X |
| | 17424 | 63073O | 74806 | 76956 | 63098A |
| | 18048 | 64917 | 74807 | 77233 | 68528A |
| UTU- | 18399 | 64379 | 74808 | 77234 | 72086A |
| | 19267 | 64380 | 74389 | 77235 | 72613A |
| 02458 | 26026A | 64381 | 74390 | 77337 | 73520X |
| 03563 | 30096 | 64805 | 74391 | 77338 | 74477X |
| 03563A | 30103 | 64806 | 74392 | 77339 | 75023X |
| 04493 | 31260 | 64917 | 74393 | 77357 | 76189X |
| 05843 | 33992 | 65207 | 74398 | 77359 | 76331X |
| 07978 | 34173 | 65210 | 74399 | 77365 | 76788X |
| 09803 | 34346 | 65635 | 74400 | 77369 | 77098X |
| 017439B | 36442 | 65967 | 74404 | 77370 | 77107X |
| 017985 | 36846 | 65969 | 74405 | 77546 | 77236X |
| 017991 | 38411 | 65970 | 74406 | 77553 | 77376X |
| 017992 | 38428 | 66184 | 74411 | 77554 | 78560X |
| 018073 | 38429 | 66185 | 74805 | 78022 | 79485X |
| 019222 | 38431 | 66191 | 74806 | 79013 | 79641X |
| 020252 | 39713 | 67168 | 74826 | 79014 | 80207X |
| 020252A | 39714 | 67170 | 74827 | 79015 | 81307X |
| 020254 | 40026 | 67208 | 74835 | 79016 | |
| 020255 | 40652 | 67549 | 74868 | 79017 | |
| 020309D | 40894 | 67586 | 74869 | 79831 | |
| 022684A | 41377 | 67845 | 74870 | 79832 | |
| 027345 | 44210 | 68105 | 74872 | 79833 | |
| 034217A | 44426 | 68548 | 74970 | 79831 | |
| 035521 | 44430 | 68618 | 75036 | 79834 | |
| 035521A | 45431 | 69060 | 75037 | 80450 | |
| 038797 | 47171 | 69061 | 75038 | 80915 | |
| 058149 | 49092 | 69744 | 75039 | 81000 | |
| 063597A | 49430 | 70821 | 75075 | | |
| 075174 | 49950 | 72103 | 75078 | | |
| 096547 | 50376 | 72104 | 75089 | | |
| 096550 | 50385 | 72105 | 75090 | | |
| | 50376 | 72106 | 75234 | | |
| | 50750 | 72107 | 75238 | | |
| 10760 | 51081 | 72108 | 76239 | | |
| 11385 | 52013 | 73086 | 76240 | | |
| 13905 | 52018 | 73087 | 76241 | | |
| 15392 | 58546 | 73807 | 76560 | | |



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, UT 84145-0155

<http://www.blm.gov>



IN REPLY REFER TO:

3106

(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office

From: Acting Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

OPERATOR CHANGE WORKSHEET**ROUTING**

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change**Merger**

The operator of the well(s) listed below has changed, effective:

9/1/2004

FROM: (Old Operator):
 N5160-Inland Production Company
 Route 3 Box 3630
 Myton, UT 84052
 Phone: 1-(435) 646-3721

TO: (New Operator):
 N2695-Newfield Production Company
 Route 3 Box 3630
 Myton, UT 84052
 Phone: 1-(435) 646-3721

CA No.**Unit:****TRAVIS****WELL(S)**

| NAME | SEC | TWN | RNG | API NO | ENTITY NO | LEASE TYPE | WELL TYPE | WELL STATUS | |
|-------------------------------|-----|------|------|------------|-----------|------------|-----------|-------------|---|
| MON BUTTE FED 13-27 | 27 | 080S | 160E | 4301331611 | 10628 | Federal | WI | A | |
| MONUMENT BUTTE FED 15-27-8-16 | 27 | 080S | 160E | 4301331786 | 10628 | Federal | OW | DRL | |
| MONUMENT BUTTE FED 16-27 | 27 | 080S | 160E | 4301331899 | 10628 | Federal | OW | P | |
| FEDERAL 15-28 | 28 | 080S | 160E | 4301330779 | 10628 | Federal | WI | A | |
| FEDERAL 14-28 | 28 | 080S | 160E | 4301330792 | 10628 | Federal | OW | S | |
| WEST MONUMENT 10-28 | 28 | 080S | 160E | 4301330856 | 10628 | Federal | OW | S | |
| FEDERAL 14A-28 | 28 | 080S | 160E | 4301331372 | 10628 | Federal | WI | A | |
| TRAVIS FEDERAL 16-28 | 28 | 080S | 160E | 4301331590 | 10628 | Federal | OW | P | |
| TRAVIS FED 9-28 | 28 | 080S | 160E | 4301331941 | 10628 | Federal | WI | A | |
| TRAVIS 11-28-8-16 | 28 | 080S | 160E | 4301332333 | | Federal | OW | LA | K |
| TRAVIS 12-28-8-16 | 28 | 080S | 160E | 4301332334 | | Federal | OW | LA | K |
| TRAVIS 13-28-8-16 | 28 | 080S | 160E | 4301332335 | | Federal | OW | LA | K |
| FEDERAL 3-33 | 33 | 080S | 160E | 4301330693 | 10628 | Federal | WI | A | |
| FEDERAL 6-33 | 33 | 080S | 160E | 4301330747 | 10628 | Federal | OW | P | |
| FEDERAL 2-33 | 33 | 080S | 160E | 4301330749 | 10628 | Federal | OW | P | |
| TRAVIS FED 5-33 | 33 | 080S | 160E | 4301331435 | 10628 | Federal | WI | A | |
| TRAVIS FEDERAL 8-33 | 33 | 080S | 160E | 4301331503 | 10628 | Federal | OW | P | |
| TRAVIS FED 1-33 | 33 | 080S | 160E | 4301331603 | 10628 | Federal | WI | A | |
| MON FED 5-34 | 34 | 080S | 160E | 4301331499 | 10628 | Federal | WI | A | |
| MONUMENT BUTTE FED 6-34 | 34 | 080S | 160E | 4301331504 | 10628 | Federal | OW | P | |
| MON BUTTE FED 3-34 | 34 | 080S | 160E | 4301331518 | 10628 | Federal | WI | A | |
| MONUMENT BUTTE FED 4-34 (I) | 34 | 080S | 160E | 4301331669 | 10628 | Federal | OW | P | |

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919

2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05



November 19, 2010

Mr. Dan Jarvis
State of Utah
Division of Oil, Gas and Mining
Post Office Box 145801
Salt Lake City, Utah 84114-5801

RE: Permit Application for Water Injection Well
Travis Federal #6-33-8-16
Monument Butte Field, Lease #UTU-34173
Section 33-Township 8S-Range 16E
Duchesne County, Utah

Dear Mr. Jarvis:

Newfield Production Company herein requests approval to convert the Travis Federal #6-33-8-16 from a producing oil well to a water injection well in the Monument Butte (Green River) Field.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,

A handwritten signature in black ink, appearing to read "Eric Sundberg". The signature is fluid and cursive, with a long horizontal stroke extending to the right.

Eric Sundberg
Regulatory Lead

RECEIVED
NOV 29 2010
DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY
APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL
TRAVIS FEDERAL #6-33-8-16
MONUMENT BUTTE FIELD (GREEN RIVER) FIELD
LEASE #UTU-34173
NOVEMBER 19, 2010

TABLE OF CONTENTS

| | |
|---|--|
| LETTER OF INTENT | |
| COVER PAGE | |
| TABLE OF CONTENTS | |
| UIC FORM 1 – APPLICATION FOR INJECTION WELL | |
| WELLBORE DIAGRAM OF PROPOSED INJECTION | |
| WORK PROCEDURE FOR INJECTION CONVERSION | |
| COMPLETED RULE R615-5-1 QUESTIONNAIRE | |
| COMPLETED RULE R615-5-2 QUESTIONNAIRE | |
| ATTACHMENT A | ONE-HALF MILE RADIUS MAP |
| ATTACHMENT A-1 | WELL LOCATION PLAT |
| ATTACHMENT B | LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS |
| ATTACHMENT C | CERTIFICATION FOR SURFACE OWNER NOTIFICATION |
| ATTACHMENT E | WELLBORE DIAGRAM – TRAVIS FEDERAL #6-33-8-16 |
| ATTACHMENT E-1 | WELLBORE DIAGRAM – TRAVIS FEDERAL #14A-28-8-16 |
| ATTACHMENT E-2 | WELLBORE DIAGRAM – WELLS DRAW #8-32-8-16 |
| ATTACHMENT E-3 | WELLBORE DIAGRAM – TRAVIS #2-33-8-16 |
| ATTACHMENT E-4 | WELLBORE DIAGRAM – TRAVIS FEDERAL #3-33-8-16 |
| ATTACHMENT E-5 | WELLBORE DIAGRAM – TRAVIS FEDERAL #4-33R-8-16 |
| ATTACHMENT E-6 | WELLBORE DIAGRAM – TRAVIS FEDERAL #5-33-8-16 |
| ATTACHMENT E-7 | WELLBORE DIAGRAM – TRAVIS FEDERAL #7-33-8-16 |
| ATTACHMENT E-8 | WELLBORE DIAGRAM – TRAVIS FEDERAL #8-33-8-16 |
| ATTACHMENT E-9 | WELLBORE DIAGRAM – FEDERAL #13-33B-8-16 |
| ATTACHMENT E-10 | WELLBORE DIAGRAM – FEDERAL #23-33B-8-16 |
| ATTACHMENT E-11 | WELLBORE DIAGRAM – WELLS DRAW FEDERAL #Q-33-8-16 |
| ATTACHMENT E-12 | WELLBORE DIAGRAM – WELLS DRAW FEDERAL #R-33-8-16 |
| ATTACHMENT E-13 | WELLBORE DIAGRAM – FEDERAL #33-33B-8-16 |
| ATTACHMENT F | WATER ANALYSIS |
| ATTACHMENT G | FRACTURE GRADIENT CALCULATIONS |
| ATTACHMENT G-1 | FRACTURE REPORTS DATED 8/24/83-9/17/83 & 2/28/84-3/6/84 & 6/17/01-7/1/01 |
| ATTACHMENT H | WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON |
| ATTACHMENT H-1 | WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL |

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR Newfield Production Company
ADDRESS 1001 17th Street, Suite 2000
Denver, Colorado 80202

Well Name and number: Travis Federal 6-33-8-16
Field or Unit name: Monument Butte (Green River) Lease No. UTU-34173
Well Location: QQ SENW section 33 township 8S range 16E county Duchesne


Is this application for expansion of an existing project? Yes ☒ No ☐
Will the proposed well be used for: Enhanced Recovery? Yes ☒ No ☐
Disposal? Yes ☐ No ☒
Storage? Yes ☐ No ☒
Is this application for a new well to be drilled? Yes ☐ No ☒
If this application is for an existing well,
has a casing test been performed on the well? Yes ☐ No ☒
Date of test: _____
API number: 43-013-30747

Proposed injection interval: from 4287 to 6122
Proposed maximum injection: rate 500 bpd pressure 1167 psig
Proposed injection zone contains ☒ oil, ☐ gas, and/or ☐ fresh water within 1/2
mile of the well.

IMPORTANT: Additional information as required by R615-5-2 should
accompany this form.

List of Attachments: Attachments "A" through "H-1"

I certify that this report is true and complete to the best of my knowledge.

Name: Eric Sundberg Signature 
Title Regulatory Lead Date 11/22/10
Phone No. (303) 893-0102

(State use only)
Application approved by _____ Title _____
Approval Date _____

Comments:

Federal #6-33

Spud Date: 8/3/83
Put on Production: 9/7/83
GL: 5678' KB: 5688'

Proposed Injection Wellbore Diagram

INITIAL PRODUCTION: 22 bopd, 3 bwpd

SURFACE CASING


CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (281')
DEPTH LANDED: 280'
HOLE SIZE: 12 1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 17.0#
LENGTH: 154 jts.
DEPTH LANDED: 6168'
HOLE SIZE: 7 7/8"
CEMENT DATA: 453 sk RFC & 155 sxs lodense.
CEMENT TOP AT: 1965'

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 180 jts (5682.1')
TUBING ANCHOR: 5766.41'
NO. OF JOINTS: 2 jts (63.7')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: 5462.9' KB
NO. OF JOINTS: 3 jt (91.4')
TOTAL STRING LENGTH: EOT @ 5856'



FRAC JOB

| | | |
|------------|-----------|--|
| 8/25/83 | 5932'-60' | Frac as follows: 116,000# 20/40 sand in 631 bbls fluid. Perfs broke down @ 2600 psi. |
| | 5057'-66' | Frac as follows: 62,640# 20/40 sand in 460 bbls fluid. |
| 6/20/01 | 6010'-46' | Break CP-3 sands - no frac |
| 6/20/01 | 5652'-66' | Frac L.ODC sands as follows: 19,595# 20/40 sand in 233 bbls Viking I-25 fluid. Treated @ avg press of 5640 psi w/avg rate of 14.7 BPM. Screened out. |
| 6/21/01 | 5450'-58' | Frac A-1 sands as follows: 40,600# 20/40 sand in 256 bbls Viking I-25 fluid. Treated @ avg press of 3900 psi w/avg rate of 14.6 BPM. Screened out. |
| 6/22/01 | 5184'-94' | Frac C sands as follows: 37,413# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 3500 psi w/avg rate of 15.2 BPM, ISIP 3040 psi. |
| 6/25/01 | 4505'-55' | Frac GB sands as follows: 112,834# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 2140 psi w/avg rate of 30.9 BPM, ISIP 2330 psi. |
| 9/29/01 | | Pump change. Update rod and tubing details. |
| 10/16/01 | | Tubing leak. Update rod and tubing details. |
| 10/29/01 | | Pump change. Update rod, tubing and fill details. |
| 11/21/01 | | Parted rods. Update rod and fill details. |
| 8/24/02 | | Pump change. Update rod and fill details |
| 12/03/03 | | Pump change. Update rod detail. |
| 3/19/04 | | Pump change and bail sand. Update rod and tubing detail. |
| 08/24/2004 | | Pump change. Updated rod detail. |
| 6/30/2010 | | Parted Rods. Update rod and tubing details. |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|----------|
| 8/25/83 | 5932'-5960' | 1 JSPF | 28 holes |
| ... | 5057'-5066' | 4 JSPF | 44 holes |
| 6/19/01 | 6040'-6066' | 4 JSPF | 24 holes |
| 6/19/01 | 6010'-6018' | 4 JSPF | 32 holes |
| 6/19/01 | 5652'-5666' | 4 JSPF | 56 holes |
| 6/19/01 | 5450'-5458' | 4 JSPF | 32 holes |
| 6/19/01 | 5184'-5194' | 4 JSPF | 40 holes |
| 6/19/01 | 4544'-4555' | 4 JSPF | 44 holes |
| 6/19/01 | 4505'-4519' | 4 JSPF | 56 holes |



Federal #6-33

1982' FNL & 1978' FWL
SE/NW Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-30747; Lease #UTU-34173

JL 11/18/10

WORK PROCEDURE FOR INJECTION CONVERSION

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down and move out.

**REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1**

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.**
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:**

2.1 The name and address of the operator of the project.

Newfield Production Company
1001 17th Street, Suite 2000
Denver, Colorado 80202

2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.

See Attachment A.

2.3 A full description of the particular operation for approval is requested.

Approval is requested to convert the Travis Federal #6-33-8-16 from a producing oil well to a water injection well in Monument Butte (Green River) Field.

2.4 A description of the pools from which the identified wells are producing or have produced.

The proposed injection well will inject into the Green River Formation.

2.5 The names, description and depth of the pool or pools to be affected.

The injection zone is in the Green River Formation. For the Travis Federal #6-33-8-16 well, the proposed injection zone is from Garden Gulch to Castle Peak (4287' - 6122'). The confining strata directly above and below the injection zones are the Garden Gulch and the top of the Wasatch Formation or TD, which ever is shallower. The Garden Gulch Marker top is at 3950' and the TD is at 6200'.

2.6 A copy of a log of a representative well completed in the pool.

The referenced log for the Travis Federal #6-33-8-16 is on file with the Utah Division of Oil, Gas and Mining.

- 2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

- 2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.**

See Attachment B.

- 2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.**

See Attachment C.

- 2.10 Any additional information the Board may determine is necessary to adequately review the petition.**

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

- 4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.**

This proposed injection well is on a Federal lease (Lease #UTU-34173) in the Monument Butte Federal (Green River) Field, and this request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL,
STORAGE AND ENHANCED RECOVERY WELLS
SECTION V – RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**

- 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.

- 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

All logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.

- 2.4 Copies of logs already on file with the Division should be referenced, but need not be refilled.**

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The casing program is 8-5/8", 24# surface casing run to 280' KB, and 5-1/2", 15.5# casing run from surface to 6168' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.

- 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.

- 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

See Attachment F.

The proposed average and maximum injection pressures.

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 1167 psig.

2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.

The minimum fracture gradient for the Travis Federal #6-33-8-16, for existing perforations (4505' - 6046') calculates at 0.67 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 1167 psig. We may add additional perforations between 3950' and 6200'. See Attachments G and G-1.

2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.

In the Travis Federal #6-33-8-16, the proposed injection zone (4287' - 6122') is in the Garden Gulch to the Castle Peak of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Federal Field. Outside the Monument Butte Federal Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.

See Attachments E through E-13.


Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.

2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.

See Attachment C.

2.12 Any other information that the Board or Division may determine is necessary to adequately review the application.

Newfield Production Company will supply any requested information to the Board or Division.



6-33-8-16 1/2 mile radius

Well Status

-  Location
-  CTI
-  Surface Spud
-  Drilling
-  Waiting on Completion
-  Producing Oil Well
-  Producing Gas Well
-  Water Injection Well
-  Dry Hole
-  Temporarily Abandoned
-  Plugged & Abandoned
-  Shut In
-  Countyline

Injection system

- high pressure
 — low pressure
 - - - proposed
 — return
 - - - return proposed
 □ Leases
 ■ Mining tracts
 Gas Pipelines
 — Gathering lines
 - - - Proposed lines

UTU-
34173

UTU -
49092

MA-
21836

SL-
071 752:

UTJ-
26026A

Federal 6-33
Section 33, T8S-R16E



1/2 Mile Radius Map

Duchesne & Uintah Counties

1001 17th Street Suite 2000
Denver, Colorado 80202
Phone: (303) 893-0102


October 5, 2010

T 8 S , R 16 E , S.L.B.&M.

PROJECT
LOMAX EXPLORATION CO.

Well location, **WEST MONUMENT**
FED. # 6 - 33, located as shown in
the SE 1/4 NW 1/4 Section 33, T 8 S,
R 16 E, S.L.B.&M. Duchesne County,
Utah.

ATTACHMENT A-1



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

Lawrence C. Key
REGISTERED LAND SURVEYOR
REGISTRATION NO. 3137
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P. O. BOX Q - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

| | | | |
|---------|---------------------|------------|----------|
| SCALE | 1" = 1000' | DATE | 2/16/83 |
| PARTY | R.K. D.B. J.K. S.B. | REFERENCES | GLO Plat |
| WEATHER | Cold | FILE | LOMAX |

X = Section Corners Located

ATTACHMENT B


| # | Legal Description | Lessor & Expiration | Lessee & Operating Rights | Surface Owner |
|---|---|----------------------------------|---|---------------|
| 1 | <u>T8S,R16E SLM</u> Section 33: N2 | USA UTU-34173 HBP | Newfield Production Company Newfield RMI LLC | USA |
| 2 | <u>T8S,R16E SLM</u> Section 33: S2 | USA UTU-49092 HBP | Newfield Production Company Newfield RMI LLC | USA |
| 3 | <u>T8S,R16E SLM</u> Section 32: ALL | State of Utah ML-21836 HBP | Newfield Production Company Newfield RMI LLC Ocean Energy, Inc. HC Buie James Fischer Four M Company Margaret Merrit Michael D Lewis Z Greenburg, Trustee Donna L. Neifeh Merrit Oil & Gas Thomas K. Lowe Gavilan Petroleum Producers Pipeline Corp. | State of Utah |
| 4 | <u>T8S,R16E SLM</u> Section 28: SW, N2SE | USA SL-071572-A HBP | Newfield Production Company Newfield RMI LLC Loex Properties 1983 Travis Oil Company War-Gal LLC | USA |
| 5 | <u>T8S,R16E SLM</u> Section 28: S2SE | USA UTU-26026-A HBP | Newfield Production Company Newfield RMI LLC Loex Properties 1983 Travis Oil Company War-Gal LLC | USA |

ATTACHMENT C


CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE: Application for Approval of Class II Injection Well
Travis Federal #6-33-8-16


I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed: 
Newfield Production Company
Eric Sundberg
Regulatory Lead

Sworn to and subscribed before me this 22nd day of November, 2010.

Notary Public in and for the State of Colorado: 

My Commission Expires 02/10/2013



Federal #6-33

Spud Date: 8/3/83
Put on Production: 9/7/83
GL: 5678' KB: 5688'

Wellbore Diagram

INITIAL PRODUCTION: 22 bopd, 3 bwpd

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (281')
DEPTH LANDED: 280'
HOLE SIZE: 12 1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING


CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 17.0#
LENGTH: 154 jts.
DEPTH LANDED: 6168'
HOLE SIZE: 7 7/8"
CEMENT DATA: 453 sk RFC & 155 sxs lodense.
CEMENT TOP AT: 1965'

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 180 jts (5682.1')
TUBING ANCHOR: 5766.41'
NO. OF JOINTS: 2 jts (63.7')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: 5462.9' KB
NO. OF JOINTS: 3 jt (91.4')
TOTAL STRING LENGTH: EOT @ 5856'

SUCKER RODS

POLISHED ROD: 1 1/2" x 22' SM
SUCKER RODS: 6- 1 1/2" weight bars, 225- 3/4" guided rods, 2-4', 1-8" x 3/4" pony rods.
PUMP SIZE: 2 1/2" x 1 1/2" x 12' x 16' RTBC Magyver pump
STROKE LENGTH: 74"
PUMP SPEED, SPM: 5 SPM
LOGS: DIGL/SP/GR/CAL

FRAC JOB

| | | |
|------------|-----------|--|
| 8/25/83 | 5932'-60' | Frac as follows: 116,000# 20/40 sand in 631 bbls fluid. Perfs broke down @ 2600 psi. |
| | 5057'-66' | Frac as follows: 62,640# 20/40 sand in 460 bbls fluid. |
| 6/20/01 | 6010'-46' | Break CP-3 sands - no frac |
| 6/20/01 | 5652'-66' | Frac LODC sands as follows: 19,595# 20/40 sand in 233 bbls Viking I-25 fluid. Treated @ avg press of 5640 psi w/avg rate of 14.7 BPM. Screened out. |
| 6/21/01 | 5450'-58' | Frac A-1 sands as follows: 40,500# 20/40 sand in 256 bbls Viking I-25 fluid. Treated @ avg press of 3900 psi w/avg rate of 14.6 BPM. Screened out. |
| 6/22/01 | 5184'-94' | Frac C sands as follows: 37,413# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 3500 psi w/avg rate of 15.2 BPM, ISIP 3040 psi. |
| 6/25/01 | 4505'-55' | Frac GB sands as follows: 112,834# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 2140 psi w/avg rate of 30.9 BPM, ISIP 2330 psi. |
| 9/29/01 | | Pump change. Update rod and tubing details. |
| 10/16/01 | | Tubing leak. Update rod and tubing details. |
| 10/29/01 | | Pump change. Update rod, tubing and fill details. |
| 11/21/01 | | Parted rods. Update rod and fill details. |
| 8/24/02 | | Pump change. Update rod and fill details. |
| 12/03/03 | | Pump change. Update rod detail. |
| 3/19/04 | | Pump change and bail sand. Update rod and tubing detail. |
| 08/24/2004 | | Pump change. Updated rod detail. |
| 6/30/2010 | | Parted Rods. Update rod and tubing details. |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|----------|
| 8/25/83 | 5932'-5960' | 1 JSFP | 28 holes |
| | 5057'-5066' | 4 JSFP | 44 holes |
| 6/19/01 | 6040'-6066' | 4 JSFP | 24 holes |
| 6/19/01 | 6010'-6018' | 4 JSFP | 32 holes |
| 6/19/01 | 5652'-5666' | 4 JSFP | 56 holes |
| 6/19/01 | 5450'-5458' | 4 JSFP | 32 holes |
| 6/19/01 | 5184'-5194' | 4 JSFP | 40 holes |
| 6/19/01 | 4544'-4555' | 4 JSFP | 44 holes |
| 6/19/01 | 4505'-4519' | 4 JSFP | 56 holes |

NEWFIELD

Federal #6-33

1982' FNL & 1978' FWL

SE/NW Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-30747; Lease #UTU-34173

CB 7/21/2010

Travis Fed 14A-28-8-16

Spud Date: 10/5/92
 Put on Injection: 10/13/93
 GL: 5617' KB: 5629'

SURFACE CASING


CSG SIZE: 8 5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (303.61')
 DEPTH LANDED: 301.71'
 HOLE SIZE: 12 1/4"
 CEMENT DATA: 516 sxs Class G cmt, est 15 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5 1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 150 jts. (6171.57')
 DEPTH LANDED: 6168.27' KB
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 148 sxs Hilift mixed & 353 sxs 50/50 Poz/G mixed
 236 sxs Hilift mixed & 133 sxs 50/50 Poz/G mixed
 CEMENT TOP AT: Surface

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
 NO. OF JOINTS: 160 jts (4939.02')
 SEATING NIPPLE: 2 7/8" (1.10')
 SN LANDED AT: 4951.02' KB
 PACKER: 4955.32'
 TOTAL STRING LENGTH: EOT @ 4959.32'

Injection Well
Wellbore Diagram

Initial Production: 147 BOPD,
 170 MCFPD, 5 BWPD

FRAC JOB

| | |
|----------|--|
| 10-5-92 | Spud Well |
| 12-1-92 | Perf: 5,666'-5,670' |
| 12-2-92 | Squeeze LODC zone and as follows: Squeezed with 100 sxs"G" cement |
| 12-4-92 | Perf: 5,590'-5,598' |
| 12-10-92 | Frac LODC zone as follows: Total 8,400 gal, 22,300# 16/30 sd Max TP 2,800 @ 20 BPM Avg TP 2,100 @ 20 BPM ISIP 2,050, after 5 min. 2,000 |
| 12-16-92 | Perf: 5,046'-5,054' |
| 12-17-92 | Frac D-2 zone as follows: Totals 13,200 gal, 33,000# 16/30sd Max TP 5,000 @ 20 BPM Avg TP 2,200 @ 19 BPM ISIP 2,500, after 5 min. 2,350 |
| 10-13-93 | Converted to Water Injector |
| 5/28/03 | Packer leak. Update tubing detail. |
| 6/04/03 | Update entire WBD. |
| 4/16/08 | 5 Year MIT completed and submitted. |

PERFORATION RECORD

| | | | |
|----------|-------------|--------|----------|
| 12/01/92 | 5666'-5670' | 4 JSPF | 16 holes |
| 12/04/92 | 5590'-5598' | 4 JSPF | 32 holes |
| 12/16/92 | 5046'-5054' | 4 JSPF | 32 holes |

NEWFIELD

Travis Federal #14A-28-8-16
 2273' FWL & 107' FSL
 SE/SW Section 28-T8S-R16E
 Duchesne Co, Utah

API # 43-013-31372; Lease # SL-071572A

Wells Draw 8-32-8-16

Spud Date: 4/27/2004
 Put on Production: 7/9/2004
 GL: 5711' KB:5723'

Initial Production: BOPD,
 MCFD, BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (312.77')
 DEPTH LANDED: 322.77' KB
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 150sxs Class "G" cmt, est 1 bbl cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 149 jts. (6349.39')
 DEPTH LANDED: 6347.39' KB
 HOLE SIZE: 7 7/8"
 CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix
 CEMENT TOP AT: Surface

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 189 jts (5954.23')
 TUBING ANCHOR: 5966.23' KB
 NO. OF JOINTS: 2 jts (63.20')
 SEATING NIPPLE: 2 7/8" (1.10')
 SN LANDED AT: 6032.20' KB
 NO. OF JOINTS: 2 jts (63.20')
 TOTAL STRING LENGTH: EOT @ 6096.50' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1 1/2" x 22'
 SUCKER RODS: 1- 2', 1-6', 2-8', x 3/4" pony rod, 100-3/4" guided rods; 86-3/4" Sucker rods, 48- 3/4" guided rods, 6-1 1/2" sinker bars.
 PUMP SIZE: 2 1/2" x 1 1/2" x 16' RHAC pump w/ SM Plunger
 STROKE LENGTH: 86"
 PUMP SPEED, SPM: 5 SPM

FRAC JOB

6/28/04 5914'-6054' **Frac CP4, 3, 2 AND 1 sands as follows:**
 78,979# 20/40 sand in 610 bbls lightning Frac 17 fluid. Treated @ avg press of 1635 psi w/avg rate of 24.7 BPM. ISIP 2000 psi. Calc flush: 5912 gal. Actual flush: 5914 gal.

6/29/04 5594'-5684' **Frac LODC sands as follows:**
 99,277# 20/40 sand in 725 bbls lightning Frac 17 fluid. Treated @ avg press of 2360 psi w/avg rate of 24.7 BPM. ISIP 3150 psi. Calc flush: 5592 gal. Actual flush: 5590 gal.

6/30/04 5403'-5438' **Frac A3 and 1 sands as follows:**
 44,757# 20/40 sand in 416 bbls lightning Frac 17 fluid. Treated @ avg press of 1775 psi w/avg rate of 24.6 BPM. ISIP 2025 psi. Calc flush: 5401 gal. Actual flush: 5401 gal.


6/30/04 5208'-5272' **Frac B2 and .5 sands as follows:**
 54,668# 20/40 sand in 460 bbls lightning Frac 17 fluid. Treated @ avg press of 1640 psi w/avg rate of 24.8 BPM. ISIP 2150 psi. Calc flush: 5206 gal. Actual flush: 5204 gal.

6/30/04 4412'-4418' **Frac GB4 sands as follows:**
 36,665# 20/40 sand in 326 bbls lightning Frac 17 fluid. Treated @ avg press of 2090 psi w/avg rate of 24.7 BPM. ISIP 4170 psi. Calc flush: 4410 gal. Actual flush: 4326 gal.

1/6/05 Stuck pump. Update rod details.
 11/16/07 Major Workover. Rod & Tubing details updated.
 1/20/09 Parted rods. Updated R & T details.
 07/19/10 Parted rods. Rod & Tubing updated.
 09/02/10 Pump Change. Rod & tubing detail updated.

PERFORATION RECORD

| | | | |
|---------|------------|--------|----------|
| 6/28/04 | 6046-6054' | 4 JSPF | 32 holes |
| 6/28/04 | 6022-6026' | 4 JSPF | 16 holes |
| 6/28/04 | 5952-5958' | 4 JSPF | 24 holes |
| 6/28/04 | 5914-5924' | 4 JSPF | 40 holes |
| 6/29/04 | 5664-5684' | 4 JSPF | 80 holes |
| 6/29/04 | 5594-5604' | 4 JSPF | 40 holes |
| 6/30/04 | 5432-5438' | 4 JSPF | 24 holes |
| 6/30/04 | 5403-5414' | 4 JSPF | 44 holes |
| 6/30/04 | 5265-5272' | 4 JSPF | 28 holes |
| 6/30/04 | 5208-5212' | 4 JSPF | 16 holes |
| 6/30/04 | 4412-4418' | 4 JSPF | 24 holes |

**NEWFIELD**

Wells Draw Unit 8-32-8-16

1969' FNL & 710' FEL

SE/NE Section 32-T8S-R16E

Duchesne Co, Utah

API #43-013-32219; Lease #ML-21836

TW 10/10/10

Travis #2-33-8-16

Spud Date: 5/31/83
Put on Production: 7/17/83
GL: 5627' KB: 5641'

Wellbore Diagram

Initial Production: 11 BOPD, NM MCFD, 2 BWPD
1994 Recompletion IP: 37 BOPD, 17 MCFD, 1 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
DEPTH LANDED: 291'
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sxs Class "G" cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 152 jts. (6141')
DEPTH LANDED: 6148' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 225 sxs Hifill & 300 sxs Thixotropic.
CEMENT TOP AT: 1530' per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 178 jts (5779.68')
TUBING ANCHOR: 5795' KB
NO. OF JOINTS: 1 jt. (')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5830' KB
NO. OF JOINTS: 1 jt. (')
TOTAL STRING LENGTH: EOT @ 5863.97' KB

SUCKER RODS


POLISHED ROD: 1-1 1/2"
SUCKER RODS: 2', 8', 8', x 3/4" pony rods, 225- 3/4" guided rods, 6- 1 1/2" weighted rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 14" RHAC
STROKE LENGTH: 58"
PUMP SPEED, SPM: 3 SPM

FRAC JOB

| | | |
|---------|-------------|---|
| 6/24/83 | 5923'-5966' | Frac zone as follows: 97,520# sand in 659 bbls 5% KCl. Treated @ avg press of 2200 psi w/avg rate of 31 BPM. ISIP 1890 psi. Calc. flush: 5923 gal. Actual flush: 6100 gal. |
| 7/01/83 | 5707'-5773' | Frac zone as follows: 172,000# sand in 1214 bbls 3% KCl. Treated @ avg press of 3200 psi w/avg rate of 45 BPM. Calc. flush: 5707 gal. Actual flush: 18300 gal. Screened out w/ 2500' sand in casing. |
| 3/13/94 | 4468'-4525' | Frac zone as follows: 45,500# sand in 447 bbls 5% KCl. Treated @ avg press of 4200 psi w/avg rate of 21 BPM. ISIP 2120 psi. Calc. flush: 4468 gal. Actual flush: 1134 gal. |
| 4/09/02 | | Tubing leak. Update rod and tubing details. |
| 8/5/03 | | Tubing leak. Update rod and tubing details. |
| 1/26/04 | | Tubing Leak. Update rod details. |
| 6-16-05 | | Tubing Leak: Update rod and tubing detail. |
| 6/23/09 | | Tubing Leak. Updated rod & tubing detail. |

PERFORATION RECORD

| | | | |
|---------|-------------|-------|-----------------|
| 6/23/83 | 5963'-5966' | 1 SPF | 04 holes |
| 6/23/83 | 5923'-5936' | 1 SPF | 09 holes |
| 6/29/83 | 5753'-5773' | 1 SPF | 10 holes |
| 6/29/83 | 5747'-5751' | 1 SPF | 02 holes |
| 6/29/83 | 5729'-5733' | 1 SPF | 02 holes |
| 6/29/83 | 5707'-5711' | 1 SPF | 02 holes |
| 3/03/84 | 5597'-5601' | 1 SPF | 02 holes |
| 3/03/84 | 5636'-5647' | 1 SPF | 07 holes |
| 3/03/84 | 5651'-5655' | 1 SPF | 02 holes |
| 3/06/94 | 4468'-4474' | 1 SPF | 06 holes |
| 3/06/94 | 4517'-4525' | 1 SPF | 08 holes |
| 3/10/94 | 4468'-4474' | 1 SPF | 06 holes Reperf |
| 3/10/94 | 4517'-4525' | 1 SPF | 08 holes Reperf |



NEWFIELD

Travis #2-33-8-16
751' FNL & 2169' FEL
NWNE Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-30749; Lease #U-34173


Travis Federal #3-33

Injection Well

Wellbore Diagram

Well History:

| | |
|----------|--|
| 11-9-82 | Spud Well |
| 12-1-82 | Perf: 5,917', 5,922'-5,930', 5,955'-5,959', 5,962'-5,967' |
| 12-2-82 | Frac CP-2 zone as follows: Totals 29,200 gal, 68,700# 20/40sd Max TP 3,000 @ 30 BPM Avg TP 2,400 @ 30 BPM ISIP 1,900, after 5 min. 1,800 |
| 12-8-82 | Perf: 5,650'-5,690' |
| 12-9-82 | Frac LODC as follows: Totals 39,000 gal, Max TP 4,200 Avg TP 2,850 ISIP 1,600, after 15 min. 1,450 |
| 12-10-82 | Perf: 5,562'-5,569', 5,574'-5,584', 5,588'-5,592', 5,596' |
| 12-10-92 | Frac LODC zone as follows: Total 92,930 gal, 289,440# 20/40 sd Max TP 3,900 Avg TP 3,300 ISIP 2,510, after 5 min. 2,270 |
| 10-8-93 | Converted To Water Injector |
| 02/26/08 | 5 year MIT |



NEWFIELD

Travis Federal #3-33
1967 FWL 642 FNL

NENW Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-30693; Lease #U-34173

JP 2-26-08

Travis Federal 4-33R-8-16

Spud Date: 10-03-05
Put on Production: 11-28-05

GL: 5677' KB: 5689'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts (279')
DEPTH LANDED: 290.85' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt, est 4.5 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 145 jts. (6117.49')
DEPTH LANDED: 6116.74' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 315 sxs Prem. Lite II mixed & 450 sxs 50/50 POZ.
CEMENT TOP AT: 210'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 185 jts (5890.08')
TUBING ANCHOR: 5902.08' KB
NO. OF JOINTS: 1 jts (32.44')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5937.32' KB
NO. OF JOINTS: 2 jts (65.21')
TOTAL STRING LENGTH: EOT @ 6004.08' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 1-4', 2-6', 1-8' X 3/4" pony rods, 96- 3/4" guided rods, 104- 3/4" slick rods, 30- 3/4" guided rods, 6-1 1/2" weight rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 16' RHAC w/SM plunger
STROKE LENGTH: 86"
PUMP SPEED, SPM: 4 SPM

Wellbore Diagram

Cement top @ 210'

**FRAC JOB**

01-17-06 5893-5940' **Frac CP.5, & CP1 sands as follows:**
50464# 20/40 sand in 518 bbls Lightning 17 frac fluid. Treated @ avg press of 1833 psi w/avg rate of 24.9 BPM. ISIP 2000 psi. Calc flush: 5891 gal. Actual flush: 5880 gal.

01-17-06 5172-5260' **Frac B.5, & C sands as follows:**
69439# 20/40 sand in 647 bbls Lightning 17 frac fluid. Treated @ avg press of 1922 psi w/avg rate of 24.9 BPM. ISIP 1950 psi. Calc flush: 5170 gal. Actual flush: 5208 gal.

01-17-06 5010-5106' **Frac D1, & D2 sands as follows:**
120342# 20/40 sand in 842 bbls Lightning 17 frac fluid. Treated @ avg press of 1760 psi w/avg rate of 24.8 BPM. ISIP 2270 psi. Calc flush: 5008 gal. Actual flush: 4998 gal.

01-17-06 4503-4510' **Frac GB4 sands as follows:**
17280# 20/40 sand in 270 bbls Lightning 17 frac fluid. Treated @ avg press of 2155 w/ avg rate of 24.9 BPM. ISIP 2420 psi. Calc flush: 4501 gal. Actual flush: 4410 gal.
Clean fill out. Update rod and tubing details.
Stuck pump. Pump change updated.
Parted rods. Updated rod & tubing details.

07/06/06
05-20-08
8/24/09

PERFORATION RECORD

| Date | Depth Range | Tool Joint | Holes |
|----------|-------------|------------|----------|
| 01-12-06 | 5930-5940' | 4 JSPF | 40 holes |
| 01-12-06 | 5893-5898' | 4 JSPF | 20 holes |
| 01-17-06 | 5256-5260' | 4 JSPF | 16 holes |
| 01-17-06 | 5204-5208' | 4 JSPF | 16 holes |
| 01-17-06 | 5172-5180' | 4 JSPF | 32 holes |
| 01-17-06 | 5098-5106' | 4 JSPF | 32 holes |
| 01-17-06 | 5079-5083' | 4 JSPF | 16 holes |
| 01-17-06 | 5010-5026' | 4 JSPF | 64 holes |
| 01-17-06 | 4503-4510' | 4 JSPF | 28 holes |

NEWFIELD

Travis Federal 4-33R-8-16

826' FNL & 691' FWL

NW/NW Section 33-T8S-R16E


Duchesne Co, Utah

API #43-013-30754; Lease #UTU-34173

Travis Federal 5-33-8-16

Well History:

| | |
|----------|---|
| 10-25-94 | Spud Well |
| 11-28-94 | Perf: 5,922'-5,932' Frac CP-1 zone as follows: Breakdown w/ 92 bbls 2% KCl w/ 60 1.3 ball sealers |
| 11-29-94 | Perf: 5,450'-5,462' |
| 11-30-94 | Frac A-1 zone as follows: Totals 418 BF, 35,000# 20/40 sd Max TP 2,450 @ 37 BPM Avg TP 2,050 @ 29 BPM ISIP 2,050, after 5 min 1,860 |
| 12-1-94 | Perf: 5,049'-5,078' |
| 12-2-94 | Frac D-2 zone as follows: Totals, 892 bbls, 49,000# 20/40sd 41,000# 16/30sd Max TP 2,300 Avg TP 1,850 ISIP 1,740, after 5 min. 1,270 |
| 1-25-00 | Convert to injection well |
| 2-7-00 | Put on Injection |
| 12-29-04 | 5 yr MIT |
| 12-16-09 | 5 yr MIT |

Injection Wellbore
Diagram

NEWFIELD



Travis Federal 5-33-8-16
1980 FNL 660 FWL
SWNW Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-31435; Lease #U-34173

Travis Federal 7-33-8-16

Spud Date: 8/11/08
Put on Production: 9/30/08
GL: 5675' KB: 5687'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (314.42')
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 152 jts. (6553.48')
HOLE SIZE: 7-7/8"
TOTAL DEPTH: 6585'
CEMENT DATA: 350 sk Prem. Lite II mixed & 475 sxs 50/50 POZ.
CEMENT TOP AT: 43'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 205 jts (6293.90')
TUBING ANCHOR: 6305.90'
NO. OF JOINTS: 2 jts (60.54')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 6369.21' KB
NO. OF JOINTS: 1 jts (30.94')
TOTAL STRING LENGTH: EOT @ 6401.70' w/12' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 26'
SUCKER RODS: 1-8', 6', 2' x 7/8" pony rods, 250- 7/8" guided rods, 4-1 1/2" weight rods, 1 5/8" shear cplg (21k)
PUMP SIZE: 2-1/2" x 1-3/4" x 20' RHAC pump w/ sm plunger
STROKE LENGTH: 122"
PUMP SPEED, SPM: 5

FRAC JOB

| | | |
|---------|------------|---|
| 9/18/08 | 6348-6362' | Frac CP5 sands as follows: Frac with 29930 #'s of 20/40 sand in 433 bbls Lightning 17 fluid. Treat at an ave pressure of 2290 psi @ 22.3 BPM. ISIP 2251 psi. |
| 9/18/08 | 6198-6268' | Frac CP3/CP4 sands as follows: Frac with 41069 #'s of 20/40 sand in 437 bbls Lightning 17 fluid. Treat at an ave pressure 2043 psi @ 22.3 BPM. ISIP 2281 psi. |
| 9/18/08 | 6020-6122' | Frac CP.5/CP1/CP2 sands as follows: Frac with 80655 #'s of 20/40 sand in 655 bbls Lightning 17 fluid. Treat at an ave pressure of 1716 psi @ 22.2 BPM. ISIP 2041 psi. |
| 9/19/08 | 5864-5894' | Frac LODC sands as follows: Frac with 60618 #'s of 20/40 sand in 544 bbls Lightning 17 fluid. Treat at an ave pressure of 2884 psi @ 22.0 BPM. ISIP 3451 psi. |
| 9/19/08 | 5544-5560' | Frac A1 sands as follows: Frac with 50355 #'s of 20/40 sand in 466 bbls Lightning 17 fluid. Treat at an ave pressure of 2193 psi @ 26.0 BPM. ISIP 2376 psi. |
| 9/19/08 | 5406-5414' | Frac B2 sands as follows: Frac with 35472 #'s of 20/40 sand in 386 bbls Lightning 17 fluid. Treat at an ave pressure of 1917 psi @ 20.2 BPM. ISIP 2058 psi. |
| 9/19/08 | 5286-5294' | Frac C sands as follows: Frac with 34983 #'s of 20/40 sand in 380 bbls Lightning 17 fluid. Treat at an ave pressure of 1890 psi @ 25.6 BPM. ISIP 2632 psi. |
| 9/19/08 | 5164-5174' | Frac D2 sands as follows: Frac with 40293 #'s of 20/40 sand in 412 bbls Lightning 17 fluid. Treat at an ave pressure of 1722 psi @ 22.2 BPM. ISIP 2226 psi. |
| 9/19/08 | 4814-4820' | Frac PB10 sands as follows: Frac with 24266 #'s of 20/40 sand in 348 bbls Lightning 17 fluid. Treat at an ave pressure of 2195 psi @ 24.1 BPM. ISIP 2317 psi. |
| 9/19/08 | 4602-4636' | Frac GB6 sands as follows: Frac with 31811 #'s of 20/40 sand in 366 bbls Lightning 17 fluid. Treat at an ave pressure of 1819 psi @ 22.4 BPM. ISIP 2064 psi. |

PERFORATION RECORD

| | | |
|------------|--------|-----------|
| 4602-4616' | 4 JSPF | 56 holes |
| 4632-4636' | 4 JSPF | 16 holes |
| 4814-4820' | 4 JSPF | 24 holes |
| 5164-5174' | 4 JSPF | 40 holes |
| 5286-5294' | 4 JSPF | 32 holes |
| 5406-5414' | 4 JSPF | 32 holes |
| 5544-5560' | 4 JSPF | 64 holes |
| 5864-5876' | 4 JSPF | 48 holes |
| 5888-5894' | 4 JSPF | 24 holes |
| 6020-6024' | 4 JSPF | 16 holes |
| 6060-6074' | 4 JSPF | 56 holes |
| 6098-6104' | 4 JSPF | 24 holes |
| 6116-6122' | 4 JSPF | 24 holes |
| 6198-6206' | 4 JSPF | 320 holes |
| 6260-6268' | 4 JSPF | 322 holes |
| 6348-6362' | 4 JSPF | 56 holes |

NEWFIELD

Travis Federal 7-33-8-16
1997' FNL & 1976' FWL
SENW Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-32798; UUTU-34173

Travis Fed. #8-33-8-16

Spud Date: 1/9/1996
Put on Production: 2/4/1996

GL: 5594' KB: 5607'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
DEPTH LANDED: 302'
HOLE SIZE: 12-1/4"
CEMENT DATA: 170 sxs Type V + 100 sxs Neat

PRODUCTION CASING


CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
DEPTH LANDED: 6179'
HOLE SIZE: 7-7/8"
CEMENT DATA: 260 sxs Hifill & 320 sxs Thixotropic.
CEMENT TOP AT: 540'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55
NO. OF JOINTS: 184 jts (5783.7')
TUBING ANCHOR: 5783.7'
NO. OF JOINTS: 2 jts (61.8')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: (5848.3')
NO. OF JOINTS: 2 jts (63')
TOTAL STRING LENGTH: EOT @ 5913'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 1-2' x 3/4" pony rod, 1-4' x 3/4" pony rod, 94- 3/4" guided rods,
62- 3/4" sucker rods, 71- 3/4" guided rods, 6- 1 1/2" sinker bars
PUMP SIZE: 2 1/2" x 1 1/2" x 12' x 16' RHAC
STROKE LENGTH: 64"
PUMP SPEED, SPM: 4 SPM

Wellbore Diagram**FRAC JOB**

| | | |
|-----------|-------------|---|
| 1/26/96 | 5884'-5896' | Frac CP sand as follows: 69,900# 20/40 sand in 558 bbls fluid. Treated @ avg press of 1600 psi w/avg rate of 26 BPM. ISIP 2009 psi. Calc flush: 5884 gal, Actual flush: 5806 gal. |
| 1/29/96 | 5569'-5653' | Frac LODC sand as follows: 144,900# 20/40 sand in 970 bbls fluid. Treated @ avg press of 2800 psi w/avg rate of 37 BPM. ISIP 2921 psi. Calc flush: 5569 gal, Actual flush: 5493 gal. |
| 1/31/96 | 5383'-5425' | Frac A sand as follows: 77,200# 20/40 sand in 585 bbls fluid. Treated @ avg press of 2290 psi w/avg rate of 32 BPM. ISIP 2412 psi. Calc flush: 5383 gal, Actual flush: 5284 gal. |
| 2/01/96 | 5238'-5270' | Frac B sand as follows: 64,200# 20/40 sand in 494 bbls fluid. Treated @ avg press of 2130 psi w/avg rate of 20.7 BPM. ISIP 2130 psi. Calc flush: 5238 gal, Actual flush: 5174 gal. |
| 6/07/02 | 5836'-5848' | Frac CP 0.5 sand as follows: 18,500# 20/40 sand in 163 bbls fluid. Treated @ avg press of 3625 psi w/avg rate of 15.9 BPM. ISIP 2180 psi. Calc flush: 1473 gal, Actual flush: 1386 gal. |
| 6/07/02 | 5681'-5716' | Frac LODC sand as follows: 60,000# 20/40 sand in 390 bbls fluid. Treated @ avg press of 3700 psi w/avg rate of 11.2 BPM. ISIP 3670 psi. Calc flush: 1384 gal, Actual flush: 1302 gal. |
| 6/07/02 | 5532'-5653' | Frac LODC sand as follows: 134,420# 20/40 sand in 820 bbls fluid. Treated @ avg press of 5250 psi w/avg rate of 19.7 BPM. ISIP 3650 psi. Calc flush: 1394 gal, Actual flush: 1302 gal. |
| 6/08/02 | 5100'-5196' | Frac C sands as follows: 54,200# 20/40 sand in 221 bbls fluid. Treated @ avg press of 2250 psi w/avg rate of 26.5 BPM. ISIP 2600 psi. Calc flush: 5100 gal, Actual flush: 4998 gal. |
| 6/08/02 | 4982'-4988' | Frac D sand as follows: 34,220# 20/40 sand in 221 bbls fluid. Treated @ avg press of 2050 psi w/avg rate of 24.1 BPM. ISIP 2250 psi. Calc flush: 4982 gal, Actual flush: 4918 gal. |
| 10-19-07 | | Tubing Leak. Updated rod & tubing details. |
| 11/14/03 | | Parted rods update: Pump Changed. Updated rod and tubing detail. |
| 1/29/2010 | | |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|-----------|
| 1/26/96 | 5884'-5896' | 4 JSPF | 48 holes |
| 1/27/96 | 5626'-5653' | 4 JSPF | 108 holes |
| 1/27/96 | 5607'-5618 | 4 JSPF | 44 holes |
| 1/27/96 | 5590'-5595' | 4 JSPF | 20 holes |
| 1/27/96 | 5583'-5586' | 4 JSPF | 12 holes |
| 1/27/96 | 5569'-5574' | 4 JSPF | 20 holes |
| 1/31/96 | 5416'-5425' | 4 JSPF | 36 holes |
| 1/31/96 | 5383'-5392' | 4 JSPF | 36 holes |
| 2/01/96 | 5259'-5270' | 4 JSPF | 44 holes |
| 2/01/96 | 5238'-5244' | 4 JSPF | 24 holes |
| 6/06/02 | 5842'-5848' | 4 JSPF | 24 holes |
| 6/06/02 | 5836'-5839' | 4 JSPF | 12 holes |
| 6/06/02 | 5681'-5716' | 2 JSPF | 70 holes |
| 6/06/02 | 5532'-5538' | 4 JSPF | 24 holes |
| 6/08/02 | 5190'-5196' | 4 JSPF | 24 holes |
| 6/08/02 | 5170'-5173' | 4 JSPF | 12 holes |
| 6/08/02 | 5111'-5114' | 4 JSPF | 12 holes |
| 6/08/02 | 5106'-5108' | 4 JSPF | 08 holes |
| 6/08/02 | 5100'-5104' | 4 JSPF | 16 holes |
| 6/08/02 | 4982'-4988' | 4 JSPF | 24 holes |

NEWFIELD**Travis Federal #8-33-8-16**

2073' FNL & 623' FEL

SENE Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-31503; Lease #U-34173

Federal #13-33B-8-16

Spud Date: 6/22/90
Put on Production: 10/3/90
GL: 5710' KB: 5725'

Initial Production: 116 BOPD,
0 MCFPD, 181 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8" / K-55 / 24#
DEPTH LANDED: 306' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 210 sx Class "G" cmt w/2% CaCl₂

PRODUCTION CASING

CSG SIZE: 5-1/2" / K-55 / 17#
SET AT: 6384'
HOLE SIZE: 7-7/8"
CEMENT DATA: Lead 180 sx Hi-Lift, tail w/445 10-0 RFC
CEMENT TOP AT: 970'

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: J-55 109 jts. (3365.29')
NO. OF JOINTS: 68 jts (2186.12')
TUBING ANCHOR: 2.80' @ 5566.41' KB
NO. OF JOINTS: 1 jts. 31.40'
SEATING NIPPLE: 1.10' @ 5600.71' KB
NO. OF JOINTS: 2 jts. 63.45'
TOTAL STRING LENGTH: EOT @ 5665.61'

SUCKER RODS

POLISHED ROD: 1 1/4" X 22"

SUCKER RODS: 2-8", 1-4", 1-2" x 7/8" pony rods, 85-7/8" scraped rods, 49-3/4" plain rods, 22-3/4" scraped rods, 5-1 5/8" weight bars, 1-1 1/2" weight bars.

PUMP SIZE: 2-1/2"x1-1/2"x 14.5" RHAC

STROKE LENGTH: 60"

PUMP SPEED, SPM: 7 SPM


LOGS: DIGL, CDL-DSN, CBL

FRAC JOB

| | |
|-------------|--|
| 5925'-5950' | 29,100# 20/40, 43,000# 16/30. |
| 5437'-5473' | 47,000# 20/40, 68,000# 16/30. |
| 4966'-5045' | 81,600# 20/40, 101,400# 16/30. |
| 1758'-1780' | Acidize w/3000 gal 15% HCl acid w/Cla-Sta & iron seq. Perfs broke @ 2027 psi, avg 15 bpm, 2200 psi avg press, 3850 psi max press. Run 130 balls, good ball action. |
| 1624'-1715' | Pump 6000 gal 15% HCl acid w/Cla-Sta & iron seq & 225 ball sealers, very little ball action. Well was on vac @ end of treatment. |
| 5140'-5200' | Frac w/118,300# 20/40 sd in 508 bbls Delta Frac. Perfs broke dn @ 3960 psi. Treated @ ave sfc press of 6700 psi w/ave rate of 27 bpm. ISIP: 2345 psi, 5 min: 1875 psi. Flowback on 12/64" choke for 1-1/2 hrs & died. Rec 19 BTF (est 4% of load). |
| 2/5/02 | Tubing leak. Update rod and tubing details. |
| 9/10/02 | Tubing leak. Updated rod and tubing details. |
| 2/26/03 | 6122'-6184' Frac BS and CP5 sands as follows: 40,735# of 20/40 sand in 330 bbls YF 125 fluid. Treated @ ave pressure 4193 psi W/ave rate of 17 BPM. ISIP-2349psi. Calc. flush: 1610 gals. Actual flush: 1405 gals. |
| 2/27/03 | 5572'-5597' Frac LODOC sands as follows: 31,897# of 20/40 sand in 288 bbls YF 125 fluid. Treated @ ave pressure 4621 psi W/ave rate of 17.1 BPM. ISIP-3400 psi. Calc. flush: 1439 gals. Actual flush: 1253 gals. |
| 2/27/03 | 4743'-4750' Frac PB11 sands as follows: 31,200# of 20/40 sand in 267 bbls YF 125 fluid. Treated @ ave pressure 3639 psi W/ave rate of 16.7 BPM. ISIP-2245 psi. Calc. flush: 1240 gals. Actual flush: 888 gals. |
| 2/27/03 | 4482'-4488' Frac GB6 sands as follows: 21,091# of 20/40 sand in 206 bbls YF 125 fluid. Treated @ ave pressure 3487 psi W/ave rate of 16.8 BPM. ISIP-2122 psi. Calc. flush: 1150 gals. Actual flush: 993 gals. |
| 9/21/04 | Parted Rods, updated rod & tubing detail. |

PERFORATION RECORD

| | | |
|-------------|--------|---------------------------|
| 5925'-5950' | 4 JSPF | 100 holes |
| 5462'-5473' | 4 JSPF | 44 holes |
| 5437'-5449' | 4 JSPF | 48 holes |
| 5036'-5045' | 4 JSPF | 36 holes |
| 5017'-5028' | 4 JSPF | 44 holes |
| 4973'-4984' | 4 JSPF | 44 holes |
| 4966'-4971' | 4 JSPF | 20 holes |
| 1758'-1780' | 4 JSPF | 88 holes Squeezed 4/10/94 |
| 1704'-1715' | 4 JSPF | 44 holes Squeezed 4/10/94 |
| 1688'-1696' | 4 JSPF | 32 holes Squeezed 4/10/94 |
| 1668'-1678' | 4 JSPF | 40 holes Squeezed 4/10/94 |
| 1624'-1642' | 4 JSPF | 72 holes Squeezed 4/10/94 |
| 5191'-5200' | 4 JSPF | 36 holes 3/11/98 |
| 5140'-5147' | 4 JSPF | 28 holes 3/11/98 |
| 4482'-4488' | 4 JSPF | 24 holes 2/25/2003 |
| 4743'-4750' | 4 JSPF | 28 holes 2/25/2003 |
| 5572'-5578' | 4 JSPF | 24 holes 2/25/2003 |
| 5595'-5597' | 4 JSPF | 8 holes 2/25/2003 |
| 6122'-6126' | 4 JSPF | 16 holes 2/25/2003 |
| 6176'-6184' | 4 JSPF | 32 holes 2/25/2003 |

**NEWFIELD****Federal #13-33B-8-16**

1972' FSL & 652' FWL

NW/SW Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-31277; Lease #U-49092

Spud Date: 12/18/89
Put on Production: 2/23/90
Put on Injection: 4/19/01

GL: 5640' KB: 5653'

Federal #23-33B-8-16

Initial Production: 60 BOPD, 0 MCFD
100 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 JTS (283')
DEPTH LANDED: 300'
HOLE SIZE: 12-1/4"
CEMENT DATA: 165 sks Class "G" cmt, est ? bbls to surface


PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: K-55
WEIGHT: 17#
LENGTH: 151 jts (6402')
HOLE SIZE: 7-7/8"
CEMENT DATA: 300 sks Hi-LiR & 575 sks 10-0 RPC
CEMENT TOP AT:
SET AT: 6402'

TUBING

SIZE/GRADE/WT: 2-7/8", J-55, 6.5#
NO. OF JOINTS: 136 jts (4297.30')
SEATING NIPPLE: 2-7/8"
SN LANDED AT: 4289.30'
TOTAL STRING LENGTH: EOT @ 4297.80'

Injection Wellbore
Diagram



FRAC JOB

| | | |
|---------|-------------|--|
| 1-27-90 | 5856'-5878' | 36,000# 20/40 sand, 42,500# 16/30 sand, and 78,500# tti sd. Avg TP 2100 psi. ISIP-2000 psi, 15 min 1817 psi. |
| 1-30-90 | 5518'-5556' | 36,000# 20/40 sand, 38,000# 16/30 sand and 74,000# tti sd. Avg TP 3000 psi. ISIP-2985 psi, 15 min 2715 psi. |
| 2-1-90 | 5347'-5377' | 78,000# 20/40 sand, 78,000# 16/30 sand, and 156,000 tti sd. Avg TP 1900 psi. ISIP-1750 psi, 15 min 1450 psi. |
| 2-3-90 | 5057'-5071' | 21,000# 20/40 SAND, 24,000# 16/30 sand, and 45,000# sd tti. Screened out 74 bbls into flush. ATP 2200 psi. |
| 2-6-90 | 4898'-4918' | 1307 bbls w/ 51,000# 20/40 sand and 51,000# 16/30 sand. BDP 2060 @ 2 BPM. Inc rate to 20 BPM. Press broke @ 3500 psi. Inc rate to 40 BPM @ 2140 psi. |
| 4/12/00 | 4352'-4436' | 469 bbls w/ 87,680# 20/40 sand. ATP 1900 @ 26 BPM. ISIP 2525 psi. Calc. flush: 4352 gal, Actual flush: 4158 gal. |
| 4/18/06 | | 5 Year MIT Completed and Submitted. |
| 7/27/06 | | Workover - Marrett squeeze treatment |
| 8/9/06 | | MIT completed and submitted. |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|-----------|
| 1-24-90 | 5856'-5878' | 4 JSPF | 88 holes |
| 1-30-90 | 5518'-5527' | 4 JSPF | 36 holes |
| 1-30-90 | 5529'-5534' | 4 JSPF | 20 holes |
| 1-30-90 | 5547'-5556' | 4 JSPF | 36 holes |
| 1-31-90 | 5347'-5377' | 4 JSPF | 120 holes |
| 2-2-90 | 5057'-5066' | 4 JSPF | 36 holes |
| 2-2-90 | 5068'-5071' | 4 JSPF | 12 holes |
| 2-4-90 | 4898'-4918' | 4 JSPF | 80 holes |
| 4/11/00 | 4352'-4355' | 2 JSPF | 06 holes |
| 4/11/00 | 4358'-4363' | 2 JSPF | 10 holes |
| 4/11/00 | 4365'-4368' | 2 JSPF | 06 holes |
| 4/11/00 | 4393'-4400' | 2 JSPF | 14 holes |
| 4/11/00 | 4423'-4432' | 2 JSPF | 18 holes |
| 4/11/00 | 4434'-4436' | 2 JSPF | 04 holes |

NEWFIELD

Federal #23-33B-8-16
1653 FSL & 1888 FWL
NESW Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-31251; Lease #U-49092

Wells Draw Federal Q-33-8-16

Spud Date: 5/20/08
Put on Production: 6/27/2008

GL: 5713' KB: 5725'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7jts
DEPTH LANDED: 305.28'
HOLE SIZE: 12-1/4"
CEMENT DATA: To surface with 160 sx class 'G' cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 160 jts
DEPTH LANDED: 6500'
HOLE SIZE: 7-7/8"
CEMENT DATA: 325 sx Premlite II and 450 sx 50/50 Poz

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 189jts
TUBING ANCHOR: 5827.93'
NO. OF JOINTS: 2jts (61.40')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5892.13'
NO. OF JOINTS: 4jts
TOTAL STRING LENGTH: EOT @ 6052.47' w/12' kb

SUCKER RODS

POLISHED ROD: 1-1/2" x 26' polished rods
SUCKER RODS: 1-8", 1-4" & 1-2" x 7/8" pony rods, 230-7/8" scraped rods, 4-1 1/2" weight rods, 21k shear cplg.
PUMP SIZE: CDI 2-1/2" x 1-3/4" x 20' RHAC pump w/sm plunger
STROKE LENGTH: 144"
PUMP SPEED, SPM: 5

Wellbore Diagram

Cement Top @ 40'

**FRAC JOB**

6/23/08 6300-6312' **Frac CP5 sds as follows:**
Frac w/ 39,852# 20/40 sand in 436 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2239 psi @ ave rate of 23.1 BPM. ISIP 2497 psi. Actual flush: 5796 gals.

6/23/08 6050-6068' **Frac CP2 sds as follows:**
Frac w/ 95,195# 20/40 sand in 747 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1862 psi @ ave rate of 23.1 BPM. ISIP 2181 psi. Actual flush: 5552 gals.

6/23/08 5526-5538' **Frac A1 & A3 sds as follows:**
Frac w/100,414# 20/40 sand in 756 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1904 psi @ ave rate of 23.1 BPM. ISIP 2131 psi. Actual flush: 5036 gals.

6/23/08 5340-5352' **Frac B1 sds as follows:**
Frac w/ 28,958# 20/40 sand in 398 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2014 psi @ ave rate of BPM. ISIP 1995 psi. Actual flush: 4838 gals.

6/23/08 5246-5264' **Frac C sds as follows:**
Frac w/ 79,993# 20/40 sand in 631 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2093 psi @ ave rate of 23.1 BPM. ISIP 2266 psi. Actual flush: 4733 gals.

6/23/08 5066-5086' **Frac D1 & D2 sds as follows:**
Frac w/ 219,703# 20/40 sand in 1489 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2076 psi @ ave rate of 24.9 BPM. ISIP 2307 psi. Actual flush: 4561 gals.

6/23/08 4576-4600' **Frac GB6 sds as follows:**
Frac w/139,638# 20/40 sand in 1000 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1874 psi @ ave rate of 25.5 BPM. ISIP 2200 psi. Actual flush: 4066 gals.

6/23/08 4506-4524' **Frac GB2 sds as follows:**
Frac w/ 65,170# 20/40 sand (34,830#s short) in 610 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2431 psi @ ave rate of 23.1 BPM. ISIP 2583 psi. Actual flush: 4502 gals.

PERFORATION RECORD

| | | |
|------------|--------|----------|
| 4506-4524' | 4 JSPF | 72 holes |
| 4576-4600' | 4 JSPF | 96 holes |
| 5066-5086' | 4 JSPF | 72 holes |
| 5090-5096' | 4 JSPF | 24 holes |
| 5122-5140' | 4 JSPF | 72 holes |
| 5246-5264' | 4 JSPF | 72 holes |
| 5340-5352' | 4 JSPF | 48 holes |
| 5526-5538' | 4 JSPF | 48 holes |
| 5572-5578' | 4 JSPF | 24 holes |
| 6050-6068' | 4 JSPF | 72 holes |
| 6300-6312' | 4 JSPF | 48 holes |

NEWFIELD

Wells Draw Fed. Q-33-8-16

346'FSL & 2122' FWL

SE/SW Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-33751; Lease # UTU-49092

Wells Draw Federal R-33-8-16

Spud Date: 7/29/2009
 Put on Production: 9/28/2009
 GL: 5673' KB: 5685'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (308.67')
 DEPTH LANDED: 320.52'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 144 jts. (6421.69')
 HOLE SIZE: 7-7/8"
 TOTAL DEPTH: 6434.94'
 CEMENT DATA: 250 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
 CEMENT TOP AT: 48'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 192 jts (6034.3')
 TUBING ANCHOR: 6046.3'
 NO. OF JOINTS: 2 jts (63.2')
 SEATING NIPPLE: 2-7/8" (1.1')
 SN LANDED AT: 6112.2' KB
 NO. OF JOINTS: 1 jts (31.4'), 3 jts (94.8')
 TOTAL STRING LENGTH: EOT @ 6246'

SUCKER RODS

POLISHED ROD: 1 1/2" x 26'
 SUCKER RODS: 1 - 2' x 7/8", 1 - 4' x 7/8", 1 - 8" x 7/8" pony rods,
 239 - 7/8" 8 per guided rods, 4-1 1/2" weight bars
 PUMP SIZE: 2 1/2" x 1 3/4" x 20" RHAC
 STROKE LENGTH: 168
 PUMP SPEED: SPM 6

FRAC JOB

| | | |
|---------|------------|--|
| 9-29-09 | 6228-6252' | Frac BLK SH sands as follows: Frac with 35390# 20/40 sand in 232 bbls Lightning 17 fluid. |
| 9-29-09 | 5916-5991' | Frac CP2, CP.5, & CP1 sands as follows: Frac with 29840# 20/40 sand in 251 bbls Lightning 17 fluid. |
| 9-29-09 | 5616-5741' | Frac LODC sands as follows: Frac with 60359# 20/40 sand in 367 bbls Lightning 17 fluid. |
| 9-29-09 | 5458-5475' | Frac A1 sands as follows: Frac with 35455# 20/40 sand in 226 bbls Lightning 17 fluid. |
| 9-29-09 | 5023-5117' | Frac D2, D1, & D3 sands as follows: Frac with 80474# 20/40 sand in 484 bbls Lightning 17 fluid. |
| 9-29-09 | 4558-4563' | Frac GB6 sands as follows: Frac with 16887# 20/40 sand in 140 bbls Lightning 17 fluid. |

PERFORATION RECORD

| | | |
|------------|--------|----------|
| 6250-6252' | 3 JSPF | 6 holes |
| 6236-6242' | 3 JSPF | 18 holes |
| 6228-6230' | 3 JSPF | 6 holes |
| 5986-5991' | 3 JSPF | 15 holes |
| 5950-5954' | 3 JSPF | 12 holes |
| 5916-5918' | 3 JSPF | 6 holes |
| 5737-5741' | 3 JSPF | 12 holes |
| 5725-5728' | 3 JSPF | 9 holes |
| 5688-5692' | 3 JSPF | 12 holes |
| 5640-5642' | 3 JSPF | 6 holes |
| 5616-5618' | 3 JSPF | 6 holes |
| 5468-5475' | 3 JSPF | 21 holes |
| 5458-5461' | 3 JSPF | 9 holes |
| 5112-5117' | 3 JSPF | 15 holes |
| 5077-5079' | 3 JSPF | 6 holes |
| 5067-5069' | 3 JSPF | 6 holes |
| 5028-5030' | 3 JSPF | 6 holes |
| 5023-5025' | 3 JSPF | 6 holes |
| 4558-4563' | 3 JSPF | 15 holes |

NEWFIELD**Wells Draw Federal R-33-8-16**

NWSE 1823' FSL & 1916' FEL

Section 33-T8S-R16E

Duchesne Co, Utah

API # 43-013-34068; Lease # UTU-49092

Federal #33-33B

Spud Date:4/30/90
Put on Production:8/11/90
GL:5667' KB:5682'

Initial Production: 57 BOPD,
0 MCFPD, 112 BWPD

Wellbore Diagram

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: jts. (7')
DEPTH LANDED: 301' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 1- 225, sxs Class "G" + 114 sxs flocele

PRODUCTION CASING


CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 17#
LENGTH: jts. (163')
DEPTH LANDED: 6400' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 155 sxs Prem. Lite II mixed & 520 sxs 50/50 POZ.

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 197 jts (6151.1')
TUBING ANCHOR: 6151.1' KB
NO. OF JOINTS: 1 jts (31.1')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 6185' KB
NO. OF JOINTS: 2 jts (62.4')
TOTAL STRING LENGTH: EOT @ 6249' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM polished rods
SUCKER RODS: 1-6", 1-4" X 3/4" Pony rods 89-3/4" guided rods, 152-3/4" slick rods, 4-1 1/2" weight rods.
PUMP SIZE: CDI 2-1/2" x 1-1/2" x 17' x 0' RHAC
STROKE LENGTH: 102"
PUMP SPEED, SPM: 4



FRAC JOB

| | | |
|-----------|-------------|---|
| 7/11/90 | 5586'-5665' | Frac zone as follows: 83,990# 20/40 sand + 110,250# 16/30 sand in 1821 bbls fluid. Treated @ avg press of 2100 psi w/avg rate of 62.5 BPM. ISIP 2200 psi. Calc. flush: 5586 gal. Actual flush: 5418 gal. |
| 7/13/90 | 5379'-5386' | Frac zone as follows: 18,600# 20/40 sand + 11,000# 16/30 sand in 443 bbls fluid. Treated @ avg press of 1600 psi w/avg rate of 63 BPM. ISIP 2100 psi. Calc. flush: 5379 gal. Actual flush: 2865 gal. |
| 7/17/90 | 4473'-4509' | Frac zone as follows: 56,100# 20/40 sand + 73,750# 16/30 sand in 1253 bbls fluid. Treated @ avg press of 2300 psi w/avg rate of 40 BPM. ISIP 2300 psi. Calc. flush: 4473 gal. Actual flush: 4368 gal. |
| 2/6/03 | 5850'-6228' | Frac CP and BS sands as follows: 119,440# 20/40 sand in 863 bbls YF 125 fluid. Treated @ avg. pressure of 4168 psi w/avg. rate of 17.4 BPM. ISIP - 1946 psi. Calc flush: 1522 gal. Actual flush: 1389 gal. |
| 2/7/03 | 5701'-5709' | Frac LoLODC sands as follows: 24,458# 20/40 sand in 202 bbls YF 125 fluid. Treated @ avg. pressure of 4996 psi w/avg. rate of 17.6 BPM. Calc flush: 1439 gal. Actual flush: 722 gal. |
| 2/7/03 | 5534'-5580' | Frac UpLODC sands as follows: 74,500# 20/40 sand in 550 bbls YF 125 fluid. Treated @ avg. pressure of 3725 psi w/avg. rate of 17.8 BPM. ISIP - 1798 psi. Calc flush: 1424 gal. Actual flush: 1277 gal. |
| 2/8/03 | 5206'-5367' | Frac B1, B2 and UpA1 sands as follows: 65,500# 20/40 sand in 474 bbls YF 125 fluid. Treated @ avg. pressure of 3512 psi w/avg. rate of 17.3 BPM. ISIP - 2189 psi. Calc flush: 1348 gal. Actual flush: 1132 gal. |
| 2/8/03 | 5037'-5096' | Frac D3 and C sands as follows: 22,468# 20/40 sand in 204 bbls YF 125 fluid. Treated @ avg. pressure of 3351 psi w/avg. rate of 17.9 BPM. |
| 5/8/03 | | Pump Change. Update rod and tubing detail. |
| 10/12/05 | | Pump Change (Lower EOT) |
| 11/14/05 | | Pump Change (Lower EOT) |
| 12/08/05 | | Tubing Leak. Detail tubing and rod update. |
| 11/9/2009 | | Pump change. Update rod and tubing details. |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|-----------|
| 7/10/90 | 5609'-5665' | 4 JSPF | 224 holes |
| 7/10/90 | 5586'-5605' | 4 JSPF | 76 holes |
| 7/12/90 | 5379'-5386' | 4 JSPF | 28 holes |
| 7/14/90 | 4473'-4509' | 4 JSPF | 144 holes |
| 2/4/03 | 6225'-6228' | 4 JSPF | 12 holes |
| 2/4/03 | 6190'-6204' | 4 JSPF | 56 holes |
| 2/4/03 | 6177'-6180' | 4 JSPF | 12 holes |
| 2/4/03 | 6163'-6168' | 4 JSPF | 36 holes |
| 2/4/03 | 6154'-6158' | 4 JSPF | 36 holes |
| 2/4/03 | 5983'-5990' | 4 JSPF | 28 holes |
| 2/4/03 | 5946'-5950' | 4 JSPF | 48 holes |
| 2/4/03 | 5932'-5940' | 4 JSPF | 48 holes |
| 2/4/03 | 5850'-5852' | 4 JSPF | 8 holes |
| 2/4/03 | 5701'-5709' | 4 JSPF | 32 holes |
| 2/4/03 | 5566'-5580' | 4 JSPF | 76 holes |
| 2/4/03 | 5556'-5561' | 4 JSPF | 76 holes |
| 2/4/03 | 5544'-5550' | 4 JSPF | 36 holes |
| 2/4/03 | 5534'-5537' | 4 JSPF | 36 holes |
| 2/4/03 | 5357'-5367' | 4 JSPF | 52 holes |
| 2/4/03 | 5346'-5349' | 4 JSPF | 52 holes |
| 2/4/03 | 5244'-5254' | 4 JSPF | 56 holes |
| 2/4/03 | 5206'-5210' | 4 JSPF | 56 holes |
| 2/4/03 | 5091'-5096' | 4 JSPF | 20 holes |
| 2/4/03 | 5051'-5057' | 4 JSPF | 36 holes |
| 2/4/03 | 5037'-5040' | 4 JSPF | 36 holes |



Federal #33-33B
1857 FSL & 1883 FEL
NWSE Section 33-T8S-R16E
Duchesne Co, Utah
API #43-013-31268; Lease #U-49092

Wells Draw Federal S-33-8-16

Spud Date: 08/01/2009
 Put on Production: 09/22/2009
 GL: 5673' KB: 5685'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (308.78')
 DEPTH LANDED: 320.63'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 143 jts. (6411.39')
 HOLE SIZE: 7-7/8"
 TOTAL DEPTH: 6424.64'
 CEMENT DATA: 300 sxs Prem. Lite II mixed & 425 sxs 50/50 POZ.
 CEMENT TOP AT: 20'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 188 jts (5985')
 TUBING ANCHOR: 5997'
 NO. OF JOINTS: 1 jts (31.6')
 SEATING NIPPLE: 2-7/8" (1.1')
 SN LANDED AT: 6031.4' KB
 NO. OF JOINTS: 2 jts (63.2')
 TOTAL STRING LENGTH: EOT @ 6096'

SUCKER RODS

POLISHED ROD: 1-1/2" x 30'
 SUCKER RODS: 1 - 2' x 7/8", 1 - 4' x 7/8" pony rods, 236 - 7/8" guided rods, 4-1 1/2" weight bars
 PUMP SIZE: 2 1/4" x 1 3/4" x 20' RHAC
 STROKE LENGTH: 168
 PUMP SPEED: SPM 6

Cement Top @ 20'

SN @ 6031'

4541-4545'

5015-5018'

5026-5028'

5075-5082'

5204-5206'

5328-5330'

5334-5338'

5602-5605'

5678-5681'

5711-5714'

5792-5795'

5921-5925'

5969-5971'

Anchor @ 5997'

6008-6013'

EOT @ 6096'

PBTD @ 6352'

TD @ 6435'

FRAC JOB

9-23-09 5921-6013' Frac CP1, CP.5 & CP2 sands as follows: Frac with 30433# 20/40 sand in 258 bbls Lightning 17 fluid.
 9-23-09 5602-5795' Frac LODC sands as follows: Frac with 201574# 20/40 sand in 1228 bbls Lightning 17 fluid.
 9-23-09 5204-5338' Frac B2 & C sands as follows: Frac with 15016# 20/40 sand in 123 bbls Lightning 17 fluid.
 9-23-09 5015-5082' Frac D2 & D1 sands as follows: Frac with 150403# 20/40 sand in 945 bbls Lightning 17 fluid.
 9-23-09 4541-4545' Frac GB6 sands as follows: Frac with 14911# 20/40 sand in 131 bbls Lightning 17 fluid.

PERFORATION RECORD

| | | |
|------------|--------|----------|
| 6008-6013' | 3 JSPF | 15 holes |
| 5969-5971' | 3 JSPF | 6 holes |
| 5921-5925' | 3 JSPF | 12 holes |
| 5792-5795' | 3 JSPF | 9 holes |
| 5711-5714' | 3 JSPF | 9 holes |
| 5678-5681' | 3 JSPF | 9 holes |
| 5602-5605' | 3 JSPF | 9 holes |
| 5334-5338' | 3 JSPF | 12 holes |
| 5328-5330' | 3 JSPF | 6 holes |
| 5204-5206' | 3 JSPF | 6 holes |
| 5075-5082' | 3 JSPF | 21 holes |
| 5026-5028' | 3 JSPF | 6 holes |
| 5015-5018' | 3 JSPF | 9 holes |
| 4541-4545' | 3 JSPF | 12 holes |

NEWFIELD**Wells Draw Federal S-33-8-16**

1836' FSL & 1899' FEL

NW/SE Section 33-T8S-R16E

Duchesne Co, Utah

API # 43-013-34067; Lease # UTU-49092

Spud Date: 7/17/95
Put on Production: 9/12/95
Put on Injection: 10/7/97

GL: 5631' KB: 5644'

Monument Butte Fed. #5-34-8-16

Initial Production: 218 BOPD,
124 MCFD, 9 BWPD

Injection Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (298')
DEPTH LANDED: 296' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 120 sxs Class "G" cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: ? jts. (6152')
DEPTH LANDED: 6148' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 340 sxs Hifill & 345 sxs Cal-Seal.
CEMENT TOP AT: ? per CBL

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 140 jts (4440.03')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 4453.03' KB
PACKER AT: 4457.48' KB
TOTAL STRING LENGTH: EOT @ 4461.68' KB

FRAC JOB


| | | |
|----------|-------------|---|
| 8/30/95 | 5663'-5693' | Frac zone as follows: 14,933# 20/40 sand + 130,948# 16/30 sand in 738 bbls Boragel frac fluid. Treated @ avg press of 2650 psi w/avg rate of 33 BPM. ISIP 2970 psi. Calc flush: 5663 gal. Actual flush: 5628 gal. |
| 9/01/95 | 5442'-5486' | Frac zone as follows: 88,000# 20/40 sand + 40,000# 16/30 sand in 548 bbls Gelled frac fluid. Treated @ avg press of ? psi w/avg rate of ? BPM. ISIP 2030 psi. Calc flush: 5442 gal. Actual flush: 5398 gal. |
| 9/03/95 | 5263'-5344' | Frac zone as follows: 58,000# 16/30 sand in 548 bbls Gelled frac fluid. Treated @ avg press of ? psi w/avg rate of ? BPM. ISIP 3537 psi. Calc flush: 5263 gal. Actual flush: 1519 gal. |
| 9/08/95 | 5044'-5052' | Frac zone as follows: 52,000# 16/30 sand in 459 bbls Gelled frac fluid. Treated @ avg press of ? psi w/avg rate of ? BPM. ISIP 2097 psi. Calc flush: 5044 gal. Actual flush: 5000 gal. |
| 9/27/97 | | Convert to injector. |
| 7-13-05 | | Re-completion and MIT. |
| | 5884'-5894' | Frac zone as follows: 19,640# 16/30 sand in 209 bbls of Lightning 17 frac fluid. Treated @ avg press of 2970 psi w/avg rate rate of 14.3 BPM. ISIP 1725 psi. Calc flush: 1589 gal. Actual flush: 1470 gal. |
| 7-13-05 | 5154'-5164' | Frac zone as follows: 14,568# 20/40 sand in 172 bbls of Lightning 17 frac fluid. Treated @ avg press of 3359 psi w/avg rate of 14.3 BPM. ISIP 2850 psi. Calc flush: 1820 gal. Actual flush: 1218 gal. |
| 7-14-05 | 4510'-4526' | Frac zone as follows: 14,210# 20/40 sand in 181 bbls of Lightning 17 frac fluid. Treated @ avg press of 3059 psi w/avg rate of 14.2 BPM. ISIP 2000 psi. Calc flush: 1166 gal. Actual flush: 1134 gal. |
| 11/15/06 | | Workover: Acidize B2 sands |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|-----------|
| 8/29/95 | 5663'-5693' | 4 JSPF | 120 holes |
| 8/31/95 | 5460'-5486' | 4 JSPF | 104 holes |
| 8/31/95 | 5455'-5458' | 4 JSPF | 12 holes |
| 8/31/95 | 5442'-5452' | 4 JSPF | 40 holes |
| 9/2/95 | 5332'-5344' | 4 JSPF | 48 holes |
| 9/2/95 | 5328'-5330' | 4 JSPF | 24 holes |
| 9/2/95 | 5322'-5326' | 4 JSPF | 16 holes |
| 9/2/95 | 5263'-5274' | 4 JSPF | 44 holes |
| 9/7/95 | 5044'-5052' | 4 JSPF | 32 holes |



Monument Butte Fed. #5-34-8-16
1980' FSL & 660' FWL
SWNW Section 34-T8S-R16E
Duchesne Co, Utah
API #43-013-31499; Lease #U-62848



Multi-Chem Group, LLC

Multi-Chem Analytical Laboratory
1553 East Highway 40
Vernal, UT 84078

multi-chem®

Water Analysis Report

Production Company: **NEWFIELD PRODUCTION (158)**

Sample ID: **WA-35260**

Well Name: **Monument Butte Injection**

Sample Point: **Before Desilter**

Sample Date: **1 /1 /2010**

Sales Rep: **Randy Huber**

Lab Tech: **John Keel**

| Sample Specifics | |
|-----------------------------|----------|
| Test Date: | 1/5/2010 |
| Temperature (°F): | 90 |
| Sample Pressure (psig): | 0 |
| Specific Gravity (g/cm³): | 1.0040 |
| pH: | 9.1 |
| Turbidity (NTU): | - |
| Calculated T.D.S. (mg/L): | 11140 |
| Molar Conductivity (µS/cm): | 16879 |
| Resistivity (Mohm): | 0.5925 |

| Analysis @ Properties in Sample Specifics | | | | | |
|---|--|---------|----------------------|--|---------|
| Cations | | mg/L | Anions | | mg/L |
| Calcium (Ca): | | 40.00 | Chloride (Cl): | | 6000.00 |
| Magnesium (Mg): | | 24.40 | Sulfate (SO 4): | | 140.00 |
| Barium (Ba): | | 14.00 | Dissolved CO 2: | | - |
| Strontium (Sr): | | - | Bicarbonate (HCO 3): | | 780.00 |
| Sodium (Na): | | 4139.00 | Carbonate (CO 3): | | - |
| Potassium (K): | | - | H 2 S: | | - |
| Iron (Fe): | | 2.29 | Phosphate (PO 4): | | - |
| Manganese (Mn): | | 0.15 | Silica (SiO 2): | | - |
| Lithium (Li): | | - | Fluoride (F): | | - |
| Aluminum (Al): | | - | Nitrate (NO 3): | | - |
| Ammonia NH 3: | | - | Lead (Pb): | | - |
| | | | Zinc (Zn): | | - |
| | | | Bromine (Br): | | - |
| | | | Boron (B): | | - |

| Test Conditions | | Scale Values @ Test Conditions - Potential Amount of Scale in lb/1000bbl | | | | | | | | | | |
|-----------------|---------------------|--|-------|---|----------|--------------------------------------|----------|--|-------|-------------------------------------|-------|-------------------------------|
| | | Calcium Carbonate CaCO ₃ | | Gypsum CaSO ₄ · 2H ₂ O | | Calcium Sulfate CaSO ₄ | | Strontium Sulfate SrSO ₄ | | Barium Sulfate BaSO ₄ | | Calculated CO ₂ |
| | | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | psi |
| Temp °F | Gauge Press. psi | | | | | | | | | | | |
| 90 | 0 | 23.17 | 69.04 | 0.00 | -2379.40 | 0.00 | -2621.80 | - | - | 55.12 | 23.32 | 0.01 |
| 80 | 0 | 21.03 | 68.87 | 0.00 | 48.75 | 0.00 | -2691.60 | - | - | 68.23 | 23.41 | 0.01 |
| 100 | 0 | 24.91 | 68.69 | 0.00 | 51.91 | 0.00 | -2527.60 | - | - | 44.78 | 23.21 | 0.01 |
| 120 | 0 | 27.06 | 67.47 | 0.00 | 53.11 | 0.00 | -2284.10 | - | - | 30.04 | 22.93 | 0.01 |
| 140 | 0 | 27.53 | 66.01 | 0.00 | 53.00 | 0.00 | -1996.20 | - | - | 20.54 | 22.53 | 0.01 |
| 160 | 0 | 26.44 | 63.35 | 0.01 | 51.01 | 0.01 | -1694.10 | - | - | 14.28 | 21.97 | 0.01 |
| 180 | 0 | 24.21 | 57.33 | 0.01 | 46.14 | 0.01 | -1400.70 | - | - | 10.07 | 21.21 | 0.01 |
| 200 | 0 | 21.32 | 48.01 | 0.01 | 38.70 | 0.01 | -1130.70 | - | - | 7.20 | 20.18 | 0.01 |
| 220 | 2.51 | 18.08 | 38.69 | 0.01 | 30.92 | 0.02 | -903.37 | - | - | 5.11 | 18.72 | 0.01 |
| 240 | 10.3 | 15.10 | 30.38 | 0.01 | 23.66 | 0.03 | -698.20 | - | - | 3.72 | 16.87 | 0.01 |
| 260 | 20.76 | 12.37 | 23.68 | 0.01 | 17.47 | 0.04 | -526.95 | - | - | 2.73 | 14.44 | 0.01 |
| 280 | 34.54 | 9.96 | 18.46 | 0.01 | 12.31 | 0.07 | -387.36 | - | - | 2.01 | 11.26 | 0.01 |
| 300 | 52.34 | 7.88 | 14.42 | 0.01 | 8.07 | 0.11 | -276.02 | - | - | 1.48 | 7.11 | 0.01 |

Conclusions:

Calcium Carbonate scale is indicated at all temperatures from 80°F to 300°F

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated





Barium Sulfate scale is indicated at all temperatures from 80°F to 300°F

Notes:

**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory
1553 East Highway 40
Vernal, UT 84078

multi-chem®

Scale Prediction GraphsWell Name: **Monument Butte Injection**Sample ID: **WA-35260**

Multi-Chem Group, LLC

Multi-Chem Analytical Laboratory
1553 East Highway 40
Vernal, UT 84078

Water Analysis Report

Production Company: **NEWFIELD PRODUCTION (158)**

Sample ID: **WA-48300**

Well Name: **federal 6-33-8-16**

Sample Point: **tank**

Sample Date: **10/15/2010**

Sales Rep: **Monty Frost**

Lab Tech: **Peter Poulsen**

| Sample Specifics | | Analysis @ Properties in Sample Specifics | | | |
|--|------------|---|-------------|----------------------------------|-------------|
| Test Date: | 10/18/2010 | Cations | mg/L | Anions | mg/L |
| Temperature (°F): | 100 | Calcium (Ca): | 3.21 | Chloride (Cl): | 4000.00 |
| Sample Pressure (psig): | 0 | Magnesium (Mg): | 1.11 | Sulfate (SO ₄): | 31.98 |
| Specific Gravity (g/cm ³): | 1.0049 | Barium (Ba): | 27.16 | Dissolved CO ₂ : | - |
| pH: | 8.2 | Strontium (Sr): | - | Bicarbonate (HCO ₃): | 1610.00 |
| Turbidity (NTU): | - | Sodium (Na): | 3184.00 | Carbonate (CO ₃): | - |
| | | Potassium (K): | - | H ₂ S: | - |
| | | Iron (Fe): | 0.96 | Phosphate (PO ₄): | - |
| | | Manganese (Mn): | 0.06 | Silica (SiO ₂): | - |
| | | Lithium (Li): | - | Fluoride (F): | - |
| Calculated T.D.S. (mg/L) | 8858 | Aluminum (Al): | - | Nitrate (NO ₃): | - |
| Molar Conductivity (μS/cm): | 13422 | Ammonia NH ₃ : | - | Lead (Pb): | - |
| Resistivity (Mohm): | 0.7450 | | | Zinc (Zn): | - |
| | | | | Bromine (Br): | - |
| | | | | Boron (B): | - |

| Test Conditions | | Scale Values @ Test Conditions - Potential Amount of Scale in lb/1000bbl | | | | | | | | | | |
|-----------------|------------------|--|-------|---|----------|--------------------------------------|----------|--|-------|-------------------------------------|-------|-------------------------------|
| | | Calcium Carbonate CaCO ₃ | | Gypsum CaSO ₄ · 2H ₂ O | | Calcium Sulfate CaSO ₄ | | Strontium Sulfate SrSO ₄ | | Barium Sulfate BaSO ₄ | | Calculated CO ₂ |
| | | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | Sat Index | Scale | psi |
| Temp °F | Gauge Press. psi | | | | | | | | | | | |
| 100 | 0 | 1.00 | -0.02 | 0.00 | -2286.60 | 0.00 | -2407.00 | - | - | 25.36 | 41.76 | 0.25 |
| 80 | 0 | 0.77 | -1.63 | 0.00 | -8.33 | 0.00 | -2561.50 | - | - | 38.41 | 43.15 | 0.13 |
| 100 | 0 | 1.00 | -0.02 | 0.00 | -4.73 | 0.00 | -2407.00 | - | - | 25.36 | 41.76 | 0.16 |
| 120 | 0 | 1.21 | 0.87 | 0.00 | -2.55 | 0.00 | -2180.90 | - | - | 17.13 | 39.96 | 0.17 |
| 140 | 0 | 1.40 | 1.35 | 0.00 | -1.27 | 0.00 | -1914.90 | - | - | 11.80 | 37.70 | 0.20 |
| 160 | 0 | 1.55 | 1.59 | 0.00 | -0.56 | 0.00 | -1636.40 | - | - | 8.29 | 34.97 | 0.22 |
| 180 | 0 | 1.66 | 1.68 | 0.00 | -0.21 | 0.00 | -1366.00 | - | - | 5.93 | 31.76 | 0.24 |
| 200 | 0 | 1.73 | 1.69 | 0.00 | -0.06 | 0.00 | -1117.30 | - | - | 4.30 | 28.03 | 0.24 |
| 220 | 2.51 | 1.73 | 1.66 | 0.00 | -0.01 | 0.00 | -907.61 | - | - | 3.10 | 23.48 | 0.24 |
| 240 | 10.3 | 1.70 | 1.61 | 0.00 | -0.02 | 0.00 | -719.55 | - | - | 2.29 | 18.53 | 0.24 |
| 260 | 20.76 | 1.63 | 1.54 | 0.00 | -0.06 | 0.00 | -562.96 | - | - | 1.71 | 12.92 | 0.25 |
| 280 | 34.54 | 1.54 | 1.42 | 0.00 | -0.13 | 0.00 | -435.35 | - | - | 1.29 | 6.54 | 0.25 |
| 300 | 52.34 | 1.43 | 1.24 | 0.00 | -0.22 | 0.00 | -333.11 | - | - | 0.97 | -0.71 | 0.25 |

Conclusions:

Calcium Carbonate scale is indicated. See graph for appropriate temperature ranges.

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated

Barium Sulfate NO CONCLUSION

Notes:





**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

multi-chem®

Scale Prediction GraphsWell Name: **federal 6-33-8-16**Sample ID: **WA-48300**

Attachment "G"

Travis Federal 6-33-8-16 Proposed Maximum Injection Pressure

| Frac Interval (feet) | | Avg. Depth (feet) | ISIP (psi) | Calculated Frac Gradient (psi/ft) | Pmax | |
|-------------------------|--------|----------------------|---------------|--|-------------|---|
| Top | Bottom | | | | | |
| 5057 | 5066 | 5062 | 1200 | 0.67 | 1167 | ← |
| 5184 | 5194 | 5189 | 3040 | 1.02 | 3006 | |
| 4505 | 4555 | 4530 | 2330 | 0.95 | 2301 | |
| | | | | Minimum | <u>1167</u> | |

Calculation of Maximum Surface Injection Pressure

$$P_{max} = (\text{Frac Grad} - (0.433 \times 1.015)) \times \text{Depth of Top Perf}$$
 where pressure gradient for the fresh water is .433 psi/ft and
 specific gravity of the injected water is 1.015.

$$\text{Frac Gradient} = (\text{ISIP} + (0.433 \times \text{Top Perf.})) / \text{Top Perf.}$$

Please note: These are existing perforations; additional perforations may be added during the actual conversion procedure.

LOMAX EXPLORATION

Federal #6-33
SE/NW Section 33, T8S, R16E
Duchesne County, Utah

DAILY COMPLETION REPORT

- 8/24/83 Present Operation - Perforating. (1 day)
REMARKS: MIRU. Turned tbg around on rack. Talleyed tbg. PU and ran 5½" bit & scraper to 6081'. Displaced hole w/ 5% KCL w/clay stay. POH. RU OWP. Ran cmt bond log from PBTD - 4000' & across cmt top @ 1965'. SDFN.
CUM COST: 4138,986
- 8/25/83 Present Operation - Flowing after frac. (2 days)
REMARKS: Tested csg to 3000psi. RIH and perf from 5932' - 60'. RD OWP and broke down perf w/rig pump. Perfs broke down @ 2600 psi. RU Western Co and fraced well as below:
- | | | | | | |
|--------|---------|-----|----------|-------|------|
| Pumped | 120,000 | gal | pad | | |
| Pumped | 4000 | gal | @ 1#/gal | 20/40 | sand |
| " | 5000 | " | 2 | " | |
| " | 6000 | " | 4 | " | |
| " | 7000 | " | 6 | " | |
| " | 4500 | " | 8 | " | |
- flushed w/137 Bbls. Ran out of sand after 4500 gal pumped on the 8#/gal stage.
- 4000
10,000
24,000
42,000
36,000
116,000 #
- SDFN.
CUM COST: \$166,386
- 8/26/83 Present Operation - Flowing. (3 days)
REMARKS: Csg press 1350 psi. Opened well on 10/64 choke. Flowed to tank for 10 hrs. Well made 204 Bbls wtr w/trace of sand and oil at the end of the day. Left well open on 10/64 choke over night. Press 400 psi at 5 PM.
CUM COST: \$168,286
- 8/27/83 Present Operation - Swabbing. (4 days)
REMARKS: Well flowed 104 Bbls fluid overnight. Csg press 0. Well flowing small amount of wtr w/5% oil. PU 5½" CS-1 pkr and RIH. Tried to set pkr @ 5829'. Pkr would not set. Swabbed well to frac tank for rest of the day. Made 33 runs. Recovered 193 Bbls fluid. 20% oil on last run. Fluid level dropped to 3200' @ 5:00 PM. Trace of sand in sample. SDFN.
CUM COST: \$170,426
- 8/28/83 Present Operation - Swabbing. (5 days)
REMARKS: Tbg press 250 psi. Csg press 100 psi. Bled off press and tried to set pkr. Pkr still would not set. Swabbed well to tank for rest of the day. IFL @ 1500'. FFL @ 5200'. Swab 172 Bbls in 26 runs. 55% oil on last run w/tr of sd. Final rate 10 Bbls/hr. Good gas blow while swabbing. Shut down for Sunday.
CUM COST: \$172,626

LOMAX EXPLORATION
Federal #6-33
Section 33, T8S, R16E
Duchesne County, Utah
DAILY COMPLETION REPORT 2

8/30/83 Present Operation - Swabbing. (6 days)
REMARKS: Tbg press 250 psi. IFL @ 700', FFL @ 5100'. Made 6 runs, well flowed for ½ hr. Swabbed well to tank for rest of the day. Made 26 runs, recovered 60 BLW, 89 BNO. 80% oil on last run w/1.5% sd and strong gas blow. Final rate 13 Bbls/hr. SDFN.
CUM COST: \$174,726

8/31/83 Present Operation - Circulating sand. (7 days)
REMARKS: Tbg press 350#. Csg press 150#. Bled press off well. Swab 4½ hrs. IFL @ 2900', FFL @ 5200'. Recovered 71 Bbls fluid. 95% oil w/trace of sd. Strong gas blow. Final rate 16 Bbls/hr. Bled press of csg. Pulled pkr & tbg out of the hole. PU and ran notched collar, 3 jts tbg, SN, 2 jts tbg, tbg anchor and remaining 2 7/8" tbg. Tag sd @ 5908'. Filled hole w/wtr. Attempted to circ sd, could not break thru top of sand. SDFN.
CUM COST: \$176,926

9/1/83 Present Operation - RDMOSU. (8 days)
REMARKS: RU swivel and rotated down through hard sand. Cleaned hole out to 6088'. Layed down 2 jts tbg and set anchor. Landed tbg w/8000# tension. EOT @ 6028'. SN @ 5929'. Anchor @ 5861', 180 jts tbg above anchor. Swabbed 60 Bbls of wtr, and RU to run rods. PU and ran bottom hole pump, 4 wt rods, 23 3/4" rods and 1 2' x3/4" pony rod. Made up wellhead and landed pump. SDFN.
CUM COST: \$184,866

9/2/83 Present Operation - WO Battery. (9 days)
REMARKS: RDMOSU. Clean out flat tank. Recovered 40 Bbls oil.
CUM COST: \$185,466

9/7/83 Pumped 16 Bbls oil, 62 wtr.

9/8/83 Pumped 26 Bbls oil, 47 wtr.

9/9/83 Pumped 60 Bbls oil, 8 wtr.

9/10/83 Pumped 47 Bbls oil, 34 wtr.

9/11/83 Pumped 32 Bbls oil, 21 wtr.

9/12/83 Pumped 30 Bbls oil, 15 wtr.

9/13/83 Pumped 4 Bbls oil. E.D. HO w/ 60 Bbls.

9/14/83 Pumped 10 Bbls oil, 18 wtr.

LOMAX EXPLORATION
Federal #6-33
Section 33, T8S, R16E
Duchesne County, Utah
DAILY COMPLETION REPORT 3

| | |
|---------|-----------------------------|
| 9/15/83 | Pumped 49 Bbls oil, 18 wtr. |
| 9/16/83 | Pumped 25 oil, 9 wtr. |
| 9/17/83 | Pumped 22 oil, 3 wtr. |

FINAL REPORT

Well Name W. Monument Butte 6-33 Completion Unit Garnoch 17 Completion Days 1

Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pkr/EOT @ PBD 6013
 Present Operation Running Paper + Plug Work Fluid 5% KCl

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____

| | | |
|----------------------------|----------------|----------------|
| SPF/#SHOTS | SPF/#SHOTS | SPF/#SHOT |
| <u>5932</u> to <u>5960</u> | _____ to _____ | _____ to _____ |
| _____ to _____ | _____ to _____ | _____ to _____ |
| _____ to _____ | _____ to _____ | _____ to _____ |

STIMULATION: Before job; SITP _____ SICP _____ Back Pressure _____
 Fluid used: _____ Company: _____

| | |
|--|---|
| Procedure: 1) _____ 2) _____ 3) _____ 4) _____ 5) _____ 6) _____ 7) _____ 8) _____ 9) _____ 10) _____ | Max TP _____ @ _____ BPM Avg TP _____ @ _____ BPM ISIP _____ _____ after _____ min _____ after _____ min _____ after _____ min Displacement fluid used: _____ _____ _____ |
|--|---|

| FLUID RECOVERY (Bbls): | | | | FLOWING: | | | | |
|------------------------|-------------|-----------|---------|---------------------------------|-----|----|----------|------------|
| | During Last | Total | Left to | CHK | HRS | TP | RECOVERY | DAILY RATE |
| | hrs. | Recovered | Recover | | | | | |
| BLW | | | | | | | | |
| BLO | | | | | | | | |
| BNW | | | | | | | | |
| BNO | | | | | | | | |
| | | | | SWABBING: #Runs Total Recovered | | | | |
| | | | | FL Maint. Swab Rate (B/H) WC | | | | |

REMARKS: Moved to location and Rigged up. Unseated pump.
Hot oiled Rods Pulled 2-8' x 3/4" and 1-6' x 3/4", and 229-3/4"
4 set rods and pump out of the hole. Released
tubing anchor. Picked up 1-jt tubing and run in
the hole. Tagged sand at 6013'. Installed BOT.
Pulled 2 7/8" tubing out of the hole. Shut down for
night.

| | |
|--|---|
| Completion Supervisor _____ Date <u>Feb 28 1984</u> | COSTS: Daily <u>2900.00</u> Cumulative <u>2900.00</u> |
|--|---|

Well Name W. Man. Butte 6-33 Completion Unit Gamache 17 Completion Days 2Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pkr/EOT @ PBD 5312'
Present Operation Running Packer. Work Fluid 5% KClPERFORATIONS: Size gun 4" Shot Diameter _____ Company: Mc Cullough

| SPF/#SHOTS | | SPF/#SHOTS | | SPF/#SHOTS | |
|-------------|----------------|------------|-----------|------------|--|
| <u>5057</u> | to <u>5066</u> | <u>21</u> | <u>18</u> | | |
| | to _____ | | | | |
| | to _____ | | | | |

STIMULATION: Before job; SITP _____ SICP _____ Back Pressure _____
Fluid used: _____ Company: _____

Procedure: 1) _____ Max TP _____ @ _____ BPM
 2) _____ Avg TP _____ @ _____ BPM
 3) _____ ISIP _____
 4) _____ after _____ min
 5) _____ after _____ min
 6) _____ after _____ min
 7) _____ Displacement fluid used: _____
 8) _____
 9) _____
 10) _____

| FLUID RECOVERY (Bbls): | | | FLOWING: | | | | | |
|------------------------|------------------|-----------------|-----------------|-------|-------|-------|----------|------------|
| | During Last hrs. | Total Recovered | Left to Recover | CHK | HRS | TP | RECOVERY | DAILY RATE |
| BLW | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |
| BLO | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |
| BNW | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |
| BNO | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |

SWABBING: #Runs _____ Total Recovered _____
 FL Maint. _____ Swab Rate (B/H) _____ WC _____

REMARKS: Run in the hole with 5 1/2" Bridge plug and packer. Set plug at 5986' and Packer at 5921'. Rigid up B.T. and pumped 20 Bbls 5% KCl water into formation at 5 BPM, 1800 Psi. ISIP 1200 psi. 5 min 900 psi, 10 min - 700 psi 15 min 600 psi. Bleed pressure off. Moved bridge plug to 5380' and pressure tested up to 3000 psi. Pressure held OK. Switched well down to 3800' and pulled tubing and packer out of the hole. Rigid up Mc Cullough and dumped sand on plug. Perforated well from 5057 to 5066'. Shut well in for night

Completion Supervisor _____
Date Feb 29 1984COSTS:
Daily 5700
Cumulative \$ 8600.00

Well Name W. Man Butte 6-33 Completion Unit Garnache Completion Days 3

Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pkr/EOT @ 4852 PBD 5312
 Present Operation Swabbing Work Fluid _____

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____
 _____ SPF/#SHOTS _____ SPF/#SHOTS _____ SPF/#SHOT _____
5057 to 5066 _____ to _____ to _____
 _____ to _____ to _____ to _____
 _____ to _____ to _____ to _____

STIMULATION: Before job; SITP 0 SICP 0 Back Pressure 0
 Fluid used: 5% KCl Company: B.J.

Procedure: 1) Pumped 45 BBLs 5% KCl Max TP 2800 @ 0 BPM
 2) with 1 Ball every 3 BBLs. Avg TP 2000 @ 6 BPM
 3) Flushed with 70 BBLs 5% KCl ISIP 1250
 4) Good Ball action during job. 750 after 5 min
 5) _____ after _____ min
 6) _____ after _____ min
 7) _____
 8) _____
 9) _____
 10) _____
 Displacement fluid used: 5% KCl.

Load Fluid 91 BBLs.

| FLUID RECOVERY (Bbls): | | | FLOWING: | | | | |
|------------------------|-----------|------------|----------|-----|----|----------|------------|
| During Last | Total | Left to | CHK | HRS | TP | RECOVERY | DAILY RATE |
| <u>24</u> hrs. | Recovered | Recover | | | | | |
| BLW <u>29</u> | <u>29</u> | <u>52.</u> | | | | | |
| BLO _____ | _____ | _____ | | | | | |
| BNW _____ | _____ | _____ | | | | | |
| BNO <u>2</u> | <u>2</u> | _____ | | | | | |

SWABBING: #Runs 11 Total Recovered 31
 FL Maint. 4700 Swab Rate (B/H) 1/2 WC 20%

REMARKS: Wellhead Pr. O. Run in the hole with
5 1/2" Packer and set it at 4852'. Run in the hole
with swab tagged fluid at 3700', 200' of fluid entry
overnight. Rigged up B.J. and Broke down perfs as
above. Swashed well to tank. IFL Surface FFL 4700'.
Final rate 1/2 BBL/hr, 80% oil on last run. S.D.F.N.

Completion Supervisor Ken Allen
 Date March 1 1984

COSTS:
 Daily 3700
 Cumulative 12300.00

Well Name W Man Butte 6-33 Completion Unit Garnache 17 Completion Days 4

Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pkr/EOT @ 5 3/2 PBD 5 3/2
 Present Operation Flowing Back Frac Work Fluid SL After Frac

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____
 SPF/#SHOTS _____ SPF/#SHOTS _____ SPF/#SHOT _____
5057 to 5066 _____ to _____ to _____
 _____ to _____ to _____ to _____
 _____ to _____ to _____ to _____

STIMULATION: Before job; SITP 0 SICP 0 Back Pressure 0
 Fluid used: 5% KCl Gelled Company: Haliburton

Procedure: 1) Pumped 5500 gals Pad. Max TP 2550 @ 20 BPM
 2) Pumped 2000 gals 1# / gal 20/40 Sand. Avg TP 1850 @ 20 BPM
 3) Pumped 2500 gals 2# / gal 20/40 Sand ISIP 1880
 4) Pumped 3000 gals 4# / gal 20/40 Sand. 1760 after 5 min
 5) Pumped 3500 gals 1# / gal 20/40 Sand 1720 after 10 min
 6) Pumped ~~2830~~ 9 gals 8# / gal 20/40 Sand. 1700 after 15 min
 7) 2830
 8) Pumped 5300 gals flush. Displacement fluid used: 5% KCl
 9) _____
 10) _____

Load 585 Bbls

| FLUID RECOVERY (Bbls): | | | FLOWING: | | | | |
|------------------------|------------|-------------|--|-----|----|----------|------------|
| During Last | Total | Left to | CHK | HRS | TP | RECOVERY | DAILY RATE |
| <u>24</u> hrs. | Recovered | Recover | | | | | |
| BLW | <u>.5</u> | <u>29.5</u> | | | | | |
| BLO | | <u>585</u> | | | | | |
| BNW | | | | | | | |
| BNO | <u>2.5</u> | <u>4.5</u> | | | | | |
| | | | SWABBING: #Runs _____ Total Recovered _____ | | | | |
| | | | FL Maint. _____ Swab Rate (B/H) _____ WC _____ | | | | |

REMARKS: 16 hr shut in tubing pr 50 psi Gashed
well to tank. I FL 4000'. FFL 4900' Made 4 Runs
recovered 3 Bbls. 80% oil. Released packer washed
fluid down to 4900'. P.O.O.H. Rigged up Haliburton
and fraced well as per above. Shut well in for
nights.

Completion Supervisor _____
 Date March 2 1984
 COSTS:
 Daily 19245
 Cumulative 31345

Well Name W. Han Butte 6-33 Completion Unit Gamache 17 Completion Days 5

Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pkr/EOT @ PBD 5312
 Present Operation Flowing Work Fluid

PERFORATIONS: Size gun Shot Diameter Company:
 SPF/#SHOTS SPF/#SHOTS SPF/#SHOTS
5052 to 5066 to to
 to to to
 to to to

STIMULATION: Before job; SITP SICP Back Pressure
 Fluid used: Company:

Procedure: 1) Max TP @ BPM
 2) Avg TP @ BPM
 3) ISIP
 4) after min
 5) after min
 6) after min
 7) Displacement fluid used:
 8)
 9)
 10)

| FLUID RECOVERY (Bbls): | | | | FLOWING: | | | | |
|------------------------|-------------------|-------------------|-------------------|--|-------------------|-------------------|-------------------|-------------------|
| | During Last | Total | Left to | CHK | HRS | TP | RECOVERY | DAILY RATE |
| | <u>2/0</u> hrs. | Recovered | Recover | | | | | |
| BLW | <u>119</u> | <u>119</u> | <u>517.5</u> | <u>20/64</u> | <u>2</u> | <u>45</u> | <u>14</u> | <u>168</u> |
| BLO | <u> </u> | <u> </u> | <u>466</u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> |
| BNW | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> |
| BNO | <u>20</u> | <u>24.5</u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> | <u> </u> |
| | | | | SWABBING: #Runs <u>11</u> Total Recovered <u>66</u> | | | | |
| | | | | FL Maint. <u>500'</u> Swab Rate (B/H) <u> </u> WC <u> </u> | | | | |

REMARKS: 16 hr. SICP
Wellhead pr. 550 psi Flowed well on 10/64 Choke
for 3 hrs. Well made 60 Bbls water and died. Run packer
and tubing in the hole and ~~set~~ circulated well. Set packer
at 4851. Rigged up to swab well. Swabbed 66 Bbls in
11 Runs, FFL 500'. Oil Cut 40%. Well started to flow
Flowed well for 2 hrs. ~~well~~ on 20/64 Choke. Well
making 2 Bbls per hr, 95% oil on last run. Left
well flowing overnight on 20/64 Choke, ~~45 psi~~ FTP
flowing at 45 psi.

Completion Supervisor COSTS:
 Date March 3 1984 Daily 2250
 Cumulative 24,425
33,725

Well Name N. Men. Fed 6-33 Completion Unit 6 # 17 Completion Days 6

Work String: Size _____ Wt _____ Grd _____ Pkr/EOT @ 4851 PBD 3312
 Present Operation Flow test Work Fluid _____

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____
 _____ SPF/#SHOTS _____ SPF/#SHOTS _____ SPF/#SHOT _____
5057 to 5066 _____ to _____ to _____
 _____ to _____ to _____ to _____
 _____ to _____ to _____ to _____

STIMULATION: Before job; SITP _____ SICP _____ Back Pressure _____
 Fluid used: _____ Company: _____

Procedure: 1) _____ Max TP _____ @ _____ BPM
 2) _____ Avg TP _____ @ _____ BPM
 3) _____ ISIP _____
 4) _____ after _____ min
 5) _____ after _____ min
 6) _____ after _____ min
 7) _____ Displacement fluid used: _____
 8) _____
 9) _____
 10) _____

| FLUID RECOVERY (Bbls): | | | | FLOWING: | | | | |
|------------------------|----------------|--------------|------------|--------------|-----------|--------------|------------|------------|
| | During Last | Total | Left to | CHK | HRS | TP | RECOVERY | DAILY RATE |
| | <u>39</u> hrs. | Recovered | Recover | | | | | |
| BLW | <u>2.5</u> | <u>121.5</u> | <u>515</u> | <u>20/64</u> | <u>39</u> | <u>60-70</u> | <u>381</u> | <u>234</u> |
| BLO | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |
| BNW | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ |
| BNO | <u>387</u> | <u>405.5</u> | _____ | _____ | _____ | _____ | _____ | _____ |

SWABBING: #Runs _____ Total Recovered _____
 FL Maint. _____ Swab Rate (B/H) _____ WC _____

REMARKS: Flow test 14 hrs thru 20/64* choke. FTP 70 psi.
Recovered 150 BNO, 2.5 BLW. Flowed to test tank
additional 3 hrs. Recovered 26 BNO. FTP 60 psi.
Flowed to production tank 22 hrs. Recovered 205 BNO
FTP 60 psi thru 20/64 choke.

Completion Supervisor _____ COSTS: _____
 Date 3-4-84 Daily 1200
 Cumulative 34975

Well Name N. Mon. Fed. 6-33 Completion Unit G. #17 Completion Days 7

Work String: Size _____ Wt _____ Grd _____ Pkr/EOE @ 4851 PBD 5312
 Present Operation Flow test Work Fluid _____

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____
Prep to TOH w/pkr.

| | | | |
|----------------------------|----------------|----------------|----------------|
| SPF/#SHOTS | SPF/#SHOTS | SPF/#SHOTS | SPF/#SHOTS |
| <u>5057</u> to <u>5066</u> | _____ to _____ | _____ to _____ | _____ to _____ |
| _____ to _____ | _____ to _____ | _____ to _____ | _____ to _____ |
| _____ to _____ | _____ to _____ | _____ to _____ | _____ to _____ |

STIMULATION: Before job; SITP _____ SICP _____ Back Pressure _____
 Fluid used: _____ Company: _____

| | |
|--|---|
| Procedure: 1) _____ 2) _____ 3) _____ 4) _____ 5) _____ 6) _____ 7) _____ 8) _____ 9) _____ 10) _____ | Max TP _____ @ _____ BPM Avg TP _____ @ _____ BPM ISIP _____ _____ after _____ min _____ after _____ min _____ after _____ min Displacement fluid used: _____ _____ _____ |
|--|---|

| FLUID RECOVERY (Bbls): | | | FLOWING: | |
|------------------------|-------------------------------|--------------------|--------------------|--|
| | During Last <u>21</u> hrs. | Total Recovered | Left to Recover | |
| BLW | _____ | <u>121.5</u> | <u>515</u> | |
| BLO | _____ | _____ | _____ | |
| BNW | _____ | _____ | _____ | |
| BNO | <u>120</u> | <u>525.5</u> | _____ | |

| CHK | HRS | TP | RECOVERY | DAILY RATE |
|--------------|-----------|-----------|------------|------------|
| <u>2 3/4</u> | <u>21</u> | <u>60</u> | <u>120</u> | <u>137</u> |

| |
|--|
| SWABBING: #Runs _____ Total Recovered _____ |
| FL Maint. _____ Swab Rate (B/H) _____ WC _____ |

REMARKS: Flow test 21 hrs. thru 2 3/4 choke. Surface line plugged. Recovered 120 BNO. Prep to TOH w/pkr.

| | |
|---|--|
| Completion Supervisor _____ Date <u>3-5-84</u> | COSTS: Daily _____ Cumulative <u>150</u> <u>35125</u> |
|---|--|

Well Name W. Monument Pette 6-32 Completion Unit Gemache 17 Completion Days 7

Work String: Size 2 7/8 Wt 6.5 Grd J-55 Pk/EOT @ 5118' PBD 5312
 Present Operation Rigging down Work Fluid _____

TDMO5L Well on pump.

PERFORATIONS: Size gun _____ Shot Diameter _____ Company: _____

| | SPF/#SHOTS | to | SPF/#SHOTS | to |
|-------------|------------|-----------|------------|-----------|
| <u>5057</u> | | <u>to</u> | | <u>to</u> |
| | | <u>to</u> | | <u>to</u> |
| | | <u>to</u> | | <u>to</u> |

STIMULATION: Before job; SITP _____ SICP _____ Back Pressure _____
 Fluid used: _____ Company: _____

Procedure: 1) _____ Max TP _____ @ _____ BPM
 2) _____ Avg TP _____ @ _____ BPM
 3) _____ ISIP _____
 4) _____ after _____ min
 5) _____ after _____ min
 6) _____ after _____ min
 7) _____ Displacement fluid used: _____
 8) _____
 9) _____
 10) _____

| FLUID RECOVERY (Bbls): | | | |
|------------------------|-------------------------------|--------------------|--------------------|
| | During Last <u>24</u> hrs. | Total Recovered | Left to Recover |
| BLW | _____ | <u>121.5</u> | <u>515</u> |
| BLO | _____ | _____ | _____ |
| BNW | _____ | _____ | _____ |
| BNO | <u>10</u> | <u>535.5</u> | _____ |

| FLOWING: | | | | |
|------------|------------|-----------|-----------------|-------------------|
| <u>CHK</u> | <u>HRS</u> | <u>TP</u> | <u>RECOVERY</u> | <u>DAILY RATE</u> |
| _____ | _____ | _____ | _____ | _____ |
| _____ | _____ | _____ | _____ | _____ |

| | |
|-----------------------|--------------------------------|
| SWABBING: #Runs _____ | Total Recovered _____ |
| FL Maint. _____ | Swab Rate (B/H) _____ WC _____ |

REMARKS: Have plugged on flowline. Released packer and flowed well until it died. Packed packer out of the hole. Run in the hole with TTHW/5.N. notched collar, 2 ft tubing, pump seating nipple, 2 ft tubing, tubing anchor, and 153 ft of tubing. EOT at 5118, S.N. at 5053, Anchor at 4987'. Set anchor and landed tubing with 8000 # tension. Removed BOP's and made safe wellhead. Picked up 1 1/2" pump, 4 int rods, and run in the hole with 3 1/2" Rods. 197-3/4" Rods. 1-4' x 3/4" Pany Rod, and 1-1 1/2" Polich Rod. Started Well on pump @ 5:15 PM. S.D.R.N.

Completion Supervisor _____
 Date March 6 1984

COSTS:
 Daily 2400 5500
 Cumulative 2400 5500
840625



ATTACHMENT 6-1
12 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16

Report Date: June 17, 2001

Completion Day: 01

Present Operation: Recompletion

Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 51/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 EOT @: BP/Sand PBTD:

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------------|------------|------------|------|-------|------------|
| D2 sds exist | 5057-5066' | 2/18 | | | |
| CP2 sds exist | 5932-5960' | 1/28 | | | |
| | | | | | |
| | | | | | |
| | | | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 16, 2001

SITP: 0 SICP: 0

MIRU Ross # 11. RU HO trk to csg & pump 80 BW @ 225°F, then 100 bbls condensate (cold), then 140 BW @ 225°F. Had returns after 160 bbls pumped. Unseat rod pump. Flush tbg & rods W 60 BW @ 225°F. Returned 75 BW & 40 BO. TOH W/ rod string. LD pump. Had light scale buildup on btm 1500' of rod string. ND wellhead. Release TA @ 5861'. TOH & talley production tbg. LD BHA. Did not find hole in tbg. TIH W/ 4 3/4" bit, 5 1/2" csg scraper, new SN (W/ standing valve in place) & 40 jts tbg. EOT @ 1260'. SIFN W/ est 205 BWTR.

FLUID RECOVERY (BBLs)

| | | | | | |
|--------------------------------------|------|------------------------------|--------|-------------------|----------------|
| Starting fluid load to be recovered: | 0 | Starting oil to rec to date: | 100 BC | | |
| Fluid lost/recovered today: | 205 | Oil lost/recovered today: | 40 | | |
| Ending fluid to be recovered: | 205 | Cum oil recovered: | 40 | | |
| IFL: | FFL: | FTP: | Choke: | Final Fluid Rate: | Final oil cut: |

STIMULATION DETAIL

COSTS

Base Fluid used: Job Type:

Company:

Procedure or Equipment detail:

| | |
|--------------------|---------|
| Ross rig | \$2,345 |
| Weatherford BOP | \$130 |
| Hagman Trucking | \$1,400 |
| 100 BC | \$3,000 |
| Zubiate HO trk | \$702 |
| IPC wtr truck | \$500 |
| Randys pump repair | \$950 |
| Randys TA repair | \$300 |
| TMT wtr truck | \$500 |
| IPC Supervision | \$200 |

Max TP: Max Rate: Total fluid pmpd:

Avg TP: Avg Rate: Total Prop pmpd:

ISIP: 5 min: 10 min: 15 min:

Completion Supervisor: Gary Dietz

DAILY COST: \$10,027

TOTAL WELL COST: \$10,027



ATTACHMENT G-1
13 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16

Report Date: June 19, 2001

Completion Day: 02

Present Operation: Recompletion

Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 51/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 EOT @: 0 BP/Sand PBTD: 6122'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------------|------------|------------|------|-------|------------|
| D2 sds exist | 5057-5066' | 2/18 | | | |
| CP2 sds exist | 5932-5960' | 1/28 | | | |
| | | | | | |
| | | | | | |
| | | | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 18, 2001

SITP: 0 SICP: 0

W/ bit, scraper, SN & 40 jts tbg in well, pump 10 BW dn tbg to pressure test. Tbg on Vacuum. TOH, LD split jt. Remove standing valve f/ SN (buried in scale chips). TIH W/ BHA & 185 good jts J-55 tbg. PU 2 jts work string. Tag fill @ 5992'. RU power swivel. C/O fill to PBTD @ 6122'. Circ hole clean. Lost 390 BW during C/O. RD drlg equipment. TOH W/ tbg. LD bit & scraper. SIFN W/ est 605 BWTR.

FLUID RECOVERY (BBLs)

| | | | |
|--------------------------------------|-----|--------------------------------------|----------------------|
| Starting fluid load to be recovered: | 205 | Starting oil to rec to date: | 100 BC |
| Fluid lost/recovered today: | 400 | Oil lost/recovered today: | 40 |
| Ending fluid to be recovered: | 605 | Cum oil recovered: | 40 |
| IFL: _____ FFL: _____ FTP: _____ | | Choke: _____ Final Fluid Rate: _____ | Final oil cut: _____ |

STIMULATION DETAIL

COSTS

Base Fluid used: _____ Job Type: _____

Company: _____

Procedure or Equipment detail: _____

| | |
|------------------------|---------|
| Ross rig | \$2,330 |
| Weatherford BOP | \$130 |
| IPC rst. Labor | \$300 |
| ICO/IPC trucking(L-80) | \$300 |
| Four Star (pwr swivel) | \$550 |
| IPC water truck | \$300 |
| Unichem(scale inhib) | \$300 |
| IPC Supervision | \$200 |

Max TP: _____ Max Rate: _____ Total fluid pmpd: _____

Avg TP: _____ Avg Rate: _____ Total Prop pmpd: _____

ISIP: _____ 5 min: _____ 10 min: _____ 15 min: _____

Completion Supervisor: Gary Dietz

DAILY COST: \$4,410

TOTAL WELL COST: \$14,437

Completion Day: 03Rig: ROSS #11

WELL STATUS

| | | | | | | | | | | | |
|-----------|--------------------|---|-------------|-------------|-----------------------|-----|---------------|--------------|----------------------|--------------|--------------|
| Surf Csg: | <u>85/8"</u> | @ | <u>280'</u> | Prod Csg: | <u>51/2"</u> | Wt: | <u>17#</u> | @ | <u>6168'</u> | Csg PBTD: | <u>6122'</u> |
| Tbg: | <u>Size: 2 7/8</u> | | Wt: | <u>6.5#</u> | <u>Grd: L-80/N-80</u> | | <u>Pkr @:</u> | <u>6030'</u> | <u>BP/Sand PBTD:</u> | <u>6088'</u> | |

PERFORATION RECORD

| <u>Zone</u> | | <u>Perfs</u> | <u>SPF/#shots</u> | <u>Zone</u> | | <u>Perfs</u> | <u>SPF/#shots</u> |
|-------------|--------------|--------------|-------------------|-------------|--------------|--------------|-------------------|
| GB4 sds | <u>new</u> | 4505-4519' | 4/56 | LDC sds | <u>new</u> | 5652-5666' | 4/56 |
| GB6 sds | <u>new</u> | 4544-4555' | 4/44 | CP2 sds | <u>exist</u> | 5932-5960' | 1/28 |
| D2 sds | <u>exist</u> | 5057-5066' | 2/18 | CP3 sds | <u>new</u> | 6010-6018' | 4/32 |
| C sds | <u>new</u> | 5184-5194' | 4/40 | CP3 sds | <u>new</u> | 6040-6046' | 4/24 |
| A1 sds | <u>new</u> | 5450-5458' | 4/32 | | | | |

CHRONOLOGICAL OPERATIONS

SITP: 0 SICP: 0

RU Schlumberger. Perf new intervals as follows: CP3 sds @ 6040-46' & 6010-18'; LDC sds @ 5652-66'; A1 sds @ 5450-58'; C sds @ 5184-94'; GB6 sds @ 4544-55' & GB4 sds @ 4505-19'. All 4 JSPF. 4 runs total. RD WLT. PU & TIH W/ Weatherford 5 1/2" "TS" RBP, 2 3/8 tbg sub, 5 1/2" "HD" pkr & L-80/N-80 tbg. Isolate CP3 sds @ 6040-46'. RBP @ 6088', pkr @ 6030'. Fill tbg W/ 20 BW. Attempt to breakdown perfs. Rig pump engine failure. Release pkr. SIFN W/ est 625 BWTR.

FLUID RECOVERY (BBLS)

| | | | | | |
|--------------------------------------|------------|-----------------------------------|---------------|-------------------|----------------|
| Starting fluid load to be recovered: | <u>605</u> | Starting oil to rec to date: | <u>100 BC</u> | | |
| Fluid <u>lost</u> /recovered today: | <u>20</u> | Oil <u>lost</u> /recovered today: | <u>40</u> | | |
| Ending fluid to be recovered: | <u>625</u> | Cum oil recovered: | <u>40</u> | | |
| IFL: | FFL: | FTP: | Choke: | Final Fluid Rate: | Final oil cut: |

STIMULATION DETAIL

Base Fluid used: Job Type:

Company:

Procedure or Equipment detail:

COSTS

| | |
|----------|---------|
| Ross rig | \$2,275 |
|----------|---------|

| | |
|-----------------|-------|
| Weatherford BOP | \$130 |
|-----------------|-------|

| | |
|---------------|-------|
| IPC wtr truck | \$300 |
|---------------|-------|

| | |
|--------------------|---------|
| Schlumberger-perfs | \$5,840 |
|--------------------|---------|

| | |
|------------------------|---------|
| Weatherford-tools/serv | \$3,000 |
|------------------------|---------|

| | |
|-----------------|-------|
| IPC Supervision | \$200 |
|-----------------|-------|

DAILY COST: \$11,745

TOTAL WELL COST: \$20,102

Max TP: Max Rate: Total fluid pmpd:

Avg TP: Avg Rate: Total Prop pmpd:

ISIP: 5 min: 10 min: 15 min:

Completion Supervisor: Gary Dietz

| | |
|-------------|----------|
| DAILY COST: | \$11,745 |
|-------------|----------|

TOTAL WELL COST: \$26,182



ATTACHMENT G-1
15 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16

Report Date: June 21, 2001

Completion Day: 04

Present Operation: Recompletion

Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 51/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: L-80/N-80 Pkr @: 5340' BP/Sand PBTD: 5500'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------|------------------|------------|---------|------------------|------------|
| GB4 sds | new 4505-4519' | 4/56 | LDC sds | new 5652-5666' | 4/56 |
| GB6 sds | new 4544-4555' | 4/44 | CP2 sds | exist 5932-5960' | 1/28 |
| D2 sds | exist 5057-5066' | 2/18 | CP3 sds | new 6010-6018' | 4/32 |
| C sds | new 5184-5194' | 4/40 | CP3 sds | new 6040-6046' | 4/24 |
| A1 sds | new 5450-5458' | 4/32 | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 20, 2001

SITP: 0 SICP: 0

Set pkr @ 6028' (RBP @ 6088'). RU BJ Services to tbg. Fill tbg W/ 21 BW & breakdown CP3 sds (6040-46') @ 3856 psi. Injection rate after 13 bbls of 7.6 BPM @ 3440 psi. Move tools & isolate CP3 sds (6010-18'). RBP @ 6028' & pkr @ 5986'. RU BJ, fill tbg & breakdown perfs @ 3212 psi. Injection rate of 9.2 BPM @ 4835 psi after 10 bbls. Used 60 bbls for both BD's. Retrieve RBP & re-set @ 5700'. Set pkr @ 5540' W/ frac valve sub collar under pipe rams. RU BJ to tbg to frac LDC sds (5652-66'). Perfs broke dn @ 3775 psi. Pumped 19,595# 20/40 sd in 233 bbls Viking I-25. Treated W/ ave rate of 14.7 BPM W/ ave press of 5640 psi. Pressure increased W/ alarming rate. Cut sd @ blender @ 6 ppg sd. Screened out W/ 5 ppg sd on perfs W/ 168 gals flushed (1289 gals short of top perf). Est 14,045# sd in perfs & left approx. 5,550# sd in pipe. Used 105 BW filling annulus & holding 300 psi during frac. RD BJ. Flowback LDC frac for 1 1/2 hrs & died. Rec 51 BTF (est 22% of frac load). Fill annulus, release pkr & circ hole clean. C/O sd to RBP @ 5700'. Lost add'l 90 BW. Release plug. Pull up & reset @ 5500'. Set pkr above, press test plug to 2000 psi. Release pkr, reset @ 5340' W/ frac valve installed. Pressure against perfs @ 2000 psi. Perfs won't break. Release pkr. SIFN W/ est 1062 BWTR.

FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 625 Starting oil to rec to date: 100 BC
Fluid lost/recovered today: 437 Oil lost/recovered today: 40
Ending fluid to be recovered: 1062 Cum oil recovered: 40
IFL: _____ FFL: _____ FTP: _____ Choke: none Final Fluid Rate: _____ Final oil cut: _____

STIMULATION DETAIL

COSTS

Base Fluid used: Viking I-25 Job Type: Sand frac
Company: BJ Services

Procedure or Equipment detail: LDC sands

4500 gals of pad
3900 gals W/ 1-5 ppg of 20/40 sand
1224 gals W/ 5-6 ppg of 20/40 sand (of 7800 gals 5-8 ppg stage)
Flush W/ 168 gals of slick water (1289 gals short of top perf)
Screened out W/ 5 ppg sd on perfs (cut sd @ blender @ 6 ppg)
Est 14,045# sd in perfs, est 5,550# sd left in pipe.

Ross rig \$1,918
Weatherford BOP \$130
IPC wtr truck (disposal) \$300
BJ Services-LDC sds \$24,031
Weatherford-tools/serv \$500
Frac water (trucked) \$400
Fuel gas (+/- 30 mcf) \$150
IPC Supervision \$200

Max TP: 7800 Max Rate: 14.8 BPM Total fluid pmpd: 233 bbls
Avg TP: 5640 Avg Rate: 14.7 BPM Total Prop pmpd: 19,595#
ISIP: NA 5 min: _____ 10 min: _____ 15 min: _____
Completion Supervisor: Gary Dietz

DAILY COST: \$27,629
TOTAL WELL COST: \$53,811



ATTACHMENT G-1
16 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16

Report Date: June 22, 2001

Completion Day: 05

Present Operation: Recompletion

Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 5 1/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: L-80/N-80 Pkr @: 5095' BP/Sand PBTD: 5220'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|--------------|------------|------------|---------------|------------|------------|
| GB4 sds new | 4505-4519' | 4/56 | LDC sds new | 5652-5666' | 4/56 |
| GB6 sds new | 4544-4555' | 4/44 | CP2 sds exist | 5932-5960' | 1/28 |
| D2 sds exist | 5057-5066' | 2/18 | CP3 sds new | 6010-6018' | 4/32 |
| C sds new | 5184-5194' | 4/40 | CP3 sds new | 6040-6046' | 4/24 |
| A1 sds new | 5450-5458' | 4/32 | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 21, 2001

SITP: 0 SICP: 0

Set pkr @5340' (RBP @ 5220'). RU BJ Services to tbg W/ frac valve sub collar under pipe rams. Breakdown A-1 sds (5450-58') @ 6080 psi. Injection rate after 11 bbls of 10 BPM @ 3880 psi. Used 11 bbls. Frac A-1. Pumped 40,600# 20/40 sd in 256 bbls Viking I-25. Treated W/ ave rate of 14.6 BPM W/ ave press of 3900 psi. Screened out with 28 of 30 bbls flushed (147 gals short of top perf). Used 35 bbls water to hold psi on csgn during frac. RD BJ. Flowback A1 frac for 1/2 hr. & died. Rec 40 BTF (est 14% of frac load). Release pkr & circ hole clean. C/O sd to RBP @ 5470'. Lost add'l 40 BW. Release plug. Pull up & reset @ 5220'. Set pkr above, press test plug to 2000 psi. Release pkr, reset @ 5095' W/ frac valve installed. Pressure against perfs @ 2000 psi. Perfs won't break. Release pkr. SIFN W/ est 1392 BWTR.

FLUID RECOVERY (BBLs)

| | | | |
|--------------------------------------|------|------------------------------|--|
| Starting fluid load to be recovered: | 1062 | Starting oil to rec to date: | 100 BC |
| Fluid lost/recovered today: | 330 | Oil lost/recovered today: | 40 |
| Ending fluid to be recovered: | 1392 | Cum oil recovered: | 40 |
| IFL: _____ FFL: _____ FTP: _____ | | Choke: none | Final Fluid Rate: _____ Final oil cut: _____ |

STIMULATION DETAIL

COSTS

Base Fluid used: Viking I-25 Job Type: Sand frac
Company: BJ Services

Procedure or Equipment detail: LDC sands

2750 gals of pad
2500 gals W/ 1-5 ppg of 20/40 sand
5000 gals W/ 5-6 ppg of 20/40 sand (of 7800 gals 5-8 ppg stage)
Flush W/ 1176 gals of slick water (147 gals short of top perf)

1.3 F.G.

Max TP: 7200 Max Rate: 14.8 BPM Total fluid pmpd: 284
Avg TP: 3900 Avg Rate: 14.6 BPM Total Prop pmpd: 40,600#
ISIP: 4475 5 min: _____ 10 min: _____ 15 min: _____
Completion Supervisor: Pat Wisener

| | |
|------------------------|----------|
| Ross rig | \$1,300 |
| Weatherford BOP | \$130 |
| Troy Murray (disposal) | \$300 |
| BJ Services-A1 sds | \$22,642 |
| Weatherford-tools/serv | \$500 |
| Frac water (trucked) | \$400 |
| Fuel gas (+/- 30 mcf) | \$150 |
| IPC Supervision | \$200 |

DAILY COST: \$25,622
TOTAL WELL COST: \$79,433



ATTACHMENT G-1
17 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16

Report Date: June 23, 2001

Completion Day: 06

Present Operation: Recompletion

Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 5 1/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: L-80/N-80 Pkr @: 5095' BP/Sand PBTD: 4620'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|--------------|------------|------------|---------------|------------|------------|
| GB4 sds new | 4505-4519' | 4/56 | LDC sds new | 5652-5666' | 4/56 |
| GB6 sds new | 4544-4555' | 4/44 | CP2 sds exist | 5932-5960' | 1/28 |
| D2 sds exist | 5057-5066' | 2/18 | CP3 sds new | 6010-6018' | 4/32 |
| C sds new | 5184-5194' | 4/40 | CP3 sds new | 6040-6046' | 4/24 |
| A1 sds new | 5450-5458' | 4/32 | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 22, 2001

SITP: 0 SICP: 0

Set pkr @5090" (RBP @ 5220'). RU BJ Services to tbg W/ frac valve sub collar under pipe rams. Breakdown A-1 sds (5450-58') @ 3510 psi. Injection rate after 10 bbls of 10 BPM @ 1910 psi. Used 10 bbls. Frac C-1. Pumped 37,4130# 20/40 sd in 236 bbls Viking I-25. Treated W/ ave rate of 15.2 BPM W/ ave press of 3500 psi. Used 105 bbls water to hold psi on csqn during frac. RD BJ. Flowback C1 frac for 2.5 hr. & died. Rec 94 BTF (est 36% of frac load). Release pkr & circ hole clean. C/O sd to RBP @ 5220'. Lost add'l 85 BW. Release plug. Pull up & reset @ 4620'. Set pkr above, press test plug to 2000 psi. TOH and lay down packer prepare to frac monday am.. SIFN W/ est 1392 BWTR.

FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1392 Starting oil to rec to date: 140
Fluid lost/recovered today: 629 Oil lost/recovered today:
Ending fluid to be recovered: 763 Cum oil recovered:
IFL: FFL: FTP: Choke: none Final Fluid Rate: Final oil cut:

STIMULATION DETAIL

COSTS

Base Fluid used: Viking I-25 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: C sands

2250 gals of pad

2300 gals W/ 1-5 ppg of 20/40 sand

4600 gals W/ 5-6 ppg of 20/40 sand

Flush W/ 1239 gals of slick water

1.02 F.G.

Ross rig \$1,818

Weatherford BOP \$130

BJ Services-C2sds \$21,252

Weatherford-tools/serv \$500

Frac water (trucked) \$400

Fuel gas (+/- 30 mcf) \$150

IPC Supervision \$200

Max TP: 4140 Max Rate: 15.3 BPM Total fluid pmpd: 266

Avg TP: 3500 Avg Rate: 15.3 BPM Total Prop pmpd: 37,4130#

ISIP: 3040 5 min: 10 min: 15 min:

Completion Supervisor: Pat Wisener

DAILY COST: \$24,450

TOTAL WELL COST: \$103,883

ATTACHMENT G-1
18 of 23

DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16Report Date: June 26, 2001Completion Day: 07Present Operation: RecompletionRig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 5 1/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: L-80/N-80 EOT @: 1544' BP/Sand PBTD:

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------|------------------|------------|---------|------------------|------------|
| GB4 sds | new 4505-4519' | 4/56 | LDC sds | new 5652-5666' | 4/56 |
| GB6 sds | new 4544-4555' | 4/44 | CP2 sds | exist 5932-5960' | 1/28 |
| D2 sds | exist 5057-5066' | 2/18 | CP3 sds | new 6010-6018' | 4/32 |
| C sds | new 5184-5194' | 4/40 | CP3 sds | new 6040-6046' | 4/24 |
| A1 sds | new 5450-5458' | 4/32 | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 25, 2001SITP: 0 SICP: 0

NU isolation tool. RU BJ Services and frac GB4/GB6 sds W/ 112,834# 20/40 sand in 670 bbls Viking I-25 fluid. Perfs broke dn @ 2085 psi. Treated @ ave press of 2140 psi W/ ave rate of 30.9 BPM. ISIP-2330 psi. RD BJ. Begin immediate flowback of GB frac on 12/64 choke @ 1 BPM. Zone flowed 4 hrs & died. Rec 208 BTF (est 31% of frac load). ND isolation tool. TIH W/ RH & tbg. Tbg displaced 11 BW on TIH. Tag sd @ 4557'. C/O sd to RBP @ 4620'. Circ hole clean. Lost no fluid. Release plug. TOH & LD frac tbg on floats. SIFN W/ EOT @ 1544'. Est 2215 BWTR.

FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1764(corr) Starting oil to rec to date: 100 BC
Fluid lost/recovered today: 451 Oil lost/recovered today:
Ending fluid to be recovered: 2215 Cum oil recovered: 40
IFL: FFL: FTP: Choke: 12/64 Final Fluid Rate: Final oil cut:

STIMULATION DETAIL

Base Fluid used: Viking I-25 Job Type: Sand fracCompany: BJ ServicesProcedure or Equipment detail: GB4/GB6 sands6000 gals of pad5750 gals W/ 1-5 ppg of 20/40 sand10500 gals W/ 5-8 ppg of 20/40 sand1558 gals W/ 8 ppg of 20/40 sandFlush W/ 4326 gals of slick water

COSTS

| | |
|---------------------------|----------|
| Ross rig | \$2,180 |
| Weatherford BOP | \$130 |
| IPC frac tks (3 X 7 days) | \$840 |
| BJ Services-GB sds | \$33,364 |
| Fuel gas (+/- 15 mcf) | \$75 |
| Frac water (trucked) | \$300 |
| IPC frac tbg (.07/day) | \$3,087 |
| IPC trucking (tbg) | \$400 |
| IPC Frac valve rental | \$1,500 |
| IPC Supervision | \$200 |

Max TP: 2686 Max Rate: 31.3 BPM Total fluid pmpd: 670 bblsAvg TP: 2140 Avg Rate: 30.9 BPM Total Prop pmpd: 112,834#ISIP: 2330 5 min: 10 min: FG: Completion Supervisor: Gary DietzDAILY COST: \$42,076TOTAL WELL COST: \$145,959



DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16Report Date: June 27, 2001Completion Day: 08Present Operation: RecompletionRig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 5 1/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 EOT @: 6016' BP/Sand PBTD: 6046'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------|-------|------------|---------|-------|------------|
| GB4 sds | new | 4505-4519' | LDC sds | new | 5652-5666' |
| GB6 sds | new | 4544-4555' | CP2 sds | exist | 5932-5960' |
| D2 sds | exist | 5057-5066' | CP3 sds | new | 6010-6018' |
| C sds | new | 5184-5194' | CP3 sds | new | 6040-6046' |
| A1 sds | new | 5450-5458' | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 26, 2001SITP: 400 SICP: 400

Bleed gas off well. Con't TOH & LD frac tbg on floats. 26 jts W/ bad threads. LD RBP & RH. TIH W/ NC & J-55 tbg. Tag sd @ 6046' (@ btm perf). Pull EOT to 6016'. RU swab equipment. IFL @ 500'. Made 10 swb runs W/ well flowing between later runs. Rec 159 BTF (est 80 BW, 79 BO) W/ heavy sand in samples & strong gas. FFL @ sfc-1100'. FOC @ 50%. SIFN W/ est 2135 BWTR.

FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 2215 Starting oil to rec to date: 100 BC
Fluid lost/recovered today: 80 Oil lost/recovered today: 79
Ending fluid to be recovered: 2135 Cum oil recovered: 119
IFL: 500' FFL: sfc-1100' FTP: _____ Choke: _____ Final Fluid Rate: _____ Final oil cut: 50%

STIMULATION DETAIL

Base Fluid used: _____ Job Type: _____

Company: _____

Procedure or Equipment detail: _____

COSTS

| | |
|-----------------|---------|
| Ross rig | \$2,245 |
| Weatherford BOP | \$130 |
| IPC wtr truck | \$300 |
| IPC Supervision | \$200 |

Max TP: _____ Max Rate: _____ Total fluid pmpd: _____

Avg TP: _____ Avg Rate: _____ Total Prop pmpd: _____

ISIP: _____ 5 min: _____ 10 min: _____ FG: _____

Completion Supervisor: Gary DietzDAILY COST: \$2,875TOTAL WELL COST: \$148,834



DAILY COMPLETION REPORT

WELL NAME: Travis Federal 6-33-8-16 Report Date: June 28, 2001 Completion Day: 09
Present Operation: Recompletion Rig: ROSS #11

WELL STATUS

Surf Csg: 85/8" @ 280' Prod Csg: 5 1/2" Wt: 17# @ 6168' Csg PBTD: 6122'
Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 EOT @: 6016' BP/Sand PBTD: 6046'

PERFORATION RECORD

| Zone | Perfs | SPF/#shots | Zone | Perfs | SPF/#shots |
|---------------------|-------------------|-------------|----------------------|-------------------|-------------|
| GB4 sds <u>new</u> | <u>4505-4519'</u> | <u>4/56</u> | LDC sds <u>new</u> | <u>5652-5666'</u> | <u>4/56</u> |
| GB6 sds <u>new</u> | <u>4544-4555'</u> | <u>4/44</u> | CP2 sds <u>exist</u> | <u>5932-5960'</u> | <u>1/28</u> |
| D2 sds <u>exist</u> | <u>5057-5066'</u> | <u>2/18</u> | CP3 sds <u>new</u> | <u>6010-6018'</u> | <u>4/32</u> |
| C sds <u>new</u> | <u>5184-5194'</u> | <u>4/40</u> | CP3 sds <u>new</u> | <u>6040-6046'</u> | <u>4/24</u> |
| A1 sds <u>new</u> | <u>5450-5458'</u> | <u>4/32</u> | | | |

CHRONOLOGICAL OPERATIONS

Date Work Performed: June 27, 2001 SITP: 500 SICP: 500
Bleed gas off well. RU swab equipment to con't swabbing all zones for cleanup. IFL @ 200'. Made 8 swb runs W/ well flowing between runs. Rec 165 BTF (est 103 BO & 62 BW) W/ strong gas. FOC @ 70%. Sd cleaned up @ end. Switch into production tks. Leave well flowing on 48/64" adjustable choke. Release rig crew.
@ 6:00 AM 6/28/01: Well still flowing slightly. Last 15 hrs rec 47 BTF (est 32 BO & 15 BW). Est 2058 BWTR.

FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 2135 Starting oil to rec to date: 100 BC
Fluid lost/recovered today: 77 Oil lost/recovered today: 135 154
Ending fluid to be recovered: 2058 Cum oil recovered: 254
IFL: 200' FFL: sfc FTP: Choke: 48/64 Final Fluid Rate: Final oil cut: 70%

STIMULATION DETAIL

Base Fluid used: Job Type:
Company:
Procedure or Equipment detail:

COSTS

| | |
|-----------------|---------|
| Ross rig | \$1,707 |
| Weatherford BOP | \$130 |
| TMT wtr truck | \$300 |
| Rebel HO trk | \$400 |
| IPC Supervision | \$200 |

Max TP: Max Rate: Total fluid pmpd:
Avg TP: Avg Rate: Total Prop pmpd:
ISIP: 5 min: 10 min: FG:
Completion Supervisor: Gary Dietz

DAILY COST: \$2,737
TOTAL WELL COST: \$151,571



Completion Day: 10

Rig: ROSS #11

| | | | | |
|-----------------------------------|------------------------------|-------------------|----------------------------|---------|
| | <u>PRODUCTION TBG DETAIL</u> | <u>ROD DETAIL</u> | Ross rig | \$1,225 |
| KB | | | Weatherford BOP | \$130 |
| | | | IPC Supervision | \$200 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | DAILY COST: | \$1,555 |
| Completion Supervisor: Gary Dietz | | | TOTAL WELL COST: \$153,126 | |



Completion Day: 11

Rig: ROSS #11

TOTAL WELL COST: \$157,596



Completion Day: 12

Rig: ROSS #11

Completion Supervisor: Gary Dietz

ATTACHMENT H

WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1. Set CIBP @ 4455'
2. Plug #1 Set 100' plug on top of CIBP using 12 sx Class "G" cement
3. Plug #2 183' balance plug using 21 sx Class "G" cement 50' above Trona-Bird's Nest extending 50' below base of Mahogany Oil Shale
4. Perforate 4 JSPF @ 1795'
5. Plug #3 120' plug covering Uinta/Green River formation using 25sx Class "G" cement pumped under CICR and out perforations. Follow using 7 sx Class "G" cement pumped on top of CICR
6. Perforate 4 JSPF @ 330'
7. Plug #4 Circulate 93 sx Class "G" cement down 5 ½" casing and up the 5-1/2" x 8-5/8" annulus

he approximate cost to plug and abandon this well is \$42,000.

Federal #6-33

Spud Date: 8/3/83
Put on Production: 9/7/83
GL: 5678' KB: 5688'

Proposed P & A Wellbore Diagram


INITIAL PRODUCTION: 22 bopd, 3 bwpd

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (281')
DEPTH LANDED: 280'
HOLE SIZE: 12 1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 17.0#
LENGTH: 154 jts.
DEPTH LANDED: 6168'
HOLE SIZE: 7 7/8"
CEMENT DATA: 453 sk RFC & 155 sxs lodense.
CEMENT TOP AT: 1965'



Federal #6-33

1982' FNL & 1978' FWL

SE/NW Section 33-T8S-R16E

Duchesne Co, Utah

API #43-013-30747; Lease #UTU-34173

JL 11/18/10

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

SUBMIT IN TRIPLICATE - Other Instructions on page 2

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone (include area code)
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1982 FNL 1978 FWL
SENE Section 33 T8S R16E

5. Lease Serial No.

USA UTU-34173

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or
GMBU

8. Well Name and No.
FEDERAL 6-33

9. API Well No.
4301330747

10. Field and Pool, or Exploratory Area
GREATER MB UNIT

11. County or Parish, State
DUCHESNE, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|--|---|---|--|---|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | |
| | <input checked="" type="checkbox"/> Convert to Injector | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation: (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield Production proposes to convert the above mentioned well from a producing oil well to an injection well.

I hereby certify that the foregoing is true and correct (Printed/ Typed)

Jill Loyie

Signature

Title

Regulatory Technician

Date

11/22/2010

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on page 2)

AFFIDAVIT OF PUBLICATION


County of Duchesne,
STATE OF UTAH

I, Geoff Liesik on oath, say that I am the EDITOR of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for 1 consecutive issues, and that the first publication was on the 21 day of December, 20 10, and that the last publication of such notice was in the issue of such newspaper dated the 21 day of December, 20 10, and that said notice was published on Utahlegals.com on the same day as the first newspaper publication and the notice remained on Utahlegals.com until the end of the scheduled run.


Editor

Subscribed and sworn to before me this

22 day of December, 20 10


Notary Public



BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-370

IN THE MATTER OF
THE APPLICATION OF
NEWFIELD PRODUCTION
COMPANY FOR
ADMINISTRATIVE APPROVAL OF CERTAIN
WELLS LOCATED IN
SECTIONS 33 AND 34,
TOWNSHIP 8 SOUTH,
RANGE 16 EAST, SECTION
15, TOWNSHIP 9
SOUTH, RANGE 15
EAST, AND SECTIONS
1, 3, AND 14, TOWNSHIP 9
SOUTH, RANGE 16
EAST, DUCHESNE
COUNTY, UTAH, AS
CLASS II INJECTION
WELLS.

THE STATE OF UTAH
TO ALL PERSONS INTERESTED IN THE
ABOVE ENTITLED
MATTER.

Notice is hereby given
that the Division of Oil,
Gas and Mining (the "Division") is commencing
an informal adjudicative
proceeding to consider the
application of Newfield
Production Company
for administrative approval of the following
wells located in Duchesne
County, Utah, for conversion to Class II injection
wells:

Greater Monument
Butte Unit:

Federal 6-33 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East

Travis Federal 7-33-8-16 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East

ship 8 South, Range 16 East

Monument Butte Federal 4-34(1) well located in NW/4 NW/4, Section 34, Township 8 South, Range 16 East

Ashley Federal 8-15-9-15 well located in SE/4 NE/4, Section 15, Township 9 South, Range 15 East

Monument Butte 1-43 well located in NE/4 SE/4, Section 1, Township 9 South, Range 16 East

Monument Butte 1-34 well located in SW/4 SE/4, Section 1, Township 9 South, Range 16 East

South Wells Draw 6-3-9-16 well located in SE/4 NW/4, Section 3, Township 9 South, Range 16 East

South Wells Draw Federal 10-3-9-16 well located in NW/4 SE/4, Section 3, Township 9 South, Range 16 East

Jonah Federal 10-14-9-16 well located in NW/4 SE/4, Section 14, Township 9 South, Range 16 East

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water

for 41 ro

and Jordan

Suzzy V

Free-thr

and Union

Free-thr

are: Alta

half time

a 13-7 ru

had led

and won

ter to go

team use

The C

59-55.

Green Ri

Riverton

Union bo

close sha

Gillette,

to return

PROOF OF PUBLICATION

CUSTOMER'S COPY

| CUSTOMER NAME AND ADDRESS | ACCOUNT NUMBER | DATE |
|--|----------------|------------|
| DIV OF OIL-GAS & MINING, 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114 | 9001402352 | 12/20/2010 |

BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH
NOTICE OF AGENCY ACTION
CAUSE NO. UIC-370

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 33 AND 34, TOWNSHIP 8 SOUTH, RANGE 16 EAST, SECTION 15, TOWNSHIP 9 SOUTH, RANGE 15 EAST, AND SECTIONS 1, 3, AND 14, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER:

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:
Federal 6-33 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East
Travis Federal 7-33-8-16 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East
Monument Butte Federal 4-34(1) well located in NW/4 NW/4, Section 34, Township 8 South, Range 16 East
Ashley Federal 8-15-9-15 well located in SE/4 NE/4, Section 15, Township 9 South, Range 15 East
Monument Butte 1-43 well located in NE/4 SE/4, Section 1, Township 9 South, Range 16 East
Monument Butte 1-34 well located in SW/4 SE/4, Section 1, Township 9 South, Range 16 East
South Wells Draw 6-3-9-16 well located in SE/4 NW/4, Section 3, Township 9 South, Range 16 East
South Wells Draw Federal 10-3-9-16 well located in NW/4 SE/4, Section 3, Township 9 South, Range 16 East
Jonah Federal 10-14-9-16 well located in NW/4 SE/4, Section 14, Township 9 South, Range 16 East

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 13th day of December, 2010.

STATE OF UTAH
DIVISION OF OIL, GAS & MINING
s/ Brad Hill
Brad Hill
Permitting Manager

647204

UPAXLP

| ACCOUNT NAME | | | |
|--|--|---------------------------|-------------|
| DIV OF OIL-GAS & MINING, | | | |
| TELEPHONE | | ADORDER# / INVOICE NUMBER | |
| 8015385340 | | 0000647204 / | |
| SCHEDULE | | | |
| Start 12/18/2010 | | End 12/18/2010 | |
| CUST. REF. NO. | | | |
| Newfield | | | |
| CAPTION | | | |
| ARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF A | | | |
| SIZE | | | |
| 73 | | Lines | 2.00 COLUMN |
| TIMES | | RATE | |
| 4 | | | |
| MISC. CHARGES | | AD CHARGES | |
| | | | |
| | | TOTAL COST | |
| | | 250.28 | |

AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-370 IN THE MATTER OF THE APPLICA FOR DIV OF OIL-GAS & MINING, WAS PUBLISHED BY THE NEWSPAPER AGENCY CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH. NOTICE IS ALSO POSTED ON UTAHLEGALS.COM ON THE SAME DAY AS THE FIRST NEWSPAPER PUBLICATION DATE AND REMAINS ON UTAHLEGALS.COM INDEFINATELY.

Start 12/18/2010

End 12/18/2010

PUBLISHED ON

SIGNATURE

12/20/2010

Sandy Taylor

VIRGINIA CRAFT
Notary Public, State of Utah
Commission # 581489
My Commission Expires
January 12, 2014

Virginia Craft

THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"
PLEASE PAY FROM BILLING STATEMENT



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

March 7, 2011

Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

Subject: Greater Monument Butte Unit Well: Federal 6-33, Section 33, Township 8 South, Range 16 East, SLBM, Duchesne County, Utah, API Well # 43-013-30747

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Newfield Production Company.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.
4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Mark Reinbold at 801-538-5333 or Brad Hill at 801-538-5315.

Sincerely,


John Rogers
Associate Director

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
SITLA
Duchesne County
Newfield Production Company, Myton
Well File

N:\O&G Reviewed Docs\ChronFile\UIC





Cement Bond Tops FEDERAL 6-33-8-16

API #43-013-30747

UIC-370.4

Legend

Buffer_of_SGID93_ENERGY_DNROilGasWells_111

SGID93.ENERGY.DNROilGasWells

GIS_STAT_TYPE

○ APD

⊙ DRL

⊙ GIW

⊙_{GS} GSW

× LA

○ LOC

● OPS

⊙ PA

⊙ PGW

● POW

▲ RET

⊙ SGW

— SOW

⊙ TA

○ TW

⊙ WDW

▲ WIW

● WSW

• Wells-CbltopsMaster9_28_11

• SGID93.ENERGY.DNROilGasWells_HDBottom

— SGID93.ENERGY.DNROilGasWells_HDPath

0 0.4 Miles

1870calc = approx cement top calculated from well completion report

N



DIVISION OF OIL, GAS AND MINING
UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT
STATEMENT OF BASIS

Applicant: Newfield Production Company **Well:** Federal 6-33-8-16

Location: 33/8S/16E **API:** 43-013-30747

Ownership Issues: The proposed well is located on BLM land. The well is located in the Greater Monument Butte Unit. Lands in the one-half mile radius of the well are administered by the BLM and the State of Utah. The Federal Government and the State of Utah are the mineral owners within the area of review (AOR). Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and lease holders in the half-mile radius. Newfield is the operator of the Greater Monument Butte Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

Well Integrity: The proposed well has surface casing set at 280 feet and has a cement top at the surface. A 5½ inch production casing is set at 6,168 feet. A cement bond log demonstrates adequate bond in this well up to at least 4,000 feet (no cement bond log from 2100 to 4000 feet). A 2 7/8 inch tubing with a packer will be set at 4,455 feet. Higher perforations will be opened at a later date. A mechanical integrity test will be run on the well prior to injection. On the basis of surface locations, there are 7 producing wells, 1 shut-in well, and 4 injection wells in the AOR. One of the producing wells is directionally drilled, with a surface location inside the AOR, but the bottom hole location is outside the AOR. Additionally, there is 1 producing well which has been directionally drilled from a surface location outside the AOR to a bottom hole location inside the AOR. Finally, there is a permitted surface location slightly outside the AOR, from which a directional well will be drilled to a bottom hole location inside the AOR. All of the existing wells have evidence of adequate casing and cement.

Ground Water Protection: As interpreted from Technical Publication No. 92, the base of moderately saline water is at a depth of approximately 500 feet. Injection shall be limited to the interval between 4,287 feet and 6,122 feet in the Green River Formation. Information submitted by Newfield indicates that the fracture gradient for the 6-33-8-16 well is 0.67 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 1,167 psig. The requested maximum pressure is 1,167 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

Federal 6-33-8-16

page 2

Oil/Gas& Other Mineral Resources Protection: The Board of Oil, Gas & Mining approved the Greater Monument Butte Unit on December 1, 2009. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

Bonding: Bonded with the BLM

Actions Taken and Further Approvals Needed: A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Mark Reinbold

Date 3/7/2011, revised 11/1/2011

BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH
NOTICE OF AGENCY ACTION
CAUSE NO. UIC-370

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 33 AND 34, TOWNSHIP 8 SOUTH, RANGE 16 EAST, SECTION 15, TOWNSHIP 9 SOUTH, RANGE 15 EAST, AND SECTIONS 1, 3, AND 14, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

Federal 6-33 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East
Travis Federal 7-33-8-16 well located in SE/4 NW/4, Section 33, Township 8 South, Range 16 East
Monument Butte Federal 4-34(I) well located in NW/4 NW/4, Section 34, Township 8 South, Range 16 East
Ashley Federal 8-15-9-15 well located in SE/4 NE/4, Section 15, Township 9 South, Range 15 East
Monument Butte 1-43 well located in NE/4 SE/4, Section 1, Township 9 South, Range 16 East
Monument Butte 1-34 well located in SW/4 SE/4, Section 1, Township 9 South, Range 16 East
South Wells Draw 6-3-9-16 well located in SE/4 NW/4, Section 3, Township 9 South, Range 16 East
South Wells Draw Federal 10-3-9-16 well located in NW/4 SE/4, Section 3, Township 9 South, Range 16 East
Jonah Federal 10-14-9-16 well located in NW/4 SE/4, Section 14, Township 9 South, Range 16 East

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 13th day of December, 2010.

STATE OF UTAH
DIVISION OF OIL, GAS & MINING



Brad Hill
Permitting Manager

Newfield Production Company

**FEDERAL 6-33, TRAVIS FEDERAL 7-33-8-16,
MONUMENT BUTTE FEDERAL 4-34(I), ASHLEY FEDERAL 8-15-9-15,
MONUMENT BUTTE 1-43, MONUMENT BUTTE 1-34,
SOUTH WELLS DRAW 6-3-9-16, SOUTH WELLS DRAW FEDERAL 10-3-9-16,
JONAH FEDERAL 10-14-9-16.**

Cause No. UIC-370

Publication Notices were sent to the following:

Newfield Production Company
1001 17th Street, Suite 2000
Denver, CO 80202

Uintah Basin Standard
268 South 200 East
Roosevelt, UT 84066
via e-mail ubs@ubstandard.com

Salt Lake Tribune
P O Box 45838
Salt Lake City, UT 84145
via e-mail naclegal@mediaoneutah.com


Vernal Office
Bureau of Land Management
170 South 500 East
Vernal, UT 84078

Duchesne County Planning
P O Box 317
Duchesne, UT 84021-0317

Bruce Suchomel
US EPA Region 8
MS 8P-W-GW
1595 Wynkoop Street
Denver, CO 80202-1129

SITLA
675 East 500 South
Salt Lake City, UT 84102-2818

Newfield Production Company
Rt 3 Box 3630
Myton, UT 84052

A handwritten signature in black ink, appearing to read "Jean Sweet", is written over a horizontal line.

Jean Sweet - Re: Notice of Agency Action Newfield Cause UIC-370

From: Cindy Kleinfelter <classifieds@ubstandard.com>
To: Jean Sweet <jsweet@utah.gov>
Date: 12/15/2010 1:44 PM
Subject: Re: Notice of Agency Action Newfield Cause UIC-370

On 12/14/2010 12:43 PM, Jean Sweet wrote:

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining
PO Box 145801
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet, Executive Secretary
Utah Div. of Oil, Gas & Mining
1594 West Temple, Suite 1210
Salt Lake City, UT
801-538-5329
jsweet@utah.gov

This notice will be published Dec. 21. Thank you.
Cindy



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 14, 2010

Via e-mail: ubs@ubstandard.com

Uintah Basin Standard
268 South 200 East
Roosevelt, UT 84066

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-370

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining
PO Box 145801
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet
Executive Secretary

Enclosure



Jean Sweet - RE: Notice of Agency Action Newfield Cause UIC-370

From: "NAC Legal" <naclegal@mediaoneutah.com>
To: "Jean Sweet" <jsweet@utah.gov>
Date: 12/14/2010 2:43 PM
Subject: RE: Notice of Agency Action Newfield Cause UIC-370

Ad #647204 is scheduled to run December 18 in Salt Lake Tribune, Deseret News and Online utahlegals.com .

Total charge is \$250.28. Please check the ad in the papers.

Thank you,

Lynn Valdez

MediaOne of Utah,

a Newspaper Agency Company

4770 South 5600 West

West Valley City, Utah 84118

Ph.: 801-204-6245

Email: naclegal@mediaoneutah.com

From: Jean Sweet [mailto:jsweet@utah.gov]
Sent: Tuesday, December 14, 2010 12:46 PM
To: naclegal@mediaoneutah.com
Subject: Notice of Agency Action Newfield Cause UIC-370



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 14, 2010

VIA E-MAIL naclegal@mediaoneutah.com

Salt Lake Tribune
P. O. Box 45838
Salt Lake City, UT 84145

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-370

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing for **account #9001402352** to:


Division of Oil, Gas and Mining
PO Box 145801
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet
Executive Secretary

Enclosure



| | | |
|--|---|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-34173 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 6-33 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1982 FNL 1978 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 33 Township: 08.0S Range: 16.0E Meridian: S | | 9. API NUMBER: 43013307470000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| COUNTY: DUCHESNE | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/27/2011 | | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The subject well has been converted from a producing oil well to an injection well on 10/26/2011. On 10/27/2011 Dennis Ingram with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/27/2011 the casing was pressured up to 1010 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 100 psig during the test. There was not a State representative available to witness the test. | | |
| Accepted by the Utah Division of Oil, Gas and Mining | | Date: 11/01/2011 |
| By:  | | |
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician |
| SIGNATURE N/A | DATE 10/28/2011 | |

Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630

Myton, UT 84052

435-646-3721

Witness: _____ Date 10/27/11 Time 1:00 P am pmTest Conducted by: DAVE EDWARD

Others Present: _____

| | |
|---|--|
| Well: <u>FEDERAL 6-33-8-16</u> | Field: <u>FEDERAL 6-33-8-16</u> <u>Duchesne County Utah</u> |
| Well Location: <u>FEDERAL 6-33-8-16</u> | API No: <u>UTU 67538X</u> |
| <u>SE/NW SEC. 33, T8S, R16E</u> | <u>43-013-30747</u> |

| <u>Time</u> | <u>Casing Pressure</u> | |
|-------------|------------------------|------|
| 0 min | <u>1010</u> | psig |
| 5 | <u>1010</u> | psig |
| 10 | <u>1010</u> | psig |
| 15 | <u>1010</u> | psig |
| 20 | <u>1010</u> | psig |
| 25 | <u>1010</u> | psig |
| 30 min | <u>1010</u> | psig |
| 35 | | psig |
| 40 | | psig |
| 45 | | psig |
| 50 | | psig |
| 55 | | psig |
| 60 min | | psig |

Tubing pressure: 100 psig


Result:

Pass

Fail

Signature of Witness: _____

Signature of Person Conducting Test: David Edward



Daily Activity Report**Format For Sundry****FEDERAL 6-33-8-16****8/1/2011 To 12/30/2011****10/26/2011 Day: 1****Conversion**

NC #3 on 10/26/2011 - MIRUSU, LD rods, run gyro. - Pump 10 bbls water down tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. - Pump 10 bbls water down tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - Pump 10 bbls water down tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. - Pump 10 bbls water down tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - Pump 10 bbls water down

tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - Pump 10 bbls water down tbg & drop std valve. Pressure test tbg to 3000 psi w/ 25 bbls water for 1 hr. Good test. RU sandline to retrieve std valve. RD sandline. RD rig floor. ND BOP. Set Pkr w/ 15000 tension. Pump 60 bbls fresh water w/ pkr fluid down csg. Pressure test csg & Pkr to 1500 psi for 1 hr. Good test. RDMOSU. READY FOR MIT!! - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - ND wellhead. Release TA. RU rig floor. TOH breaking collars, & inspecting pins w/ 40- jts 2 7/8. Tbg became plugged while trying to flush. RU Perforators to perforate tbg. RD Perforators. Cont to break collars w/ 98- jts 2 7/8. LD w/ 40- jts 2 7/8, TA, 1- jt 2 7/8, SN, 1- jt 2 7/8, PBGA, 3- jts 2 7/8, BP. PU TIH w/ Arrowset Pkr, SN, 138- jts 2 7/8. SDFD. - Road rig to location. MIRUSU. Pump 60 bbls water down csg @ 250. RD pumping unit. Unseat rod pump. Flush tbg & rods w/ 40 bbls water @ 250. Softseat & pressure test tbg to 3000 psi w/ 20 bbls water. Good test. Unseat rod pump. TOH & LD w/ 222- 3/4 guided rods, 6- 1 1/2 wt bars, rod pump. Pump looked good. X- over to tbg eq. RU VES to run gyro survey. RD VES. SDFD. **Finalized**

Daily Cost: \$0**Cumulative Cost:** \$12,258**10/28/2011 Day: 4****Conversion**

Rigless on 10/28/2011 - Conduct an MIT - On 10/27/2011 Dennis Ingram with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/27/2011 the casing was pressured up to 1010 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 100 psig during the test. There was not a State representative available to witness the test. - On 10/27/2011 Dennis Ingram with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 10/27/2011 the casing was pressured up to 1010 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 100 psig during the test. There was not a State representative available to witness the test. **Finalized**

Daily Cost: \$0**Cumulative Cost:** \$78,046**Pertinent Files: Go to File List**

| | | | | | |
|---|---|---|---|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 | | | |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-34173 | | | |
| 1. TYPE OF WELL Water Injection Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | | | |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) | | | |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 6-33 | | | |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1982 FNL 1978 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 33 Township: 08.0S Range: 16.0E Meridian: S | | 9. API NUMBER: 43013307470000 | | | |
| 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE | | COUNTY: DUCHESNE | | | |
| STATE: UTAH | | | | | |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | | | | |
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/7/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date: | <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="Put On Injection"/> </td> </tr> </table> | | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="Put On Injection"/> |
| <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="Put On Injection"/> | | | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above reference well was put on injection at 12:30 PM on 12/07/2011. | | | | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY | | | | | |
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician | | | |
| SIGNATURE N/A | DATE 12/7/2011 | | | | |

Federal 6-33-8-16

Spud Date: 8/3/83
Put on Production: 9/7/83
GL: 5678' KB: 5688'

Injection Wellbore Diagram

Initial Production:
22 bopd, 3 bwpd

SURFACE CASING


CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (281')
DEPTH LANDED: 280'
HOLE SIZE: 12 1/4"
CEMENT DATA: 210 sxs Class "G" cmt.

PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 17.0#
LENGTH: 154 jts.
DEPTH LANDED: 6168'
HOLE SIZE: 7 7/8"
CEMENT DATA: 453 sk RFC & 155 sxs lodense.
CEMENT TOP AT: 1965'

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 138 jts (4461.4')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: 4439.4' KB
CE @ 4443.63'
TOTAL STRING LENGTH: EOT @ 4448'



FRAC JOB

| | | |
|------------|-----------|---|
| 8/25/83 | 5932'-60' | Frac as follows: 116,000# 20/40 sand in 631 bbls fluid. Perfs broke down @ 2600 psi. |
| | 5057'-66' | Frac as follows: 62,640# 20/40 sand in 460 bbls fluid. |
| 6/20/01 | 6010'-46' | Break CP-3 sands - no frac |
| 6/20/01 | 5652'-66' | Frac LODC sands as follows: 19,595# 20/40 sand in 233 bbls Viking I-25 fluid. Treated @ avg press of 5640 psi w/avg rate of 14.7 BPM. Screened out. |
| 6/21/01 | 5450'-58' | Frac A-1 sands as follows: 40,600# 20/40 sand in 256 bbls Viking I-25 fluid. Treated @ avg press of 3900 psi w/avg rate of 14.6 BPM. Screened out. |
| 6/22/01 | 5184'-94' | Frac C sands as follows: 37,413# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 3500 psi w/avg rate of 15.2 BPM, ISIP 3040 psi. |
| 6/25/01 | 4505'-55' | Frac GB sands as follows: 112,834# 20/40 sand in 236 bbls Viking I-25 fluid. Treated @ avg press of 2140 psi w/avg rate of 30.9 BPM, ISIP 2330 psi. |
| 9/29/01 | | Pump change. Update rod and tubing details. |
| 10/16/01 | | Tubing leak. Update rod and tubing details. |
| 10/29/01 | | Pump change. Update rod, tubing and fill details. |
| 11/21/01 | | Parted rods. Update rod and fill details. |
| 8/24/02 | | Pump change. Update rod and fill details |
| 12/03/03 | | Pump change. Update rod detail. |
| 3/19/04 | | Pump change and bail sand. Update rod and tubing detail. |
| 08/24/2004 | | Pump change. Updated rod detail. |
| 6/30/2010 | | Parted Rods. Update rod and tubing details. |
| 10/26/11 | | Convert to Injection Well |
| 10/27/11 | | Conversion MIT Finalized - update tbg detail |

PERFORATION RECORD

| | | | |
|---------|-------------|--------|----------|
| 8/25/83 | 5932'-5960' | 1 JSPF | 28 holes |
| ... | 5057'-5066' | 4 JSPF | 44 holes |
| 6/19/01 | 6040'-6066' | 4 JSPF | 24 holes |
| 6/19/01 | 6010'-6018' | 4 JSPF | 32 holes |
| 6/19/01 | 5652'-5666' | 4 JSPF | 56 holes |
| 6/19/01 | 5450'-5458' | 4 JSPF | 32 holes |
| 6/19/01 | 5184'-5194' | 4 JSPF | 40 holes |
| 6/19/01 | 4544'-4555' | 4 JSPF | 44 holes |
| 6/19/01 | 4505'-4519' | 4 JSPF | 56 holes |

NEWFIELD

Federal 6-33-8-16

1982' FNL & 1978' FWL
SE/NW Section 33-T8S-R16E
Duchesne Co, Utah

API #43-013-30747; Lease #UTU-34173



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

UNDERGROUND INJECTION CONTROL PERMIT


Cause No. UIC-370

Operator: Newfield Production Company
Well: Federal 6-33
Location: Section 33, Township 8 South, Range 16 East
County: Duchesne
API No.: 43-013-30747
Well Type: Enhanced Recovery (waterflood)

Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on March 7, 2011.
2. Maximum Allowable Injection Pressure: 1,167 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Green River Formation (4,287' – 6,122')
5. Any subsequent wells drilled within a ½ mile radius of this well shall have production casing cement brought up to or above the top of the unitized interval for the Greater Monument Butte Unit.

Approved by:


John Rogers
Associate Director

11-1-2011
Date


JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
SITLA
Eric Sundberg, Newfield Production Company, Denver
Newfield Production Company, Myton
Duchesne County
Well File


N:\O&G Reviewed Docs\ChronFile\UIC\Newfield

1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114 -5801
telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • www.ogm.utah.gov



| | | |
|---|---|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-34173 |
| 1. TYPE OF WELL Water Injection Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 6-33 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. API NUMBER: 43013307470000 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1982 FNL 1978 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 33 Township: 08.0S Range: 16.0E Meridian: S | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| COUNTY: DUCHESNE | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 11/29/2012 | <input type="checkbox"/> ALTER CASING | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CASING REPAIR | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input checked="" type="checkbox"/> OTHER | |
| | OTHER: <input type="text" value="Step Rate Test"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. A step rate test was conducted on the subject well on November 29, 2012. Results from the test indicate that the fracture gradient is 0.742 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed from 1167 psi to 1365 psi. | | |
| Accepted by the Utah Division of Oil, Gas and Mining Date: December 18, 2012 By:  | | |
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician |
| SIGNATURE N/A | | DATE 12/17/2012 |

**Federal 6-33-8-16
Greater Monument Butte Unit
Step Rate Test
November 29, 2012**



Start Pressure:

853 psi

Top Perforation:

4505 feet

Fracture pressure (Pfp):

1365 psi

FG:

0.742 psi/ft

| Step | Rate(bpd) | Pressure(psi) |
|------|-----------|---------------|
| 1 | 200 | 923 |
| 2 | 400 | 1013 |
| 3 | 600 | 1113 |
| 4 | 800 | 1211 |
| 5 | 1000 | 1322 |
| 6 | 1200 | 1388 |
| 7 | 1400 | 1426 |

Data Table Report

Report Name: PrTemp1000 Data Table
 Report Date: 11/29/2012 14:41:51
 File Name: C:\Program Files\PTC® Instruments 2.03.12\
 Federal 6-33-8-16 SRT (11-29-2012).csv
 Device: PrTemp1000 - Temperature and Pressure Recorder
 Hardware Revision: REV2C (64K)
 Serial Number: N87695
 Device ID: PrTemp
 Data Start Date: Nov 29, 2012 08:30:00 AM MST
 Data End Date: Nov 29, 2012 01:00:00 PM MST
 Reading: 1 to 55 of 55
 Reading Rate: 30 Seconds
 Last Calibration Date: Aug 28, 2012
 Next Calibration Date: Aug 28, 2013
 Next Calibration Date: Aug 28, 2013

Federal 6-33-8-16 SRT (11-29-2012)

| Unit Type | (All Units) | |
|-----------|--------------------------|-------------------|
| Reading | DateTime (MST) | Channel 2 PSIA |
| 1 | Nov 29, 2012 08:30:00 AM | 859.2 |
| 2 | Nov 29, 2012 08:35:00 AM | 857.2 |
| 3 | Nov 29, 2012 08:40:00 AM | 856.6 |
| 4 | Nov 29, 2012 08:45:00 AM | 855.6 |
| 5 | Nov 29, 2012 08:50:01 AM | 854.8 |
| 6 | Nov 29, 2012 08:55:00 AM | 854 |
| 7 | Nov 29, 2012 09:00:01 AM | 853.4 |
| 8 | Nov 29, 2012 09:05:00 AM | 879.6 |
| 9 | Nov 29, 2012 09:10:01 AM | 894 |
| 10 | Nov 29, 2012 09:15:00 AM | 903.6 |
| 11 | Nov 29, 2012 09:20:00 AM | 910.2 |
| 12 | Nov 29, 2012 09:25:00 AM | 917.4 |
| 13 | Nov 29, 2012 09:30:00 AM | 923 |
| 14 | Nov 29, 2012 09:35:01 AM | 956.8 |
| 15 | Nov 29, 2012 09:40:00 AM | 973.6 |
| 16 | Nov 29, 2012 09:45:01 AM | 985.4 |
| 17 | Nov 29, 2012 09:50:00 AM | 997 |
| 18 | Nov 29, 2012 09:55:01 AM | 1004.8 |
| 19 | Nov 29, 2012 10:00:00 AM | 1013.2 |
| 20 | Nov 29, 2012 10:05:00 AM | 1055.2 |
| 21 | Nov 29, 2012 10:10:00 AM | 1070.2 |
| 22 | Nov 29, 2012 10:15:00 AM | 1084.6 |
| 23 | Nov 29, 2012 10:20:01 AM | 1096.4 |
| 24 | Nov 29, 2012 10:25:00 AM | 1104.8 |
| 25 | Nov 29, 2012 10:30:01 AM | 1113.4 |
| 26 | Nov 29, 2012 10:35:00 AM | 1156.8 |
| 27 | Nov 29, 2012 10:40:01 AM | 1171.8 |
| 28 | Nov 29, 2012 10:45:00 AM | 1186.4 |
| 29 | Nov 29, 2012 10:50:00 AM | 1198.4 |
| 30 | Nov 29, 2012 10:55:00 AM | 1202.4 |
| 31 | Nov 29, 2012 11:00:00 AM | 1211.2 |
| 32 | Nov 29, 2012 11:05:01 AM | 1268 |
| 33 | Nov 29, 2012 11:10:00 AM | 1287.6 |
| 34 | Nov 29, 2012 11:15:01 AM | 1298.6 |
| 35 | Nov 29, 2012 11:20:00 AM | 1314.6 |
| 36 | Nov 29, 2012 11:25:01 AM | 1316.6 |
| 37 | Nov 29, 2012 11:30:00 AM | 1322.2 |
| 38 | Nov 29, 2012 11:35:00 AM | 1358.8 |

| Unit Type | (All Units) | |
|-----------|----------------|-------------------|
| Reading | DateTime (MST) | Channel 2 PSIA |

| | | |
|----|--------------------------|--------|
| 39 | Nov 29, 2012 11:40:00 AM | 1368 |
| 40 | Nov 29, 2012 11:45:00 AM | 1374.8 |
| 41 | Nov 29, 2012 11:50:01 AM | 1372.4 |
| 42 | Nov 29, 2012 11:55:00 AM | 1382.8 |
| 43 | Nov 29, 2012 12:00:01 PM | 1388 |
| 44 | Nov 29, 2012 12:05:00 PM | 1405 |
| 45 | Nov 29, 2012 12:10:01 PM | 1412.4 |
| 46 | Nov 29, 2012 12:15:00 PM | 1412.8 |
| 47 | Nov 29, 2012 12:20:00 PM | 1423.8 |
| 48 | Nov 29, 2012 12:25:00 PM | 1421.6 |
| 49 | Nov 29, 2012 12:30:00 PM | 1426.2 |
| 50 | Nov 29, 2012 12:35:01 PM | 1446.4 |
| 51 | Nov 29, 2012 12:40:00 PM | 1446.4 |
| 52 | Nov 29, 2012 12:45:01 PM | 1457 |
| 53 | Nov 29, 2012 12:50:00 PM | 1461.6 |
| 54 | Nov 29, 2012 12:55:01 PM | 1458.6 |
| 55 | Nov 29, 2012 01:00:00 PM | 1472.6 |

End of Report


Data Table Report

Report Name: PrTemp1000 Data Table
 Report Date: 11/29/2012 14:42:03
 File Name: C:\Program Files\PTC® Instruments 2.03.12\
 Federal 6-33-8-16 ISIP (11-29-2012).csv
 Device: PrTemp1000 - Temperature and Pressure Recorder
 Hardware Revision: REV2C (64K)
 Serial Number: N87695
 Device ID: PrTemp
 Data Start Date: Nov 29, 2012 01:00:21 PM MST
 Data End Date: Nov 29, 2012 01:30:21 PM MST
 Reading: 1 to 31 of 31
 Reading Rate: 30 Seconds
 Last Calibration Date: Aug 28, 2012
 Next Calibration Date: Aug 28, 2013
 Next Calibration Date: Aug 28, 2013

Federal 6-33-8-16 ISIP (11-29-2012)

| Unit Type | (All Units) | |
|-----------|--------------------------|-------------------|
| Reading | DateTime (MST) | Channel 2 PSIA |
| 1 | Nov 29, 2012 01:00:21 PM | 1470.4 |
| 2 | Nov 29, 2012 01:01:21 PM | 1364.4 |
| 3 | Nov 29, 2012 01:02:20 PM | 1355.2 |
| 4 | Nov 29, 2012 01:03:21 PM | 1346.6 |
| 5 | Nov 29, 2012 01:04:21 PM | 1339.8 |
| 6 | Nov 29, 2012 01:05:20 PM | 1333.2 |
| 7 | Nov 29, 2012 01:06:21 PM | 1327.6 |
| 8 | Nov 29, 2012 01:07:21 PM | 1322.6 |
| 9 | Nov 29, 2012 01:08:21 PM | 1317.4 |
| 10 | Nov 29, 2012 01:09:21 PM | 1313.2 |
| 11 | Nov 29, 2012 01:10:21 PM | 1308.6 |
| 12 | Nov 29, 2012 01:11:21 PM | 1305 |
| 13 | Nov 29, 2012 01:12:20 PM | 1300.6 |
| 14 | Nov 29, 2012 01:13:21 PM | 1296.6 |
| 15 | Nov 29, 2012 01:14:21 PM | 1293 |
| 16 | Nov 29, 2012 01:15:20 PM | 1289.6 |
| 17 | Nov 29, 2012 01:16:21 PM | 1286.4 |
| 18 | Nov 29, 2012 01:17:21 PM | 1283.2 |
| 19 | Nov 29, 2012 01:18:20 PM | 1280 |
| 20 | Nov 29, 2012 01:19:21 PM | 1277.8 |
| 21 | Nov 29, 2012 01:20:21 PM | 1273.8 |
| 22 | Nov 29, 2012 01:21:20 PM | 1271.8 |
| 23 | Nov 29, 2012 01:22:21 PM | 1268.6 |
| 24 | Nov 29, 2012 01:23:21 PM | 1266.2 |
| 25 | Nov 29, 2012 01:24:21 PM | 1263.6 |
| 26 | Nov 29, 2012 01:25:21 PM | 1261.2 |
| 27 | Nov 29, 2012 01:26:21 PM | 1258.8 |
| 28 | Nov 29, 2012 01:27:21 PM | 1256.2 |
| 29 | Nov 29, 2012 01:28:20 PM | 1254.4 |
| 30 | Nov 29, 2012 01:29:21 PM | 1252.2 |
| 31 | Nov 29, 2012 01:30:21 PM | 1249.4 |

End of Report



| | | |
|--|---|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: U-34173 |
| 1. TYPE OF WELL Water Injection Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 6-33 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1982 FNL 1978 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 33 Township: 08.0S Range: 16.0E Meridian: S | | 9. API NUMBER: 43013307470000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| COUNTY: DUCHESNE | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/22/2016 | <input type="checkbox"/> ALTER CASING | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CASING REPAIR | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input checked="" type="checkbox"/> OTHER | |
| | OTHER: <input type="text" value="5 YR MIT"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 09/19/2016 Amy Doebele with the State of Utah DOGM was contacted concerning the 5 Year MIT on the above listed well. On 09/22/2016 the casing was pressured up to 1190 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 310 psig during the test. There was a State representative available to witness the test - Amy Doebele. | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 27, 2016 | | |
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician |
| SIGNATURE N/A | DATE 9/26/2016 | |

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630
Myton, UT 84052
435-646-3721

Witness: Amy Deebale Date 9/22/16 Time 10:05 am pm
Test Conducted by: Troy Lazenby
Others Present: _____

Well: Federal 6-33-8-16

Field: Monument Butte

Well Location: SE/SW Sec. 33, T8S, R1E
Duchesne County, Utah

API No: 43-013-30747

| <u>Time</u> | <u>Casing Pressure</u> | |
|-----------------------------|------------------------|------|
| 0 min | <u>1240</u> | psig |
| 5 | <u>1240</u> | psig |
| 10 | <u>1230</u> | psig |
| 15 | <u>1220</u> | psig |
| 20 | <u>1210</u> | psig |
| 25 | <u>1190</u> | psig |
| 30 min | | psig |
| 35 | | psig |
| 40 | | psig |
| 45 | | psig |
| 50 | | psig |
| 55 | | psig |
| 60 min | | psig |
| Tubing pressure: <u>310</u> | | psig |

Identified leaking
valve on back side
of casing valve causing
steady decrease in
pressure. Recharged
annulus and identify
leak in same area
of valve. No other
issues witnessed.
Test successful,
Operator to swap out
valves and monitor
build up of pressure
in annulus.

Qd 9/22/16

Result: Pass Fail

Signature of Witness: _____

Signature of Person Conducting Test: _____

Sundry Number: 74650 API Well Number: 43013307470000

